

LOAN DOCUMENT

		PHOTOGRAPH THIS SHEET		INVENTORY ①
		LEVEL		
DTIC ACCESSION NUMBER	Bioventing Pilot Test Work Plan for DOCUMENT IDENTIFICATION mar 94			
	DISTRIBUTION STATEMENT A Approved for Public Release Distribution Unlimited			
ACCESSION DATA		DISTRIBUTION STATEMENT		
NTIS <input type="checkbox"/> GRAM <input type="checkbox"/>				
DTIC <input type="checkbox"/> TRAC <input type="checkbox"/>				
UNANNOUNCED <input type="checkbox"/>				
JUSTIFICATION <input type="checkbox"/>				
BY		DATE ACCESSIONED		
DISTRIBUTION/				
AVAILABILITY CODES				
DISTRIBUTION		DATE RETURNED		
AVAILABILITY AND/OR SPECIAL				
A-1		REGISTERED OR CERTIFIED NUMBER		
DISTRIBUTION STAMP				
DATE RECEIVED IN DTIC				
PHOTOGRAPH THIS SHEET AND RETURN TO DTIC-FDAC				

H
A
N
D
L
E

W
I
T
H

C
A
R
E

DRAFT

**Bioventing Pilot Test Work Plan for
Sites 27, 28, and 44
Nellis AFB, Nevada**

PART II

**Draft Interim Pilot Test Results Report for
Sites 27, 28, and 44
Nellis AFB, Nevada**

Prepared For

**Air Force Center for Environmental Excellence
Brooks AFB, Texas**

and

**USAFWTC/EVR
Nellis AFB, Nevada**

ES

Engineering-Science, Inc.

March 1994

**1700 BROADWAY, SUITE 900
DENVER, COLORADO 80290**

ENGINEERING-SCIENCE

AQM01-03-0429

**DEFENSE TECHNICAL INFORMATION CENTER
REQUEST FOR SCIENTIFIC AND TECHNICAL REPORTS**

Title

AFCEE Collection**1. Report Availability (Please check one box)**

- ☒ This report is available. Complete sections 2a - 2f.
☐ This report is not available. Complete section 3.

**2a. Number of
Copies Forwarded**1 each**2b. Forwarding Date**July/2000**2c. Distribution Statement (Please check ONE box)**

DoD Directive 5230.24, "Distribution Statements on Technical Documents," 18 Mar 87, contains seven distribution statements, as described briefly below. Technical documents **MUST** be assigned a distribution statement.

- ☒ DISTRIBUTION STATEMENT A: Approved for public release. Distribution is unlimited.
- ☐ DISTRIBUTION STATEMENT B: Distribution authorized to U.S. Government Agencies only.
- ☐ DISTRIBUTION STATEMENT C: Distribution authorized to U.S. Government Agencies and their contractors.
- ☐ DISTRIBUTION STATEMENT D: Distribution authorized to U.S. Department of Defense (DoD) and U.S. DoD contractors only.
- ☐ DISTRIBUTION STATEMENT E: Distribution authorized to U.S. Department of Defense (DoD) components only.
- ☐ DISTRIBUTION STATEMENT F: Further dissemination only as directed by the controlling DoD office indicated below or by higher authority.
- ☐ DISTRIBUTION STATEMENT X: Distribution authorized to U.S. Government agencies and private individuals or enterprises eligible to obtain export-controlled technical data in accordance with DoD Directive 5230.25, Withholding of Unclassified Technical Data from Public Disclosure, 6 Nov 84.

2d. Reason For the Above Distribution Statement (in accordance with DoD Directive 5230.24)**2e. Controlling Office**HQ AFCEE**2f. Date of Distribution Statement
Determination**15 Nov 2000**3. This report is NOT forwarded for the following reasons. (Please check appropriate box)**

- ☐ It was previously forwarded to DTIC on _____ (date) and the AD number is _____
- ☐ It will be published at a later date. Enter approximate date if known. _____
- ☐ In accordance with the provisions of DoD Directive 3200.12, the requested document is not supplied because: _____

Print or Type Name

Laura Peña

Telephone

210-536-1431

Signature

Laura Peña

(For DTIC Use Only)

AQ Number M01-03-0429

PART I
BIOVENTING PILOT TEST WORK PLAN FOR
SITES 27, 28, AND 44

NELLIS AFB, NEVADA

March 1994

Prepared for:

Air Force Center for Environmental Excellence
Brooks AFB, Texas

and

USAFWTC/EVR
Nellis AFB, Nevada

Prepared by:

Engineering-Science, Inc.
1700 Broadway, Suite 900
Denver, Colorado 80290

CONTENTS

PART I - BIOVENTING PILOT TEST WORK PLAN FOR SITES 27, 28, AND 44 NELLIS AFB, NEVADA

	<u>Page</u>
1.0 Introduction	I-1
2.0 Site Descriptions	I-2
2.1 Site 27	I-2
2.1.1 Site History and Location.....	I-2
2.1.2 Site Geology	I-2
2.1.3 Site Contaminants.....	I-2
2.2 Site 28	I-5
2.2.1 Site History and Location.....	I-5
2.2.2 Site Geology	I-5
2.2.3 Site Contaminants.....	I-5
2.3 Site 44	I-7
2.3.1 Site History and Location.....	I-7
2.3.2 Site Geology	I-7
2.3.3 Site Contaminants.....	I-7
3.0 Pilot Test Activities	I-7
3.1 Bioventing Test Design for Site 27.....	I-9
3.2 Bioventing Test Design for Site 28.....	I-13
3.3 Bioventing Test Design for Site 44.....	I-13
3.4 Background Well.....	I-18
3.5 Handling of Drill Cuttings.....	I-18
3.6 Soil and Soil Gas Sampling.....	I-21
3.6.1 Soil Samples	I-21
3.6.2 Soil Gas Samples.....	I-21
3.7 Blower Systems	I-21
3.8 <i>In Situ</i> Respiration Tests	I-23
3.9 Air Permeability Tests	I-23
3.10 Potential For Air Emissions	I-23
3.11 Extended Pilot Test Bioventing System.....	I-23
4.0 Exceptions to Protocol Procedures	I-24
5.0 Base Support Requirements	I-24
6.0 Project Schedule	I-25
7.0 Points of Contact.....	I-25
8.0 References	I-26

FIGURES

<u>No.</u>	<u>Title</u>	<u>Page</u>
2.1	Site 27, 28, and 44 Locations in Relation to the Base	I-3
2.2	Site Layout, Site 27	I-4
2.3	Site Layout, Site 28	I-6
2.4	Site Layout, Site 44	I-8
3.1	Proposed Vent Well/Monitoring Point Locations, Site 27	I-10
3.2	Proposed Injection Vent Well Construction Detail, Site 27	I-11
3.3	Proposed Monitoring Point Construction Detail, Site 27	I-12
3.4	Proposed Vent Well/Monitoring Point Locations, Site 28	I-14
3.5	Proposed Injection Vent Well Construction Detail, Site 28	I-15
3.6	Proposed Monitoring Point Construction Detail, Site 28	I-16
3.7	Proposed Vent Well/Monitoring Point Locations, Site 44	I-17
3.8	Proposed Injection Vent Well Construction Detail, Site 44	I-19
3.9	Proposed Monitoring Point Construction Detail, Site 44	I-20
3.10	Blower System Instrumentation Diagram for Air Injection	I-22

PART I

**BIOVENTING PILOT TEST WORK PLAN FOR
SITES 27, 28, AND 44
NELLIS AFB, NEVADA**

1.0 INTRODUCTION

This work plan presents the scope of multiphase bioventing pilot tests for *in situ* treatment of fuel-contaminated soils at Sites 27, 28, and 44 at Nellis Air Force Base (AFB), Nevada. The pilot tests will be performed by Engineering-Science, Inc. (ES). The three primary objectives of the proposed pilot tests are: 1) to assess the potential for supplying oxygen throughout the contaminated soil interval, 2) to determine the rate at which indigenous microorganisms will degrade fuel when supplied with oxygen-rich soil gas, and 3) to evaluate the potential for sustaining these rates of biodegradation until fuel contamination is remediated to concentrations below regulatory standards.

The pilot tests will be conducted in two phases. A vent well (VW) and vapor monitoring points (MPs) will be installed during site investigation activities. The initial test phase at each site will also include an *in situ* respiration test, an air permeability test, and installation of a blower system for air injection. This initial testing is expected to take approximately 3 weeks. If the initial phase is successful, the second phase will begin immediately. During the second phase, the bioventing systems will be operated and monitored over a 1-year period.

If bioventing proves to be an effective means of remediating soil contamination at these sites, pilot test data may be used to design full-scale remediation systems and to estimate the time required for site cleanup. An added benefit of the pilot testing at the sites is that a significant amount of the fuel contamination should be biodegraded during the 1-year pilot test, as the testing will take place within the most contaminated soils at the sites. Additional background information on the development and recent success of the bioventing technology is found in the document entitled *Test Plan and Technical Protocol for a Field Treatability Test for Bioventing* (Hinchee et al., 1992). This protocol document will serve as the primary reference for pilot test well designs and the detailed procedures to be used during the test.

2.0 SITE DESCRIPTIONS

2.1 Site 27

2.1.1 Site History and Location

Site 27 is located at Facility 1014 northwest of Las Vegas Boulevard (Figure 2.1). The pilot test area is just to the southwest of the boundary fence for the fuel yard (Figure 2.2). Site 27 is the location of a reported leak from a waste petroleum, oils, and lubricants (POL) tank. Four 20,000-gallon underground storage tanks (USTs) were located at the facility. The tanks, installed in 1942 and removed in 1989, were used to store heating oil until 1974, when they were converted to store waste POL. The leak, reported in 1981, was discovered in the southernmost UST. At that time it was estimated that the tank was releasing approximately 50 gallons of waste POL and solvents per month. It is not known how long the leak existed prior to its discovery. The tanks stopped receiving POL immediately upon discovery of the leak. The site was officially closed in April 1988, and the tanks were removed in June 1989. Soil samples taken during the excavation of the tanks had concentrations of total recoverable petroleum hydrocarbons (TRPH) of up to 14,000 milligrams per kilogram (mg/kg).

Since removal of the tanks, two additional potential sources of contamination have been discovered. During leak testing at the base, Tracer Research Corporation (TRC) injected a halon tracer into a pipeline that connects aboveground storage tanks (ASTs) located in the fuel yard just to the northeast of the pilot test site. Two leaks were discovered, one in an aboveground valve "Christmas tree" and another in the bottom of AST number 1054. The leaks were repaired in the spring and summer of 1992, respectively. Both the tree and the tank are still active. The leaks appear to be the primary source of a free-phase petroleum product plume beneath Site 27 (Radian Corporation, 1993a).

2.1.2 Site Geology

Because the bioventing technology is applied to the unsaturated soils, this section primarily addresses soils above the shallow aquifer. Nellis AFB is located in an area predominated by valley fill alluvium to depths of several thousand feet. The alluvium typically consists of silt, clay, fine sand, and some lenses of pebble conglomerate. Near-surface lithology at Site 27 consists of fine-grained sediments, with sands and clays being most common. Lenses of caliche are common throughout the entire soil profile.

The inferred potentiometric gradient suggests that groundwater flow direction is to the east on the northern portion of the site and gradually shifts to the southeast on the southern portion of the site. Groundwater occurs at depths ranging from 70 to 86 feet below ground surface (bgs). On the basis of groundwater level monitoring results from several sampling events, flow direction and gradient fluctuate slightly throughout the year (Radian Corporation, 1993a).

2.1.3 Site Contaminants

Since the removal of the USTs, extensive groundwater and soil sampling has been performed at the site by several consultants. A total of 45 groundwater monitoring wells have been installed in and around Site 27. Free product thickness of up to 8 feet was evident in 12 of the wells during sampling performed in December 1992 (Radian




FIGURE 2.1

SITES 27, 28, AND 44
LOCATIONS IN RELATION
TO THE BASE

NELLIS AFB, NEVADA

ENGINEERING-SCIENCE, INC.
Denver, Colorado

**SUNRISE MANOR
UNINCORPORATED AREA**

NELLIS
AIR
BASE


ST.
ST.

RISTY LN.

TY LN.

LN.

**MANOR
TOWN**



- LEGEND**
- EW-03 • PRODUCT RECOVERY WELL
 - CHAINLINK FENCE
 - MW-24 ⊕ MONITORING WELL

FIGURE 2.2

**SITE LAYOUT
SITE 27**

NELLIS AFB, NEVADA

ENGINEERING-SCIENCE, INC.

Denver, Colorado




FIGURE 2.3

SITE LAYOUT SITE 28

NELLIS AFB, NEVADA

ENGINEERING-SCIENCE, INC.
Denver, Colorado

LEGEND

- EW-36 ● PRODUCT RECOVERY WELL
- MW-74 ● GROUNDWATER MONITORING WELL
- TB-9 ○ SOIL BORING

nondetect levels to 11,000 µg/L at well MW-79, located on the apron to the east of the site (Radian Corporation, 1993b).

Soil headspace field screening and soil data collected during the installation of a monitoring well and two borings immediately to the north of the pilot test area suggest that contamination starts approximately 15 feet bgs and extends to the groundwater surface at approximately 50 feet bgs. Analytical soil samples contained TRPH concentrations of up to 24,000 mg/kg (Radian Corporation, 1993c).

2.3 Site 44

2.3.1 Site History and Location

Site 44 is the site of a petroleum hydrocarbon leak southwest of the aerospace ground equipment (AGE) shop. The AGE shop, Building 270, is located along the flight line off Tyndall Drive (Figures 2.1 and 2.4). A site investigation performed in October 1991 identified a plume of petroleum contamination extending southwest of Building 270. Three USTs were removed from a service island at the AGE shop in 1989 (Figure 2.4). At the time of the tank removal, a soil investigation was performed. Soil borings advanced to depths of 40 to 50 feet bgs in the vicinity of the tanks had elevated levels of TRPH (ES, 1993).

2.3.2 Site Geology

The geology of Site 44 is similar to that of Site 27 (Section 2.1.2), with slightly more sand in the sediment than Site 27. The inferred potentiometric gradient suggests that groundwater flow direction is to the east on the northwestern portion of the site and gradually shifts to the southeast on the southern and eastern portion of the site. Groundwater occurs at depths ranging from 32 to 35 feet below ground surface (bgs). On the basis of groundwater level monitoring results from several sampling events, flow direction and gradient fluctuate slightly throughout the year (ES, 1993).

2.3.3 Site Contaminants

Since the discovery of contamination at Site 44, extensive groundwater and soil monitoring has been performed at the site by a consultant. A total of 19 groundwater monitoring wells have been installed in and around Site 44. Free product has been observed in well MW-5 during recent sampling events. Sampling results from the site indicate that BTEX compounds are the primary contaminants at the site. BTEX concentrations in soil ranged from nondetect levels to 205 mg/kg at monitoring well MW-5. TRPH concentrations in samples taken from the borings ranged from 10 mg/kg to 5,400 mg/kg at MW-5. The majority of the contamination at MW-5 was found immediately below the former location of the AGE USTs at approximately 22 feet bgs (ES, 1992a and 1993).

3.0 PILOT TEST ACTIVITIES

The purpose of this section is to describe the pilot test activities to take place at Sites 27, 28, and 44. The proposed locations and construction details for the central VWs and vapor MPs are discussed. Criteria for locating a suitable background well position are outlined. Soil and soil gas sampling procedures and the blower configuration that will be used to

270

AGE Service Area

SB-1

TO FLIGHT LINE

MW-11

MW-4

264

MW-5

MW-9

LEGEND






-  Former AGE UST Pit
-  Fence
-  Building Number
-  SB-1 Soil Boring
-  MW-2 Monitoring Well



FIGURE 2.4

SITE LAYOUT SITE 44

NELLIS AFB, NEVADA

ENGINEERING-SCIENCE, INC.

Denver, Colorado

inject air (oxygen) into contaminated soils are also discussed in this section. Finally, a brief description of the pilot test procedures is provided.

The bioventing technology is intended to remediate contamination only in the unsaturated zone. Therefore, pilot test activities will be confined mainly to unsaturated soils. The central VWs may be completed below the anticipated groundwater level. This is to provide oxygen to the deepest levels of the unsaturated zone in the event of natural groundwater table fluctuation and/or water table drawdown during future free product removal. No dewatering will take place during the pilot tests.

Existing monitoring wells will not be used as primary air injection wells. However, monitoring wells that have a portion of their screened interval above the water table may be used as vapor MPs or to measure the composition of background soil gas.


3.1 Bioventing Test Design for Site 27

A general description of criteria for siting a central VW and vapor MPs is included in the protocol document (Hinchee et al., 1992). Figure 3.1 illustrates the proposed locations of the central VW and MPs at Site 27. The final locations of these wells may vary slightly from the proposed locations if significant fuel contamination is not observed in the boring for the central VW. Soils in this area are expected to be contaminated with petroleum hydrocarbons and to be oxygen depleted ($<2\%$). Biological activity should be stimulated by oxygen-rich soil gas ventilation during pilot test operations.

Due to the relatively deep contamination at this site and the potential for highly permeable soils, the potential radius of venting influence around the central VW is expected to be 40 to 50 feet. Three vapor MPs (MPA, MPB, and MPC) will be located within a 50-foot radius of the central VW.

The VW will be constructed of 4-inch-diameter Schedule 40 polyvinyl chloride (PVC) casing, with a 30-foot interval of 0.04-inch slotted screen set at 40 to 70 feet bgs. Flush-threaded PVC casing and screen with no organic solvents or glues will be used. The filter pack will be clean, well-rounded silica sand with a 6-9 grain size and will be placed in the annular space to 1 foot above the screened interval. A 35-foot layer of bentonite will be placed directly over the filter pack. The first 12 inches of bentonite will consist of bentonite pellets hydrated in place in 6-inch lifts with potable water. This layer of pellets will prevent the addition of bentonite slurry from saturating the filter pack. The remaining 34 feet of bentonite will be fully hydrated and mixed aboveground, and the slurry will be tremmied into the annular space to produce an air-tight seal above the screened interval. The borehole will then be completed to the ground surface with a bentonite/cement grout. A complete seal is critical to prevent injected air from short-circuiting to the surface during the bioventing test. Figure 3.2 illustrates the proposed central VW construction detail for this site.

A typical multidepth vapor MP installation for this site is shown in Figure 3.3. Soil gas oxygen and carbon dioxide concentrations will be monitored at depths of 40, 55, and 65 feet bgs at each location. Multidepth monitoring will confirm that the entire soil profile is receiving oxygen and will be used to measure fuel biodegradation rates at three depths. The annular spaces between the three screened MP intervals will be sealed with bentonite to isolate the monitoring intervals. As with the central VW, several inches of bentonite



- LEGEND**
- EW-03 ● PRODUCT RECOVERY WELL
- CHAINLINK FENCE
- MW-24 ⊕ MONITORING WELL
- MPA ⊕ PROPOSED MONITORING POINT
- VW ▲ VENT WELL



FIGURE 3.1

**PROPOSED VENT WELL
AND MONITORING POINT
LOCATIONS
SITE 27**


NELLIS AFB, NEVADA

ENGINEERING-SCIENCE, INC.

Denver, Colorado

2" DIAMETER SCH 40
PVC HEADER SLOPED
TO WELL

TO BLOWER



NOT TO SCALE


FIGURE 3.2

**PROPOSED INJECTION
VENT WELL
CONSTRUCTION DETAIL
SITE 27**

NELLIS AFB, NEVADA

ENGINEERING-SCIENCE, INC.

Denver, Colorado



NOT TO SCALE

FIGURE 3.3
PROPOSED TYPICAL
MONITORING POINT
CONSTRUCTION DETAIL
SITE 27

NELLIS AFB, NEVADA

ENGINEERING-SCIENCE, INC.

Denver, Colorado

pellets will be used to shield the filter pack from rapid infiltration of bentonite slurry additions. Thermocouples will be installed at the shallowest and deepest depths at MPA to measure soil temperature. Additional details on VW and MP construction are presented in Section 4 of the protocol document (Hinchee et al., 1992).

3.2 Bioventing Test Design for Site 28

Figure 3.4 illustrates the proposed locations of the central VW and MPs at Site 28. The final location of these wells may vary slightly from the proposed location if significant fuel contamination is not observed in the boring for the central VW. Soils in this area are expected to be contaminated with petroleum hydrocarbons and to be oxygen depleted (<2%). Biological activity should be stimulated by oxygen-rich soil gas ventilation during pilot test operations.


Due to the relatively deep contamination at this site and the potential for highly permeable soils, the potential radius of venting influence around the central VW is expected to be 50 to 60 feet. Three vapor MPs (MPA, MPB, and MPC) will be located within a 60-foot radius of the central VW.

The VW will be constructed of 4-inch-diameter Schedule 40 PVC, with a 35-foot interval of 0.04-inch slotted screen set at 15 to 50 feet bgs. Flush-threaded PVC casing and screen with no organic solvents or glues will be used. The filter pack will be clean, well-rounded silica sand with a 6-9 grain size and will be placed in the annular space to 1 foot above the screened interval. A 12-foot layer of bentonite will be placed directly over the filter pack. The first 12 inches of bentonite will consist of bentonite pellets hydrated in place in 6-inch lifts with potable water. This layer of pellets will prevent the rapid addition of bentonite slurry from saturating the upper portion of the filter pack. The remaining 11 feet of bentonite will be fully hydrated and mixed aboveground, and then tremmied into the annular space to produce an air-tight seal above the screened interval that will prevent injected air from short-circuiting to the surface during the bioventing test. The well will be completed to the ground surface with a bentonite/cement grout. Figure 3.5 illustrates the proposed central VW construction for this site.

A typical multidepth vapor MP installation design for this site is shown in Figure 3.6. Soil gas oxygen and carbon dioxide concentrations will be monitored at depths of 20, 32, and 45 feet bgs at each location. Multidepth monitoring will confirm that the entire soil profile is receiving oxygen, and will be used to measure fuel biodegradation rates at each depth. The annular spaces between the three monitoring intervals in each MP will be sealed with bentonite to isolate the intervals. As in the central VW, several inches of bentonite pellets will be used to shield the filter pack from rapid infiltration of bentonite slurry additions. Thermocouples will be installed at the shallowest and deepest depths at MPA to measure soil temperature. Additional details on VW and MP construction are provided in Section 4 of the protocol document (Hinchee et al., 1992).


3.3 Bioventing Test Design for Site 44

Figure 3.7 illustrates the proposed locations of the central VW and MPs at Site 44. The final location of these wells may vary slightly from the proposed location if significant fuel contamination is not observed in the boring for the central VW. Soils in this area are expected to be contaminated with petroleum hydrocarbons and to be oxygen depleted



2" DIAMETER SCH 40
PVC HEADER SLOPED
TO WELL

TO BLOWER



NOT TO SCALE


FIGURE 3.5

**PROPOSED INJECTION
VENT WELL
CONSTRUCTION DETAIL
SITE 28**

NELLIS AFB, NEVADA

ENGINEERING-SCIENCE, INC.

Denver, Colorado




NOT TO SCALE

FIGURE 3.6
PROPOSED TYPICAL
MONITORING POINT
CONSTRUCTION DETAIL
SITE 28

NELLIS AFB, NEVADA

ENGINEERING-SCIENCE, INC.

Denver, Colorado



(<2%). Biological activity should be stimulated by oxygen-rich soil gas ventilation during pilot test operations.

Due to the shallower depth of contamination at this site and the potential for highly permeable soils, the potential radius of venting influence around the central VW is expected to be 25 to 35 feet. Three vapor MPs (MPA, MPB, and MPC) will be located within a 35-foot radius of the central VW.

The VW will be constructed of 4-inch-diameter Schedule 40 PVC, with a 15-foot interval of 0.04-inch slotted screen set at 18 to 43 feet bgs. Flush-threaded PVC casing and screen with no organic solvents or glues will be used. The filter pack will be clean, well-rounded silica sand with a 6-9 grain size and will be placed in the annular space to one foot above the screened interval. A 15-foot layer of bentonite will be placed directly over the filter pack. The first 12 inches of bentonite will consist of bentonite pellets hydrated in place in 6-inch lifts with potable water. This layer of pellets will prevent the rapid addition of bentonite slurry from saturating the upper portion of the filter pack. The remaining 14 feet of bentonite will be fully hydrated and mixed aboveground, and then tremmed into the annular space to produce an air-tight seal above the screened interval that will prevent injected air from short-circuiting to the surface during the bioventing test. The well will be completed to the ground surface with a bentonite/cement grout. Figure 3.8 illustrates the proposed central VW construction for this site.

A typical multi-depth vapor MP installation design for this site is shown in Figure 3.9. Soil gas oxygen and carbon dioxide concentrations will be monitored at depths of 20, 30, and 40-feet bgs at each location. Multi-depth monitoring will confirm that the entire soil profile is receiving oxygen, and will be used to measure fuel biodegradation rates at each depth. The annular spaces between the three monitoring intervals in each MP will be sealed with bentonite to isolate the intervals. As in the central VW, several inches of bentonite pellets will be used to shield the filter pack from rapid infiltration of bentonite slurry additions. Thermocouples will be installed at the shallowest and deepest depths at MPA to measure soil temperature. Additional details on VW and MP construction are provided in Section 4 of the protocol document (Hinchee et al., 1992).

3.4 Background Well

The construction of an additional vapor MP may be required to measure background levels of oxygen and carbon dioxide and to determine if natural carbon sources are contributing to oxygen uptake during the *in situ* respiration test described in Section 3.7. This background well would be installed in an area of uncontaminated soil and in the same stratigraphic formation as the VWs and MPs to be installed at Sites 27, 28, and 44. The background well would be similar in construction to the MPs (Figures 3.3, 3.6, and 3.9), and would be screened at three depths. ES will require assistance from Nellis AFB in selecting an appropriate location for the proposed background well.

3.5 Handling of Drill Cuttings

Drill cuttings from all VW and MP borings will be collected in US Department of Transportation (DOT) approved containers. The containers will be labeled and placed in the Nellis AFB hazardous materials storage area. These drill cuttings will become the responsibility of Nellis AFB, and will be analyzed, handled, and disposed of in accordance

2" DIAMETER SCH 40
PVC HEADER SLOPED
TO WELL

TO BLOWER





FIGURE 3.8

**PROPOSED INJECTION
VENT WELL
CONSTRUCTION DETAIL
SITE 44**

NELLIS AFB, NEVADA

ENGINEERING-SCIENCE, INC.

Denver, Colorado



NOT TO SCALE

FIGURE 3.9
PROPOSED TYPICAL
MONITORING POINT
CONSTRUCTION DETAIL
SITE 44

NELLIS AFB, NEVADA

ENGINEERING-SCIENCE, INC.

Denver, Colorado

with the current procedures for ongoing remedial investigations. This project is expected to generate approximately 20 55-gallon drums of cuttings.

3.6 Soil and Soil Gas Sampling

3.6.1 Soil Samples

Three soil samples will be collected from each pilot test area during the installation of the VW and MPs. Sampling procedures will follow those outlined in the protocol document. One sample will be collected from the most contaminated interval of each VW boring, and one sample will be collected from the interval of highest apparent contamination in each of the borings for the two MPs closest to the VW. Soil samples will be analyzed for TRPH, BTEX, soil moisture, pH, particle sizing, alkalinity, total iron, and nutrients. One sample will be collected from the background MP boring and analyzed for total Kjeldahl nitrogen (TKN).

Samples for TRPH and BTEX analysis will be collected using a split-spoon sampler containing brass tube liners. Soil samples collected in the brass tubes for TRPH and BTEX analyses will be immediately trimmed, and the ends will be sealed with aluminum foil or Teflon[®] fabric held in place by plastic caps. Soil samples collected for physical parameter analyses will be placed in glass sample jars or other appropriate sample containers specified in the base sample handling plan. Soil samples will be labeled following the nomenclature specified in the protocol document (Section 5), wrapped in plastic, and placed in a cooler for shipment. A chain-of-custody form will be filled out, and the cooler will be shipped to the Pace, Inc. laboratory in Huntington Beach, California, for analysis. This laboratory has been audited by the Air Force and meets all quality assurance/quality control and certification requirements for the State of California.


3.6.2 Soil Gas Samples

A total hydrocarbon vapor analyzer will be used during auguring to screen split-spoon soil samples for intervals of fuel contamination. Initial and final soil gas samples will be collected in SUMMA[®] canisters, in accordance with the bioventing field sampling plan (ES, 1992b), from the VWs and from the MPs closest to and furthest from the VWs. Additionally, these soil gas samples will be used to predict potential air emissions, to determine the reduction in BTEX and total volatile hydrocarbons (TVH) during the 1-year test, and to detect any migration of these vapors from the source area.

Soil gas sample canisters will be placed in a small cooler and packed with foam pellets to prevent excessive movement during shipment. Samples will not be sent on ice in order to prevent condensation of hydrocarbons. A chain-of-custody form will be filled out, and the cooler will be shipped to the Air Toxics, Inc. laboratory in Folsom, California for analysis.

3.7 Blower Systems

A 3-horsepower positive-displacement blower capable of injecting air at a flow rate of 20 to 40 standard cubic feet per minute (scfm) at a pressure of 8 pounds per square inch (psi) will be used to conduct the initial air permeability tests at each site. Figure 3.10 is a schematic of a typical air injection system used for pilot testing. The maximum power requirement anticipated for these pilot tests is 230-volt, single-phase, 30-amp service. Additional



LEGEND

- VI 1 VACUUM INDICATOR
- PI 1 PRESSURE INDICATOR
- TI 1 TEMPERATURE INDICATOR
- AV AIR VELOCITY INDICATOR
- FCV FLOW CONTROL VALVE
- PRV PRESSURE RELIEF VALVE

FIGURE 3.10

PROPOSED BLOWER SYSTEM INSTRUMENTATION DIAGRAM FOR AIR INJECTION

NELLIS AFB, NEVADA

ENGINEERING-SCIENCE, INC.

Denver, Colorado

details on power supply requirements are described in Section 5.0, Base Support Requirements.

3.8 *In Situ* Respiration Tests

The objective of the *in situ* respiration tests is to determine the rate at which soil bacteria degrade petroleum hydrocarbons. Respiration tests will be performed at every vapor MP at each of the three sites where bacterial biodegradation of hydrocarbons is indicated by low oxygen levels and elevated carbon dioxide concentrations in the soil gas. Using a 1-scfm pump, air will be injected into each MP depth interval containing low levels (<2%) of oxygen. A 20-hour air injection period will be used to oxygenate local contaminated soils. At the end of the 20-hour air injection period, the air supply will be cut off, and oxygen and carbon dioxide levels will be monitored for the following 48 to 72 hours. The decline in oxygen and increase in carbon dioxide concentrations over time will be used to estimate rates of bacterial degradation of fuel residuals. Helium will also be injected at three or four MPs at each site to determine whether there are leaks in the monitoring points, allowing oxygen to escape. Additional details on the *in situ* respiration test procedures are provided in Section 5.7 of the protocol document (Hinchee et al., 1992).

3.9 Air Permeability Tests

The objective of the air permeability tests is to determine the extent of the subsurface that can be oxygenated using the VWs. Air will be injected into the 4-inch-diameter VWs using the blower unit, and pressure response will be measured at each MP with differential pressure gauges to determine the region influenced by the unit. Oxygen will also be monitored in the MPs to ascertain whether oxygen levels in the soil increase as the result of air injection. One air permeability test lasting 4 to 8 hours will be performed at each site.

3.10 Potential for Air Emissions

The potential for air emissions is considered low for these sites. Soil gas will move outward and upward from the deep contamination, and volatile contaminants in the soil gas will biodegrade as the gas migrates. During initial air injection, health and safety monitoring will ensure that breathing-zone hydrocarbon concentrations do not exceed 1 part per million, volume per volume (ppmv).

3.11 Extended Pilot Test Bioventing System

If initial testing shows adequate soil permeability and oxygen transport, extended bioventing systems will also be installed at Site 27, 28, and 44. At each site, the base will be requested to provide a power pole with a 230-volt, single-phase, 30-amp breaker box, one 230-volt receptacle, and one 110-volt duplex receptacle. Depending on the availability of a base electrician, a base electrician or a licensed electrician subcontracted to ES will assist in wiring the blowers to line power. The blowers will be 1.0-horsepower regenerative blowers capable of injecting air at approximately 2 psi and 88 scfm. The blowers will be provided with vacuum, pressure, and temperature gauges, air filters, and pressure relief and flow control valves (see Figure 3.10). The blowers will be housed in small, prefabricated sheds to provide protection from the weather.

The systems will be in operation for 1 year, and every 6 months ES personnel will conduct *in situ* respiration tests to monitor the long-term performance of this bioventing system. Weekly system checks will be performed by Nellis AFB personnel. If required, major maintenance of the blower unit may be performed by ES personnel. Detailed blower system information and a maintenance schedule will be included in the operation and maintenance (O&M) manual to be provided to the base. More detailed information regarding the test procedures can be found in the protocol document.

4.0 EXCEPTIONS TO PROTOCOL PROCEDURES

The procedures that will be used to measure the air permeability of the soil and *in situ* respiration rates are described in Sections 4 and 5 of the protocol document (Hinchee et al., 1992). No exceptions to the protocol procedures are anticipated.

5.0 BASE SUPPORT REQUIREMENTS

The following base support is needed prior to the arrival of the drilling subcontractor and the ES pilot test team:

- Assistance in obtaining drilling and digging permits.
- Assistance in selecting a suitable location for the background well. The background well location should be in an area with no fuel contamination and with similar stratigraphy to that of Sites 27, 28, and 44. Preferably, a 110-volt receptacle will be available within 150 feet of the background well location.
- Installation of power at Sites 27, 28, 44. Each site will require a 230-volt, 30-amp, single-phase service and a breaker box with one 230-volt receptacle and one 110-volt duplex receptacle. The breaker box should be located as close as possible, but within 50 feet of the proposed central VW location at each site.
- Provision of any paperwork required to obtain gate passes and security badges for approximately two ES employees, two drillers, and an electrician (if a base electrician is not available). Vehicle passes will be needed for one truck and a drill rig.

During the initial testing, the following base support is needed:

- A decontamination area where the driller can clean augers between borings.
- Acceptance of responsibility by Nellis AFB for drill cuttings from VW and MP borings, including any sampling to determine hazardous waste status.
- Twelve square feet of desk space and a telephone in a building located as close to the site as practicable.
- The use of a facsimile machine for transmitting 15 to 20 pages of test results.

During the 1-year extended pilot test, base personnel will be required to perform the following activities:

- Check the blower system once per week to ensure that it is operating and to record the air injection pressure and temperature. Change air filters when required. ES will provide a brief training session on these procedures and an O&M manual.

- If the blower stops working, notify Mr. Russell Frishmuth or Mr. Doug Downey, ES-Denver, at (303) 831-8100, or Mr. Marty Faile, AFCEE, at (210) 536-4342.
- Arrange site access for an ES technician to conduct *in situ* respiration tests approximately 6 months and 1 year after the initial pilot test.

6.0 PROJECT SCHEDULE

The following schedule is contingent upon timely approval of this pilot test work plan.

<u>Event</u>	<u>Date</u>
Draft Test Work Plan to AFCEE/Nellis AFB	9 December 1993
Begin Initial Pilot Tests	11 January 1994
 <u>Event</u>	 <u>Date</u>
Complete Initial Pilot Tests	10 February 1994
Interim Results Report	30 March 1994
Second Respiration Tests	August 1994
Final Respiration Tests	February 1995

7.0 POINTS OF CONTACT

Sarah Robison
USAFWTC/EVR
4551 Devlin Drive
Nellis AFB, NV 89141-6546
(702) 652-3164

Waldo Pulido
USAFWTC/EVR
4551 Devlin Drive
Nellis AFB, NV 89141-6546
(707) 652-3567

Marty Faile
AFCEE/EST
2504 D Drive, Suite 3
Brooks AFB, TX 78235-5103
(210) 536-4366

Doug Downey and
Russell Frishmuth
Engineering-Science, Inc.
1700 Broadway, Suite 900
Denver, CO. 80290
(303) 831-8100
Fax (303) 831-8208

8.0 REFERENCES

- Engineering-Science, Inc. (ES). 1992a. *Service Island Site Assessment, Nellis Air Force Base, Las Vegas, Nevada*. March. Austin, TX.
- Engineering-Science, Inc. (ES). 1992b. *Field Sampling Plan for AFCEE Bioventing*. April. Denver, CO.
- Engineering-Science, Inc. (ES). 1993. *Remedial Investigation of Site 44 at Nellis Air Force Base, Las Vegas, Nevada*. Interim Draft. August. Houston, TX.
- Hinchee, R.E., S.K. Ong, R.N. Miller, D.C. Downey, and R. Frandt. 1992. *Test Plan and Technical Protocol for a Field Treatability Test for Bioventing*. January.
- OHM Remediation Services Corporation. 1992. *Site 27 Fuel Recovery System Installation, Nellis Air Force Base, Las Vegas, Nevada*. Volume I. December. Walnut Creek, CA.
- Radian Corporation. 1993a. *December 1992 Quarterly Monitoring Report Site 27, Nellis Air Force Base, Nevada*. April. Austin, TX.
- Radian Corporation. 1993b. *March 1993 Quarterly Monitoring Report Site 28, Nellis Air Force Base, Nevada*. June. Austin, TX.
- Radian Corporation. 1993c. *Installation Restoration Program Remedial Investigation for Sites 27 and 28. Technical Memorandum, Nellis Air Force Base, Nevada*. Draft. January. Austin, TX.

PART II
DRAFT INTERIM PILOT TEST RESULTS REPORT FOR
SITES 27, 28, AND 44

NELLIS AFB, NEVADA

March 1994

Prepared for:

Air Force Center for Environmental Excellence
Brooks AFB, Texas

and

USAFWTC/EVR
Nellis AFB, Nevada

Prepared by:

Engineering-Science, Inc.
1700 Broadway, Suite 900
Denver, Colorado 80290

CONTENTS

PART II - DRAFT INTERIM PILOT TEST RESULTS REPORT FOR SITES 27, 28, AND 44 NELLIS AFB, NEVADA

	<u>Page</u>
1.0 Pilot Test Design and Construction	II-1
1.1 Site 27	II-1
1.1.1 Air Injection Vent Well	II-4
1.1.2 Monitoring Points	II-4
1.1.3 Blower Unit	II-4
1.2 Site 28	II-4
1.2.1 Air Injection Vent Well	II-9
1.2.2 Monitoring Points	II-9
1.2.3 Blower Unit	II-9
1.3 Site 44	II-14
1.3.1 Air Injection Vent Well	II-14
1.3.2 Monitoring Points	II-14
1.3.3 Blower Unit	II-14
2.0 Pilot Test Soil and Soil Gas Sampling Results	II-20
2.1 Site 27	II-20
2.1.1 Sampling Results	II-20
2.1.2 Exceptions to Test Protocol Document Procedures	II-20
2.2 Site 28	II-22
2.2.1 Sampling Results	II-22
2.2.2 Exceptions to Test Protocol Document Procedures	II-22
2.3 Site 44	II-24
2.3.1 Sampling Results	II-24
2.3.2 Exceptions to Test Protocol Document Procedures	II-24
3.0 Pilot Test Results	II-26
3.1 Site 27	II-26
3.1.1 Initial Soil Gas Chemistry	II-26
3.1.2 Air Permeability	II-26
3.1.3 Oxygen Influence	II-26
3.1.4 <i>In Situ</i> Respiration Rates	II-26
3.1.5 Potential Air Emissions	II-30
3.2 Site 28	II-30
3.2.1 Initial Soil Gas Chemistry	II-30
3.2.2 Air Permeability	II-30
3.2.3 Oxygen Influence	II-38
3.2.4 <i>In Situ</i> Respiration Rates	II-38
3.2.5 Potential Air Emissions	II-38
3.3 Site 44	II-45
3.3.1 Initial Soil Gas Chemistry	II-45
3.3.2 Air Permeability	II-45
3.3.3 Oxygen Influence	II-45
3.3.4 <i>In Situ</i> Respiration Rates	II-45
3.3.5 Potential Air Emissions	II-49

CONTENTS (Continued)

	<u>Page</u>
4.0 Recommendations	II-49
4.1 Site 27.....	II-49
4.2 Site 28.....	II-55
4.3 Site 44.....	II-55
5.0 References	II-56
Appendix A	Geologic Boring Logs, Chain-of-Custody Forms, Test Data, and Calculations
Appendix B	Operation and Maintenance Checklist

TABLES

<u>No.</u>	<u>Title</u>	<u>Page</u>
2.1	Soil and Soil Gas Laboratory Analytical Results, Site 27	II-21
2.2	Soil and Soil Gas Laboratory Analytical Results, Site 28	II-23
2.3	Soil and Soil Gas Laboratory Analytical Results, Site 44	II-25
3.1	Initial Soil Gas Chemistry, Site 27	II-27
3.2	Maximum Pressure Response, Air Permeability Test, Site 27	II-28
3.3	Influence of Air Injection at Vent Well on Monitoring Point Oxygen Levels, Site 27.....	II-29
3.4	Oxygen Utilization Rates, Site 27.....	II-35
3.5	Initial Soil Gas Chemistry, Site 28	II-36
3.6	Maximum Pressure Response, Air Permeability Test, Site 28	II-37
3.7	Influence of Air Injection at Vent Well on Monitoring Point Oxygen Levels, PS-4, Site 28	II-39
3.8	Oxygen Utilization Rates, Site 28.....	II-44
3.9	Initial Soil Gas Chemistry, Site 44	II-46
3.10	Maximum Pressure Response, Air Permeability Test, Site 44	II-47
3.11	Influence of Air Injection at Vent Well on Monitoring Point Oxygen Levels, PS-4, Site 44	II-48
3.12	Oxygen Utilization Rates, Site 44.....	II-54

FIGURES

<u>No.</u>	<u>Title</u>	<u>Page</u>
1.1	As-Built Vent Wells and Monitoring Point Locations, Site 27	II-2
1.2	Hydrogeologic Cross Section, Site 27.....	II-3
1.3	As-Built Air Injection Vent Well Construction Detail, Site 27	II-5
1.4	Typical As-Built Monitoring Point Construction Detail, Site 27	II-6
1.5	As-Built Blower System Instrumentation Diagram for Air Injection, Site 27	II-7
1.6	As-Built Vent Well and Monitoring Point Locations, Site 28	II-8
1.7	Hydrogeologic Cross Section, Site 28.....	II-10
1.8	As-Built Air Injection Vent Well Construction Detail, Site 28	II-11
1.9	Typical As-Built Monitoring Point Construction Detail, Site 28	II-12

FIGURES (Continued)

<u>No.</u>	<u>Title</u>	<u>Page</u>
1.10	As-Built Blower System Instrumentation Diagram for Air Injection, Site 28	II-13
1.11	As-Built Vent Well and Monitoring Point Locations, Site 44	II-15
1.12	Hydrogeologic Cross Section, Site 44.....	II-16
1.13	As-Built Air Injection Vent Well Construction Detail, Site 44	II-17
1.14	Typical As-Built Monitoring Point Construction Detail, Site 44	II-18
1.15	As-Built Blower System Instrumentation Diagram for Air Injection, Site 44	II-19
3.1	Respiration Test Results: Vent Well, Site 27.....	II-31
3.2	Respiration Test Results: Monitoring Point MPA-70, Site 27	II-32
3.3	Respiration Test Results: Monitoring Point MPB-55, Site 27	II-43
3.4	Respiration Test Results: Monitoring Point MPC-55, Site 27	II-34
3.5	Respiration Test Results: Vent Well, Site 28.....	II-40
3.6	Respiration Test Results: Monitoring Point MPA-50, Site 28	II-41
3.7	Respiration Test Results: Monitoring Point MPB-60, Site 28	II-42
3.8	Respiration Test Results: Monitoring Point MPC-40, Site 28	II-43
3.9	Respiration Test Results: Vent Well, Site 44.....	II-50
3.10	Respiration Test Results: Monitoring Point MPA-32, Site 44	II-51
3.11	Respiration Test Results: Monitoring Point MPB-39, Site 44	II-52
3.12	Respiration Test Results: Monitoring Point MPC-24, Site 44	II-53

PART II
DRAFT
INTERIM PILOT TEST RESULTS REPORT FOR
SITES 27, 28, AND 44
NELLIS AFB, NEVADA

Initial bioventing pilot tests for *in situ* treatment of fuel-contaminated soils at Sites 27, 28, and 44 at Nellis Air Force Base (AFB) (the Base), Nevada were completed by Engineering-Science, Inc. (ES) during the period from January 11 through February 10, 1994. The three primary objectives of the pilot tests are:

- To assess the potential for supplying oxygen throughout the contaminated soil interval;
- To determine the rate at which indigenous microorganisms will degrade fuel when supplied with oxygen-rich soil gas, and
- To evaluate the potential for sustaining these rates of biodegradation until fuel contamination is remediated to concentrations below regulatory standards.


The purpose of this report is to describe the results of the initial pilot tests at Sites 27, 28, and 44 and to make specific recommendations for extended testing to determine the long-term impact of bioventing on site contaminants. Descriptions of the history, geology, and contamination at the sites are contained in Part I, the Bioventing Pilot Test Work Plan.

1.0 PILOT TEST DESIGN AND CONSTRUCTION


Installation of three vapor monitoring points (MPs) and one vent well (VW) at Site 27 took place on January 13 through January 16, 1994. Installation of three MPs and one VW at Site 28 took place on January 19 through January 21, 1994. Installation of three MPs and one VW at Site 44 took place on January 16 through January 19, 1994. Drilling oversight, MP installation, and soil sampling was conducted by Mr. Rusty Frishmuth, ES site manager, and Mr. Scott Pearson, ES test engineer. Drilling services were provided by Enviro-Drill of Phoenix, Arizona, and electrical services were provided by Canyon Electric, Inc. of Las Vegas, Nevada. The following sections describe the final design and installation of the bioventing systems at each site.

1.1 Site 27

Three MPs, one VW, and a blower unit were installed at Site 27. Locations of the VW and MPs completed at the site are shown in Figure 1.1. The hydrogeologic cross-section of the site is shown in Figure 1.2. Boring logs for the MPs and VW are included in Appendix A.



EW-03



LEGEND

- EW-03 ● PRODUCT RECOVERY WELL
- CHAINLINK FENCE
- MW-24 ⊕ MONITORING WELL
- MPA ⊕ VAPOR MONITORING POINT
- VW ▲ VENT WELL


FIGURE 1.1

AS-BUILT VENT WELL AND MONITORING POINT LOCATIONS SITE 27

Nellis AFB, Nevada

ENGINEERING-SCIENCE, INC.

Denver, Colorado



LITHOLOGIC DESCRIPTION

SAND
 SILTY CLAY
 CLAY, SILT AND SAND
 + + CALICHE

LEGEND

- VW ▲ VENT WELL
- MPA ● MONITORING POINT
- 200
- 193
- — — GROUNDWATER ELEVATION
- — — GEOLOGIC CONTACT, DASHED WHERE INFERRED
- MONITORING POINT
- SCREENED INTERVAL
- SCREENED WELL INTERVAL

FIGURE 1.2

HYDROGEOLOGIC CROSS SECTION SITE 27

Nellis AFB, Nevada

ENGINEERING-SCIENCE, INC.

Denver, Colorado

The background MP for this site is MW-6, a monitoring well located approximately 400 feet north of Site 44. MW-6 is screened from 30 to 50 feet below ground surface (bgs) and has approximately 17 feet of screen above the groundwater surface. Soil gas was extracted from this well, however, a soil sample was not collected. A background soil sample will be collected during 1-year testing.

1.1.1 Air Injection Vent Well

The air injection VW was installed following procedures described in the Air Force Center for Environmental Excellence (AFCEE) bioventing protocol document (Hinchee et al., 1992). Figure 1.3 shows construction details for the VW. The VW was installed in contaminated soils with the screened interval extending from 55 to 80 feet bgs. The groundwater surface was approximately 71 feet bgs prior to the pilot test. The VW was constructed using 4-inch-diameter, Schedule 40 polyvinyl chloride (PVC) casing, with 25 feet of 0.04-inch slotted PVC screen. The annular space between the well casing and borehole was filled with 6-9 grain-size silica sand from the bottom of the borehole to approximately 3 feet above the well screen. Five feet of 0.25-inch bentonite pellets was placed above the sand in 6-inch lifts and hydrated in place. Forty-four feet of granular bentonite was placed above the pellets and hydrated in place. The VW was completed with a PVC tee set approximately 1 foot bgs. The tee was then covered with a well box set at the ground surface.

1.1.2 Monitoring Points


MP screens were installed at 55, 65, and 70 feet bgs. The three MPs (MPA, MPB, and MPC) at this site were constructed as shown in Figure 1.4. MPA, MPB, and MPC were installed 10, 25, and 45 feet from the VW, respectively. Each was constructed using 6-inch sections of 1-inch-diameter PVC well screen with 0.25-inch PVC riser pipes extending to the ground surface. At the top of each riser, a ball valve and a 3/16-inch hose barb were installed. The top of each MP was completed with a flush-mounted metal well protector set in concrete. A thermocouple was installed at the 70-foot depth at MPA to measure soil temperature variations.

1.1.3 Blower Unit

A 1-horsepower Gast® regenerative blower was installed at Site 27 for the initial and extended pilot test. During the initial pilot test, the blower was energized by 208-volt, single-phase, 20-amp power from a temporary receptacle mounted on a post by Canyon Electric; for the extended pilot test, the unit has been hard-wired to a newly installed disconnect mounted on the post. The blower was configured to inject approximately 40 standard cubic feet per minute (scfm) for the extended pilot test. The configuration, instrumentation, and specifications for the extended pilot test blower unit are shown on Figure 1.5. Prior to departing from the site, ES engineers provided an operations and maintenance (O&M) briefing checklist and blower maintenance manual to base personnel. A copy of the checklist is provided in Appendix B.

1.2 Site 28

Three MPs, one VW, and a blower unit were installed at Site 28. Locations of the VW and MPs completed at the site are shown on Figure 1.6. The hydrogeologic cross-section for the site is



NOT TO SCALE

FIGURE 1.3

AS-BUILT AIR INJECTION
VENT WELL
CONSTRUCTION DETAIL
SITE 27

Nellis AFB, Nevada

ENGINEERING-SCIENCE, INC.

Denver, Colorado





FIGURE 1.4
TYPICAL AS-BUILT
MONITORING POINT
CONSTRUCTION DETAIL
SITE 27

Nellis AFB, Nevada

ENGINEERING-SCIENCE, INC.

Denver, Colorado



LEGEND






- 
VACUUM INDICATOR
 0-60" H₂O
- 
PRESSURE INDICATOR
 0-100" H₂O
- 
TEMPERATURE INDICATOR
 0-250°F
- 
FLOW CONTROL VALVE
- 
PRESSURE RELIEF VALVE
 SET AT 50" H₂O


FIGURE 1.5

AS-BUILT BLOWER SYSTEM INSTRUMENTATION DIAGRAM FOR AIR INJECTION SITE 27

Nellis AFB, Nevada

ENGINEERING-SCIENCE, INC.

Denver, Colorado



shown on Figure 1.7. Boring logs for the MPs and VW are included in Appendix A. The background MP for this site is MW-6, a monitoring well located in similar soils approximately 400 feet north of Site 44. The well is screened from 30 to 50 feet bgs and has approximately 17 feet of screen above the groundwater surface. Soil gas was extracted from this well, however, a soil sample was not collected. A background soil sample will be collected during 1-year testing.

1.2.1 Air Injection Vent Well


The air injection VW was installed following procedures described in the AFCEE bioventing protocol document (Hinchee et al., 1992). Figure 1.8 shows construction details for the VW. The VW was installed in contaminated soils with the screened interval extending from 30 to 65 feet bgs. The groundwater surface at this site prior to the test varied from approximately 50 feet bgs at MPC to approximately 63.5 feet bgs at the VW. The VW was constructed using 4-inch-diameter, Schedule 40 PVC casing, with 35 feet of 0.04-inch slotted PVC screen. The annular space between the well casing and borehole was filled with 6-9 grain size silica sand from the bottom of the borehole to approximately 3 feet above the well screen. Five feet of 1/4-inch bentonite pellets was placed above the sand in 6-inch lifts and hydrated in place. Twenty feet of granular bentonite was placed above the pellets, hydrated in place, and overlaid with a concrete seal to the existing gravel surface.

1.2.2 Monitoring Points

MP screens were installed at 30-, 40-, 50-, and 60-foot depths at MPA and MPB. Due to elevated groundwater at MPC, a 60-foot screen was not possible; MPC screens were installed at 30, 40, and 50 feet bgs. Four screens were installed at MPA and MPB when it was discovered that contamination extended over a 35 foot interval and several soil types. The three MPs (MPA, MPB, and MPC) at this site were constructed as shown in Figure 1.9. MPA, MPB, and MPC were installed 15, 29, and 56 feet from the VW, respectively (Figure 1.6). The uneven spacing of the MPs was necessary to avoid several underground utilities in the area. Each MP was constructed using 6-inch sections of 1-inch-diameter PVC well screen and 0.25-inch PVC riser pipes extending to the ground surface. At the top of each riser, a ball valve and a 3/16-inch hose barb were installed. The top of each MP was completed with a flush-mounted metal well protector set in concrete. A thermocouple was installed at the 50-foot depth at MPC to measure soil temperature variations.

1.2.3 Blower Unit

A 3-horsepower Roots® positive-displacement blower unit was used at Site 28 for the initial pilot test, and a 1-horsepower Gast® regenerative blower unit was installed at the site for the extended pilot test. The initial pilot test blower was energized by 208-volt, single-phase, 20-amp power from a temporary receptacle mounted on a post outside Building 947. The extended pilot test unit is wired to a newly installed disconnect on the post. The 1-horsepower extended pilot test blower was configured to inject approximately 52 scfm for the extended pilot test. The configuration, instrumentation, and specifications for the extended pilot test blower unit are shown on Figure 1.10. Prior to departing from the site, ES engineers provided an O&M briefing checklist and blower maintenance manual to Base personnel. A copy of the checklist is provided in Appendix B.



LITHOLOGIC DESCRIPTION

	SAND		SILTY CLAY		CLAY AND SAND		SILT AND SAND
	SAND		SILTY CLAY		CLAY, SILT AND SAND		SILT AND SAND


LEGEND

 CALICHE

VENT WELL	GROUNDWATER ELEVATION
MONITORING POINT	GEOLOGIC CONTACT, DASHED WHERE INFERRED
FIELD SCREENING RESULTS FOR TOTAL VOLATILE HYDROCARBONS (ppmv)	MONITORING POINT SCREENED INTERVAL
LABORATORY RESULTS FOR SOIL TOTAL PETROLEUM HYDROCARBONS (mg/kg)	SCREENED WELL INTERVAL

2" DIAMETER SCH 40
PVC HEADER SLOPED
TO WELL

TO BLOWER



NOT TO SCALE


FIGURE 1.8

AS-BUILT AIR INJECTION
VENT WELL
CONSTRUCTION DETAIL
SITE 28

Nellis AFB, Nevada

ENGINEERING-SCIENCE, INC.

Denver, Colorado




NOT TO SCALE

FIGURE 1.9
TYPICAL AS-BUILT
MONITORING POINT
CONSTRUCTION DETAIL
SITE 28

Nellis AFB, Nevada

ENGINEERING-SCIENCE, INC.

Denver, Colorado



LEGEND






- 
VACUUM INDICATOR
0-60" H₂O
- 
PRESSURE INDICATOR
0-100" H₂O
- 
TEMPERATURE INDICATOR
0-250°F
- 
FLOW CONTROL VALVE
- 
PRESSURE RELIEF VALVE
SET AT 50" H₂O

FIGURE 1.10

AS-BUILT BLOWER SYSTEM INSTRUMENTATION DIAGRAM FOR AIR INJECTION SITE 28

Nellis AFB, Nevada

ENGINEERING-SCIENCE, INC.

Denver, Colorado

1.3 Site 44

Three MPs, one VW, and a blower unit were installed at Site 44. Locations of the VW and MPs completed at the site are shown on Figure 1.11. The hydrogeologic cross-section for the site is shown on Figure 1.12. Boring logs for the MPs and VW are included in Appendix A. The background MP for this site is MW-6, a monitoring well located approximately 400 feet north of the site. The well is screened from 30 to 50 feet bgs and has approximately 17 feet of screen above the groundwater surface. Soil gas was extracted from this well, however, a soil sample was not collected. A background soil sample will be collected during 1-year testing.

1.3.1 Air Injection Vent Well


The air injection VW was installed following procedures described in the AFCEE bioventing protocol document (Hinchee et al., 1992). Figure 1.13 shows construction details for the VW. The VW was installed in contaminated soils with the screened interval extending from 18 to 43 feet bgs. The groundwater surface at this site was approximately 44 feet bgs prior to the pilot test. The VW was constructed using 4-inch-diameter, Schedule 40 PVC casing, with 25 feet of 0.04-inch slotted PVC screen. The annular space between the well casing and borehole was filled with 6-9 grain size silica sand from the bottom of the borehole to approximately 3 feet above the well screen. Sixteen feet of granular bentonite was placed above the sand, hydrated in place, and overlaid with a concrete seal to the existing asphalt surface.


1.3.2 Monitoring Points

The MP screens were installed at 24-, 32-, and 39-foot depths. The three MPs (MPA, MPB, and MPC) at this site were constructed as shown in Figure 1.14. MPA, MPB, and MPC were installed 10, 20, and 35 feet from the VW, respectively. Each was constructed using 6-inch sections of 1-inch-diameter PVC well screen and 0.25-inch PVC riser pipes extending to the ground surface. At the top of each riser, a ball valve and a 3/16-inch hose barb were installed. The top of each MP was completed with a flush-mounted metal well protector set in concrete. A thermocouple was installed at the 39-foot depth at MPA to measure soil temperature variations.

1.3.3 Blower Unit

A 1-horsepower Gast® regenerative blower was installed at Site 44 for the initial and extended pilot test. During the initial pilot test, the blower was energized by 208-volt, single-phase, 20-amp power from a temporary receptacle mounted on a newly installed pole by Canyon Electric; for the extended pilot test, the unit has been hard-wired to a newly installed breaker mounted on the pole. The blower was configured to inject approximately 61 scfm for the extended pilot test. The configuration, instrumentation, and specifications for the extended pilot test unit are shown on Figure 1.15. Prior to departing from the site, ES engineers provided an O&M briefing checklist and blower maintenance manual to base personnel. A copy of the checklist is provided in Appendix B.





LITHOLOGIC DESCRIPTION

SILTY CLAY
 SILT AND SAND
 CALICHE

LEGEND

- VW VENT WELL
- MPA MONITORING POINT
- 780 FIELD SCREENING RESULTS FOR TOTAL VOLATILE HYDROCARBONS (ppmv)
- 865 LABORATORY RESULTS FOR SOIL TOTAL PETROLEUM HYDROCARBONS (mg/kg)
- GROUNDWATER ELEVATION
- GEOLOGIC CONTACT, DASHED WHERE INFERRED
- MONITORING POINT SCREENED INTERVAL
- SCREENED WELL INTERVAL

FIGURE 1.12

HYDROGEOLOGIC CROSS SECTION SITE 44


Nellis AFB, Nevada

ENGINEERING-SCIENCE, INC.

Denver, Colorado

2" DIAMETER SCH 40
PVC HEADER SLOPED
TO WELL

TO BLOWER



NOT TO SCALE


FIGURE 1.13

AS-BUILT AIR INJECTION
VENT WELL
CONSTRUCTION DETAIL
SITE 44

Nellis AFB, Nevada

ENGINEERING-SCIENCE, INC.

Denver, Colorado




NOT TO SCALE

FIGURE 1.14
TYPICAL AS-BUILT
MONITORING POINT
CONSTRUCTION DETAIL
SITE 44

Nellis AFB, Nevada

ENGINEERING-SCIENCE, INC.

Denver, Colorado



LEGEND

- VI 1 VACUUM INDICATOR
0-60" H₂O
- PI 1 PRESSURE INDICATOR
0-100" H₂O
- TI 1 TEMPERATURE INDICATOR
0-250°F
- FCV FLOW CONTROL VALVE
- PRV PRESSURE RELIEF VALVE
SET AT 50" H₂O

FIGURE 1.15

AS-BUILT BLOWER SYSTEM INSTRUMENTATION DIAGRAM FOR AIR INJECTION SITE 44

Nellis AFB, Nevada

ENGINEERING-SCIENCE, INC.

Denver, Colorado

2.0 PILOT TEST SOIL AND SOIL GAS SAMPLING RESULTS

2.1 Site 27

2.1.1 Sampling Results

Soils at this site generally consist of silty clay with lenses of sand and caliche (Figure 1.2). Bedrock was not encountered during drilling for this pilot test and is not shown on the figure. The general soil profile consists of clay, silt, and sand in the upper 19 feet, a lens of caliche from 19 to 23 feet bgs, silty clay from 23 to approximately 42 feet bgs, a lens of sand from 42 to 45 feet bgs, and silty clay to at least 80 feet bgs. Several other small, isolated lenses of caliche were encountered during drilling. Groundwater occurred at 72 feet bgs in the completed VW. Approximately 0.75 foot of free product was floating on the groundwater surface. Boring logs for the MPs and VW are included in Appendix A.

Hydrocarbon contamination at this site appears to extend from approximately 50 to at least 80 feet bgs. Contaminated soils were identified based on odor and total volatile hydrocarbon (TVH) field screening results. Contaminated soils were encountered in all MP boreholes, with the greatest contamination occurring at 70 feet bgs in MPB (Figure 1.2). Soils at these locations had a strong hydrocarbon odor.

Soil samples for laboratory analysis were collected from split-spoon samplers with 2-inch-diameter brass liners. Soil samples were screened for TVH using a GasTech[®] TVH analyzer to determine the presence of contamination and to select soil samples for laboratory analysis. Soil samples for laboratory analysis were collected from a depth of 80 from the VW, 65 feet from MPA, 70 feet from MPB, and 65 feet from MPC. Soil gas samples were collected by extracting soil gas from a depth of 55 feet bgs from MPA, 70 feet bgs from MPC, and from the VW.

Soil samples were shipped via Federal Express[®] to the Pace, Inc. laboratory in Huntington Beach, California for chemical and physical analysis. Soil samples were analyzed for total recoverable petroleum hydrocarbons (TRPH); benzene, toluene, ethylbenzene, and xylenes (BTEX); iron; alkalinity; total Kjeldahl nitrogen (TKN); and several physical parameters. Soil gas samples were shipped via Federal Express[®] to Air Toxics, Inc. in Folsom, California for TVH and BTEX analysis. The results of these analyses are provided in Table 2.1. Concentrations of soil contaminants appear to be lower than expected when compared to soil gas contaminant concentrations and field observations. Matrix interference appears to be a probable cause for the low laboratory results. Isolated vertical fissures in the soil appeared to contain the majority of the contamination. If soils outside of the fissure zones were collected for laboratory analysis, it is probable that results would be much lower than expected.

2.1.2 Exceptions To Test Protocol Document Procedures

Procedures described in the protocol document (Hinchee et al., 1992) were used to complete treatability tests at Site 27 with a few exceptions. One additional soil sample was analyzed after contamination was discovered in a different soil type and depth at MPC. This sample was included so that the site could be more accurately characterized. One thermocouple was installed at MPA instead of the two prescribed in the test protocol. A 1-

TABLE 2.1
SOIL AND SOIL GAS ANALYTICAL RESULTS
SITE 27
NELLIS AFB, NEVADA

Analyte (Units) ^{a/}	Sample Location-Depth (feet below ground surface)			
<u>Soil Gas Hydrocarbons</u>	<u>VW 55-80</u>	<u>MPA-55</u>	<u>MPC-70</u>	
TVH (ppmv)	89,000	56,000	100,000	
Benzene (ppmv)	390	260	980	
Toluene (ppmv)	240	66	810	
Ethylbenzene (ppmv)	45	25	42	
Xylenes (ppmv)	94	65	140	
<u>Soil Hydrocarbons</u>	<u>VW-80</u>	<u>MPA-65</u>	<u>MPB-70</u>	<u>MPC-65</u>
TRPH (mg/kg)	ND ^{b/}	ND	193	5.9
Benzene (mg/kg)	0.41	0.23	0.51	0.42
Toluene (mg/kg)	0.41	0.022	2.7	4.3
Ethylbenzene (mg/kg)	0.072	0.0076	1.1	2.9
Xylenes (mg/kg)	0.35	0.022	5.4	13
<u>Soil Inorganics</u>	<u>VW-80</u>	<u>MPA-65</u>	<u>MPB-70</u>	<u>MPC-65</u>
Iron (mg/kg)	7,930	9,400	6,350	4,120
Alkalinity (mg/kg as CaCO ₃)	3,930	480	1690	353
pH (units)	8.7	8.6	8.8	9
TKN (mg/kg)	740	100	70	120
Phosphate (mg/kg)	170	170	130	210
<u>Soil Physical Parameters</u>	<u>VW-80</u>	<u>MPA-65</u>	<u>MPB-70</u>	<u>MPC-65</u>
Moisture (% wt.)	13.2	22.7	14.3	5.7
Gravel (%)	0.0	0.0	0.0	8.4
Sand (%)	21.6	25.5	25.2	28.1
Silt (%)	45.0	41.0	40.7	36.7
Clay (%)	33.4	33.5	34.0	26.8
<u>Soil Temperature (°F)</u>	<u>MPA-70</u>			
	69.4			

^{a/} mg/kg = milligrams per kilogram; ppmv = parts per million, volume per volume; CaCO₃ = calcium carbonate; TKN = total Kjeldahl nitrogen; TVH = total volatile hydrocarbons; TRPH = total recoverable petroleum hydrocarbons; °F = degrees Fahrenheit.

^{b/} ND = not detected.

horsepower regenerative blower was used to perform the permeability test. This blower was used after the motor on the 3-horsepower positive-displacement test blower failed and rendered the blower inoperable. Based on data from the permeability test, the smaller blower appears to have provided sufficient air flow to obtain meaningful results.

2.2 Site 28

2.2.1 Sampling Results

Soils at this site consist primarily of silty clays with layers of caliche and sand (Figure 1.7). Bedrock was not encountered during drilling for this pilot test and is not shown in the figure. The general soil profile consists of clay, silt, and sand to 10 feet bgs; silty clays with layers of caliche and sand to 50 to 60 feet bgs; clay, silt, and sand to 55 to 65 feet bgs; and silty clay to at least 65 feet bgs. The groundwater surface at this site prior to the test varied from approximately 50 feet bgs at MPC to approximately 63.5 feet bgs at the VW. Boring logs for the MPs and VW are included in Appendix A.

Hydrocarbon contamination at this site appears to extend from approximately 30 to at least 65 feet bgs. Contaminated soils were identified based on odor and TVH field screening results. Contaminated soils were encountered in all MP boreholes with the greatest contamination occurring at 50 feet bgs at MPB. Soils at these locations had a strong hydrocarbon odor.

Soil samples for laboratory analysis were collected from split-spoon samplers with 2-inch-diameter brass liners. Soil samples were screened for TVH using a GasTech[®] TVH analyzer to determine the presence of contamination and to select soil samples for laboratory analysis. Soil samples for laboratory analysis were collected from a depth of 65 feet from the VW, 42 feet from MPA, and 50 feet from MPB. Soil gas samples were collected by extracting soil gas from a depth of 50 feet bgs from MPA, 30 feet bgs from MPC, and the VW.

Soil samples were shipped via Federal Express[®] to the Pace, Inc. laboratory in Huntington Beach, California for chemical and physical analysis. Soil samples were analyzed for TRPH, BTEX, iron, alkalinity, TKN, and several physical parameters. Soil gas samples were shipped via Federal Express[®] to Air Toxics, Inc. in Folsom, California for TVH and BTEX analysis. The results of these analyses are provided in Table 2.2. Concentrations of soil contaminants appear to be lower than expected when compared to soil gas contaminant concentrations and field observations. Matrix interference appears to be a probable cause for the low laboratory results. Isolated vertical fissures in the soil appeared to contain the majority of the contamination. If soils outside of the fissure zones were collected for laboratory analysis, it is probable that results would be much lower than expected. This is evident when the sample MPB-50 is compared to all of the other samples collected from the area. The area is known to have widespread contamination, yet sample MPB-50 was the only sample that had appreciable concentrations of TRPH or BTEX.

2.2.2 Exceptions To Test Protocol Document Procedures

Procedures described in the protocol document (Hinchee et al., 1992) were used to complete treatability tests at Site 28 with two exceptions. One thermocouple was installed at MPC instead of two at MPA as prescribed in the test protocol. Additionally, two of the MPs,

TABLE 2.2
SOIL AND SOIL GAS ANALYTICAL RESULTS
SITE 28
NELLIS AFB, NEVADA

Analyte (Units) ^{a/}	Sample Location-Depth (feet below ground surface)			
<u>Soil Gas Hydrocarbons</u>	<u>VW 30-65</u>	<u>MPA-50</u>	<u>MPC-30</u>	
TVH (ppmv)	98,000	80,000	38,000	
Benzene (ppmv)	870	400	290	
Toluene (ppmv)	1000	310	330	
Ethylbenzene (ppmv)	64	20	80	
Xylenes (ppmv)	230	65	260	
<u>Soil Hydrocarbons</u>	<u>VW-65</u>	<u>MPA-42</u>	<u>MPB-50</u>	<u>MPB-30</u>
TRPH (mg/kg)	196	ND ^{b/}	8,720	ND
Benzene (mg/kg)	29	0.24	25	0.024
Toluene (mg/kg)	120	0.03	140	0.0025
Ethylbenzene (mg/kg)	51	0.033	68	0.0057
Xylenes (mg/kg)	220	0.18	280	0.026
<u>Soil Inorganics</u>	<u>VW-65</u>	<u>MPA-42</u>	<u>MPB-50</u>	<u>MPB-30</u>
Iron (mg/kg)	6,340	6,550	4,520	NS ^{c/}
Alkalinity (mg/kg as CaCO ₃)	486	433	315	NS
pH (units)	8.7	8.4	8.7	NS
TKN (mg/kg)	93	110	100	110
Phosphate (mg/kg)	490	230	150	NS
<u>Soil Physical Parameters</u>	<u>VW-65</u>	<u>MPA-42</u>	<u>MPB-50</u>	<u>MPB-30</u>
Moisture (% wt.)	32.3	26.6	16	21.6
Gravel (%)	8.9	25.8	1.4	NS
Sand (%)	49.0	40.1	55.2	NS
Silt (%)	27.0	20.4	28.1	NS
Clay (%)	15.1	13.7	15.3	NS
<u>Soil Temperature (°F)</u>	<u>MPC-50</u>			
	73.8			

^{a/} mg/kg = milligrams per kilogram; ppmv = parts per million, volume per volume; CaCO₃ = calcium carbonate; TKN = total Kjeldahl nitrogen; TVH = total volatile hydrocarbons; TRPH = total recoverable petroleum hydrocarbons; °F = degrees Fahrenheit.

^{b/} ND = not detected.

^{c/} NS = not sampled.

MPA and MPB, were constructed with four screened monitoring intervals instead of the typical three. Four monitoring depths were installed because the contaminated soil interval discovered at the site was so large.

2.3 Site 44

2.3.1 Sampling Results

Soils at this site generally consist of silty clays with lenses of caliche (Figure 1.12). Bedrock was not encountered during drilling for this pilot test and is not shown on the figure. The general soil profile consists of silty clay throughout the test interval with lenses of caliche at 11, 20, 35, and 39 feet bgs. A small interval of silt and sand was encountered at the surface at the VW. Groundwater occurred at 44 feet bgs in the VW borehole. Boring logs for the MPs and VW are included in Appendix A.

Hydrocarbon contamination at this site appears to extend from approximately 20 to at least 44 feet bgs. Contaminated soils were identified based on odor and TVH field screening results. Contaminated soils were encountered in all MP boreholes, with the greatest contamination occurring at 32 feet bgs in MPA. Soils at these locations had a strong hydrocarbon odor (Figure 1.12).

Soil samples for laboratory analysis were collected from split-spoon samplers with 2-inch-diameter brass liners. Soil samples were screened for TVH using a GasTech[®] TVH analyzer to determine the presence of contamination and to select soil samples for laboratory analysis. Soil samples for laboratory analysis were collected from a depth of 40 from the VW, 32 feet from MPA, and 24 feet from MPB. Soil gas samples were collected by extracting soil gas from a depth of 32 feet bgs from MPA, 39 feet bgs from MPC, and the VW.

Soil samples were shipped via Federal Express[®] to the Pace, Inc. laboratory in Huntington Beach, California for chemical and physical analysis. Soil samples were analyzed for TRPH, BTEX, iron, alkalinity, TKN, and several physical parameters. Soil gas samples were shipped via Federal Express[®] to Air Toxics, Inc. in Folsom, California for TVH and BTEX analysis. The results of these analyses are provided in Table 2.3. Concentrations of soil contaminants appear to be lower than expected when compared to soil gas contaminant concentrations and field observations. Matrix interference appears to be a probable cause for the low laboratory results. Isolated vertical fissures in the soil appeared to contain the majority of the contamination. If soils outside of the fissure zones were collected for laboratory analysis, it is probable that results would be much lower than expected.

2.3.2 Exceptions To Test Protocol Document Procedures

Procedures described in the protocol document (Hinchee et al., 1992) were used to complete treatability tests at Site 44 with two exceptions. One thermocouple was installed at MPA instead of the two prescribed in the test protocol. A 1-horsepower regenerative blower was used to perform the permeability test. This blower was used after the motor on the 3-horsepower positive displacement test blower failed and rendered the blower inoperable. Based on data from the permeability test, the smaller blower provided sufficient air flow to obtain meaningful results.

TABLE 2.3
SOIL AND SOIL GAS ANALYTICAL RESULTS
SITE 44
NELLIS AFB, NEVADA

Analyte (Units) ^{a/}	Sample Location-Depth (feet below ground surface)		
<u>Soil Gas Hydrocarbons</u>	<u>VW 18-43</u>	<u>MPA-32</u>	<u>MPC-39</u>
TVH (ppmv)	20,000	23,000	45,000
Benzene (ppmv)	99	140	370
Toluene (ppmv)	760	1000	500
Ethylbenzene (ppmv)	74	79	50
Xylenes (ppmv)	460	500	170
<u>Soil Hydrocarbons</u>	<u>VW-40</u>	<u>MPA-32</u>	<u>MPB-24</u>
TRPH (mg/kg)	ND ^{b/}	865	25.3
Benzene (mg/kg)	3.7	ND	ND
Toluene (mg/kg)	6	150	2.7
Ethylbenzene (mg/kg)	0.96	77	7.1
Xylenes (mg/kg)	4.2	240	74
<u>Soil Inorganics</u>	<u>VW-40</u>	<u>MPA-32</u>	<u>MPB-24</u>
Iron (mg/kg)	12,000	2,900	5,360
Alkalinity (mg/kg as CaCO ₃)	625	198	1570
pH (units)	8.2	8.4	8.8
TKN (mg/kg)	140	ND	ND
Phosphate (mg/kg)	430	74	120
<u>Soil Physical Parameters</u>	<u>VW-40</u>	<u>MPA-32</u>	<u>MPB-24</u>
Moisture (% wt.)	45.9	10.5	18.4
Gravel (%)	47.7	0.7	15.8
Sand (%)	20.0	30.2	40.8
Silt (%)	18.1	29.8	27.3
Clay (%)	14.2	39.3	16.0
<u>Soil Temperature (°F)</u>	<u>MPA-39</u>		
	74.0		

^{a/} mg/kg = milligrams per kilogram; ppmv = parts per million, volume per volume; CaCO₃ = calcium carbonate; TKN = total Kjeldahl nitrogen; TVH = total volatile hydrocarbons; TRPH = total recoverable petroleum hydrocarbons; °F = degrees Fahrenheit.

^{b/} ND = not detected.

3.0 PILOT TEST RESULTS

3.1 Site 27

3.1.1 Initial Soil Gas Chemistry

Prior to initiating any air injection, all MPs and the VW were purged until oxygen levels had stabilized, and initial oxygen, carbon dioxide, and TVH concentrations were sampled using portable gas analyzers as described in the protocol document (Hinchee et al., 1992). At all MP screened intervals sampled, microorganisms had significantly depleted soil gas oxygen supplies, indicating significant biological activity and soil contamination. Table 3.1 summarizes the initial soil gas chemistry.

3.1.2 Air Permeability

An air permeability test was conducted according to protocol document procedures. Air was injected into the VW for 21.5 hours at a rate of approximately 7.0 scfm and an average pressure of 1.5 pounds per square inch (psi). The maximum pressure response at each MP is listed in Table 3.2. The pressure measured at the MPs quickly increased at a regular rate throughout the period of air injection. Due to the short-term pressure response, the steady-state method of determining air permeability was selected. A soil gas permeability value of 2.9 darcys, typical for clay soils, was calculated for this site. A radius of pressure influence of at least 45 feet was observed at the 55- and 70-foot depths.

3.1.3 Oxygen Influence

The depth and radius of oxygen increase in the subsurface resulting from air injection into the central VW during pilot testing is the primary design parameter for full-scale bioventing systems. Optimization of full-scale and multiple VW systems requires pilot testing to determine the volume of soil that can be oxygenated at a given flow rate and VW screen configuration.

Table 3.3 presents the change in soil gas oxygen levels that occurred during the 21.5-hour air permeability test. Since the permeability test was conducted with the same blower that will be used for the 1-year extended pilot tests, these oxygen influence results are indicative of what the long-term results will be. This period of air injection at approximately 7.0 scfm produced changes in soil gas oxygen levels at all of the functioning MP screened intervals. Based on measured changes in oxygen levels, it is anticipated that the radius of influence for a long-term bioventing system at this site will exceed 45 feet at the 55- and 70-foot depths. Good oxygen influence above and below the layer at 65 feet bgs should lead to oxygen diffusion into these low-permeability soils. Monitoring during the extended pilot test at this site will better define the effective treatment radius.

3.1.4 In Situ Respiration Rates

The *in situ* respiration test was performed by injecting a mixture of air (oxygen) and approximately 1.9 percent helium (inert tracer gas) into three MP screened intervals (MPA-70, MPB-55, and MPC-55) and the VW for a 19-hour period. Oxygen loss and other changes in soil gas composition over time were then measured at these intervals and at all other MP intervals which had elevated oxygen levels following the air injection. Oxygen, TVH, carbon dioxide, and helium were measured for a period of approximately 9 days following air

TABLE 3.1
INITIAL SOIL GAS CHEMISTRY
SITE 27
NELLIS AFB, NEVADA

Sample Location	Depth (ft)	O ₂ (%)	CO ₂ (%)	Field TVH (ppmv) ^{a/}	Lab TVH (ppmv) ^{b/}	Soil TRPH (mg/kg) ^{c/}
MPA	55	0.5	10.0	>20,000	56,000	NS ^{d/}
MPB	55	0.7	11.0	>20,000	NS	NS
MPC	55	1.8	9.5	>20,000	NS	NS
MPA	65	--- ^{e/}	---	---	---	ND ^{f/}
MPB	65	---	---	---	---	NS
MPC	65	---	---	---	---	5.9
MPA	70	1.0	1.0	>20,000	NS	NS
MPB	70	2.5	0.9	>20,000	NS	193
MPC	70	2.9	0.8	>20,000	100,000	NS
VW	55-80	2.0	8.1	>20,000	89,000	ND ^{g/}

^{a/} Field screening results, in parts per million, volume per volume (ppmv).

^{b/} Laboratory results.

^{c/} Laboratory soil results, in milligrams per kilogram (mg/kg).

^{d/} NS = not sampled.

^{e/} --- = unable to collect sample due to tight soil conditions.

^{f/} ND = not detected.

^{g/} Sample collected from 80 feet bgs.

TABLE 3.2
MAXIMUM PRESSURE RESPONSE
AIR PERMEABILITY TEST
SITE 27
NELLIS AFB, NEVADA

	Distance from VW (feet)								
	10 (MPA)			25 (MPB)			45 (MPC)		
Depth (feet)	55	65	70	55	65	70	55	65	70
Time (min)	1,140	1,140	1,140	1,140	1,140	1,140	1,140	25	1,140
Max Press. (inches H ₂ O)	6.30	0.82	11.5	3.10	1.70	8.80	3.05	0.13	8.40

TABLE 3.3
INFLUENCE OF AIR INJECTION AT VENT WELL
ON MONITORING POINT OXYGEN LEVELS
SITE 27
NELLIS AFB, NEVADA

MP	Distance From VW (ft)	Depth (ft)	Initial O ₂ (%)	Final O ₂ (%) ^{a/}
A	10	55	0.5	20.7
B	25	55	0.7	20.4
C	45	55	1.8	17.9
A	10	65	--- ^{b/}	---
B	25	65	---	---
C	45	65	---	---
A	10	70	1.0	18.2
B	25	70	2.5	20.6
C	45	70	2.9	20.3

^{a/} Reading taken after approximately 21.5 hours of injection using long-term blower system.

^{b/} --- = unable to collect sample due to tight soil conditions.

injection. The measured oxygen losses were then used to calculate biological oxygen utilization rates. The results of *in situ* respiration testing for the MP intervals at this site are presented in Figures 3.1 through 3.4. Additional respiration test results are included in Appendix A. Table 3.4 provides a summary of the oxygen utilization rates.

Because helium is a conservative, inert gas, the change in helium concentrations over time can be useful in determining the effectiveness of the bentonite seals between MP screened intervals. Figures 3.1 through 3.4 compare oxygen utilization and helium retention. Because the observed helium loss was negligible, and because helium will diffuse approximately three times faster than oxygen due to oxygen's greater molecular weight, the measured oxygen loss is the result of bacterial respiration and is not due to faulty MP construction.

Oxygen loss occurred at slow rates, ranging from 0.0001 percent per minute at MPC-55 to 0.0038 percent per minute at the VW. At the VW, oxygen dropped from 20.6 percent to 12.7 percent in 1,980 minutes.

Based on these oxygen utilization rates, an estimated 40 to 150 milligrams (mg) of fuel per kilogram (kg) of soil can be degraded each year at this site. This conservative estimate is based on an average air-filled porosity of approximately 0.14 liter per kg of soil, and a ratio of 3.5 mg of oxygen consumed for every 1 mg of fuel biodegraded. If oxygen can be uniformly distributed in these soils, moderate long-term remediation of fuel hydrocarbons is predicted.

3.1.5 Potential Air Emissions

The long-term potential for air emissions from full-scale bioventing operations at this site is low because of the air injection depth. Accumulated vapors will move slowly outward from the air injection VW, and vapor-phase hydrocarbons will be biodegraded as they move horizontally through the soil.

3.2 Site 28

3.2.1 Initial Soil Gas Chemistry

Prior to initiating any air injection, all MPs and the VW were purged until oxygen levels had stabilized, and initial oxygen, carbon dioxide, and TVH concentrations were sampled using portable gas analyzers, as described in the protocol document (Hinchee et al., 1992). At all MP screened intervals sampled, microorganisms had significantly depleted soil gas oxygen supplies, indicating significant biological activity and soil contamination. Table 3.5 summarizes the initial soil gas chemistry.

3.2.2 Air Permeability

An air permeability test was conducted according to protocol document procedures. Air was injected into the VW for 18 hours at a flow rate of approximately 27 scfm and an average pressure of 3.0 psi. The maximum pressure response at each MP are presented in Table 3.6. The pressure measured at the MPs quickly increased regularly during the period of air injection. Due to the short-term pressure response, the steady-state method of determining air permeability was selected. A soil gas permeability value of 1.01 darcys, typical for clay soils, was calculated for this site. A radius of pressure influence of at least 56 feet was observed in soils below 30 feet bgs.

Figure 3.1
Respiration Test
Oxygen and Helium Concentrations
Site 27, VW
Nellis AFB, Nevada




Figure 3.2
Respiration Test
Oxygen and Helium Concentrations
Site 27, MPA-70
Nellis AFB, Nevada




Figure 3.3
Respiration Test
Oxygen and Helium Concentrations
Site 27, MPB-55
Nellis AFB, Nevada




Figure 3.4
Respiration Test
Oxygen and Helium Concentrations
Site 27, MPC-55
Nellis AFB, Nevada




TABLE 3.4
OXYGEN UTILIZATION RATES
SITE 27
NELLIS AFB, NEVADA

Location	O ₂ Loss ^{a/} (%)	Test ^{b/} Duration (min)	O ₂ Utilization ^{c/} Rate (%/min)
MPA-70	3.7	7,220	0.0005
MPB-55	4.0	7,230	0.0005
MPC-55	2.5	13,050	0.0001
VW	7.9	1,980	0.0038

^{a/} Actual measured oxygen loss.

^{b/} Elapsed time from beginning of test to time when minimum oxygen concentration was measured.

^{c/} Values based on best-fit lines (Figures 3.1 through 3.4).

TABLE 3.5
INITIAL SOIL GAS CHEMISTRY
SITE 28
NELLIS AFB, NEVADA

Sample Location	Depth (ft)	O ₂ (%)	CO ₂ (%)	Field TVH (ppmv) ^{a/}	Lab TVH (ppmv) ^{b/}	Soil TRPH (mg/kg) ^{c/}
MPA	30	0.5	15.3	15,400	NS ^{d/}	NS
MPB	30	1.0	15.0	16,400	NS	ND ^{e/}
MPC	30	0.8	14.2	13,800	38,000	NS
MPA	40	0.5	13.9	>20,000	NS	NS
MPB	40	1.0	14.5	>20,000	NS	NS
MPC	40	1.0	14.0	>20,000	NS	NS
MPA	50	0.0	2.5	>20,000	80,000	NS
MPB	50	--- ^{f/}	---	---	---	8,720
MPC	50	0.7	14.0	>20,000	NS	NS
MPA	60	---	---	---	---	NS
MPB	60	2.2	8.2	>20,000	NS	NS
VW	55-80	1.2	14.0	>20,000	98,000	196 ^{g/}

^{a/} Field screening results, in parts per million, volume per volume (ppmv).

^{b/} Laboratory results.

^{c/} Laboratory soil results, in milligrams per kilogram (mg/kg).

^{d/} NS = not sampled.

^{e/} ND = not detected.

^{f/} --- = unable to collect sample due to tight soil conditions.

^{g/} Sample collected from 65 feet bgs.

TABLE 3.6

**MAXIMUM PRESSURE RESPONSE
AIR PERMEABILITY TEST
SITE 28
NELLIS AFB, NEVADA**

	Distance from VW (feet)											
	15 (MPA)				29 (MPB)				56 (MPC)			
Depth (feet)	30	40	50	60	30	40	50	60	30	40	50	
Time (min)	90	90	120	110	90	90	150	150	100	70	110	
Max Press. (inches H ₂ O)	0.40	0.90	1.80	36.5	0.24	0.50	0.00	28.4	0.16	0.25	0.54	

3.2.3 Oxygen Influence

The depth and radius of oxygen increase in the subsurface resulting from air injection into the central VW during pilot testing is the primary design parameter for full-scale bioventing systems. Optimization of full-scale and multiple VW systems requires pilot testing to determine the volume of soil that can be oxygenated at a given flow rate and VW screen configuration.

Table 3.7 presents the change in soil gas oxygen levels that occurred during the 18-hour air permeability test. This period of air injection at approximately 27 scfm produced changes in soil gas oxygen levels at each of the functioning MP screened intervals. Based on measured changes in oxygen levels, it is anticipated that the radius of influence for a long-term bioventing system at this site will exceed 55 feet at all depths between the groundwater surface and approximate 30 feet bgs. Monitoring during the extended pilot test at this site will better define the effective treatment radius.

3.2.4 *In Situ* Respiration Rates

The *in situ* respiration test was performed by injecting a mixture of air (oxygen) and approximately 2.2 percent helium (inert tracer gas) into three MP screened intervals (MPA-50, MPB-60, and MPC-40) and the VW for a 22-hour period. Oxygen loss and other changes in soil gas composition over time were then measured at these intervals and at all other MP intervals which had elevated oxygen levels following the air injection. Oxygen, TVH, carbon dioxide, and helium were measured for a period of approximately 3.6 days following air injection. The measured oxygen losses were then used to calculate biological oxygen utilization rates. The results of *in situ* respiration testing for the MP intervals at this site are presented in Figures 3.5 through 3.8. Additional respiration test results are included in Appendix A. Table 3.8 provides a summary of the oxygen utilization rates.

Because helium is a conservative, inert gas, the change in helium concentrations over time can be useful in determining the effectiveness of the bentonite seals between MP screened intervals. Figures 3.5 through 3.8 compare oxygen utilization and helium retention. Because the observed helium loss was negligible, and because helium will diffuse approximately three times faster than oxygen due to oxygen's greater molecular weight, the measured oxygen loss is the result of bacterial respiration and is not due to faulty MP construction.

Oxygen loss occurred at moderate rates, ranging from 0.0009 percent per minute at MPC-40 to 0.0046 percent per minute at MPA-50. At MPA-50, oxygen dropped from 20.0 percent to 4.9 percent in 3,410 minutes.

Based on these oxygen utilization rates, an estimated 70 to 1,220 mg of fuel per kg of soil can be degraded each year at this site. This conservative estimate is based on an average air-filled porosity of approximately 0.08 liter per kg of soil, and a ratio of 3.5 mg of oxygen consumed for every 1 mg of fuel biodegraded.

3.2.5 Potential Air Emissions

The long-term potential for air emissions from full-scale bioventing operations at this site is low because of the air injection depth. Accumulated vapors will move slowly outward from the air injection VW, and vapor-phase hydrocarbons will be biodegraded as they move horizontally through the soil. Health and safety readings were taken inside Building 947

TABLE 3.7

**INFLUENCE OF AIR INJECTION AT VENT WELL
ON MONITORING POINT OXYGEN LEVELS
SITE 28
NELLIS AFB, NEVADA**

MP	Distance From VW (ft)	Depth (ft)	Initial O ₂ (%)	Final O ₂ (%) ^{a/}
A	15	30	0.5	7.0
B	29	30	1.0	1.0
C	56	30	0.8	0.8
A	15	40	0.5	20.2
B	29	40	1.0	19.4
C	56	40	1.0	14.1
A	15	50	0.0	5.5
B	29	50	--- ^{b/}	20.4
C	56	50	0.7	17.4
A	15	60	---	19.7
B	29	60	2.2	17.9

^{a/} Reading taken at end of 18-hour air permeability test.

^{b/} --- = unable to collect sample due to tight soil conditions.

Figure 3.5
Respiration Test
Oxygen and Helium Concentrations
Site 28, VW
Nellis AFB, Nevada




Figure 3.6
Respiration Test
Oxygen and Helium Concentrations
Site 28, MPA-50
Nellis AFB, Nevada




Figure 3.7
 Respiration Test
 Oxygen and Helium Concentrations
 Site 28, MPB-60
 Nellis AFB, Nevada




TABLE 3.8
OXYGEN UTILIZATION RATES
SITE 28
NELLIS AFB, NEVADA

Location	O ₂ Loss ^{a/} (%)	Test ^{b/} Duration (min)	O ₂ Utilization ^{c/} Rate (%/min)
MPA-50	15.1	3,410	0.0046
MPB-60	8.1	2,810	0.0030
MPC-40	4.6	5,220	0.0009
VW	8.9	1,990	0.0043

^{a/} Actual measured oxygen loss.

^{b/} Elapsed time from beginning of test to time when minimum oxygen concentration was measured.

^{c/} Values based on best-fit lines (Figures 3.5 through 3.8).

prior to leaving the site to ensure that no vapors were migrating into the building as a result of air injection at the site. All readings inside and beneath the building were at background levels.

3.3 Site 44

3.3.1 Initial Soil Gas Chemistry

Prior to initiating any air injection, all MPs and the VW were purged until oxygen levels had stabilized, and initial oxygen, carbon dioxide, and TVH concentrations were sampled using portable gas analyzers as described in the protocol document (Hinchee et al., 1992). At all MP screened intervals sampled, microorganisms had significantly depleted soil gas oxygen supplies, indicating significant biological activity and soil contamination. Table 3.9 summarizes the initial soil gas chemistry.

3.3.2 Air Permeability

An air permeability test was conducted according to protocol document procedures. Air was injected into the VW for 27 hours at a rate of approximately 48 scfm and an average pressure of 1.5 psi. The maximum pressure response at each MP is listed in Table 3.10. The pressure measured at the MPs quickly increased at a regular rate throughout the period of air injection. Due to the short-term pressure response, the steady-state method of determining air permeability was selected. A soil gas permeability value of 2.9 darcys, typical for clay soils, was calculated for this site. A radius of pressure influence of at least 35 feet was observed at all depths.

3.3.3 Oxygen Influence

The depth and radius of oxygen increase in the subsurface resulting from air injection into the central VW during pilot testing is the primary design parameter for full-scale bioventing systems. Optimization of full-scale and multiple VW systems requires pilot testing to determine the volume of soil that can be oxygenated at a given flow rate and VW screen configuration.

Table 3.11 presents the change in soil gas oxygen levels that occurred during the 27-hour air permeability test. Since the permeability test was conducted with the same blower that will be used for the 1-year extended pilot tests, these oxygen influence results are indicative of what the long-term results will be. This period of air injection at approximately 48 scfm produced changes in soil gas oxygen levels at all of the functioning MP screened intervals. Based on measured changes in oxygen levels, it is anticipated that the radius of influence for a long-term bioventing system at this site will exceed 35 feet at all depths. Monitoring during the extended pilot test at this site will better define the effective treatment radius.

3.3.4 In Situ Respiration Rates

The *in situ* respiration test was performed by injecting a mixture of air (oxygen) and approximately 2.8 percent helium (inert tracer gas) into three MP screened intervals (MPA-32, MPB-39, and MPC-24) and the VW for a 19-hour period. Oxygen loss and other changes in soil gas composition over time were then measured at these intervals and at all other MP intervals which had elevated oxygen levels following the air injection. Oxygen, TVH,

TABLE 3.9
INITIAL SOIL GAS CHEMISTRY
SITE 44
NELLIS AFB, NEVADA

Sample Location	Depth (ft)	O ₂ (%)	CO ₂ (%)	Field TVH (ppmv) ^{a/}	Lab TVH (ppmv) ^{b/}	Soil TRPH (mg/kg) ^{c/}
MPA	24	0.0	15.5	6,000	NS ^{d/}	NS
MPB	24	0.5	15.0	7,200	NS	25.3
MPC	24	0.8	13.5	10,400	NS	NS
MPA	32	0.0	16.9	12,400	23,000	865
MPB	32	0.5	13.8	16,200	NS	NS
MPC	32	1.0	10.0	>20,000	NS	NS
MPA	39	--- ^{e/}	---	---	---	NS
MPB	39	0.5	3.7	>20,000	NS	NS
MPC	39	0.5	1.4	>20,000	45,000	NS
VW	18-43	1.2	15.9	11,600	20,000	ND ^{f/ g/}

^{a/} Field screening results, in parts per million, volume per volume (ppmv).

^{b/} Laboratory results.

^{c/} Laboratory soil results, in milligrams per kilogram (mg/kg).

^{d/} NS = not sampled.

^{e/} --- = unable to collect sample due to tight soil conditions.

^{f/} ND = not detected.

^{g/} Sample collected from 40 feet bgs.

TABLE 3.10
MAXIMUM PRESSURE RESPONSE
AIR PERMEABILITY TEST
SITE 44
NELLIS AFB, NEVADA

	Distance from VW (feet)								
	10 (MPA)			20 (MPB)			35 (MPC)		
Depth (feet)	24	32	39	24	32	39	24	32	39
Time (min)	1,620	1,620	1,620	1,620	1,620	1,620	1,620	1,620	1,620
Max Press. (inches H ₂ O)	1.20	1.55	2.25	0.85	1.15	1.35	0.50	0.65	0.73

TABLE 3.11
INFLUENCE OF AIR INJECTION AT VENT WELL
ON MONITORING POINT OXYGEN LEVELS
SITE 44
NELLIS AFB, NEVADA

MP	Distance From VW (ft)	Depth (ft)	Initial O ₂ (%)	Final O ₂ (%) ^{a/}
A	10	24	0.0	18.3
B	20	24	0.5	3.9
C	35	24	0.8	15.5
A	10	32	0.0	20.2
B	20	32	0.5	19.4
C	35	32	1.0	3.1
A	10	39	--- ^{b/}	---
B	20	39	0.5	19.9
C	35	39	0.5	0.9

^{a/} Reading taken after approximately 27 hours of injection using long-term blower system.

^{b/} --- = unable to collect sample due to tight soil conditions.

carbon dioxide, and helium were measured for a period of approximately 3 days following air injection. The measured oxygen losses were then used to calculate biological oxygen utilization rates. The results of *in situ* respiration testing for the MP intervals at this site are presented in Figures 3.9 through 3.12. Additional respiration test results are included in Appendix A. Table 3.12 provides a summary of the oxygen utilization rates.

Because helium is a conservative, inert gas, the change in helium concentrations over time can be useful in determining the effectiveness of the bentonite seals between MP screened intervals. Figures 3.9 through 3.12 compare oxygen utilization and helium retention. Because the observed helium loss was negligible, and because helium will diffuse approximately three times faster than oxygen due to oxygen's greater molecular weight, the measured oxygen loss is the result of bacterial respiration and not due to faulty MP construction.

Oxygen loss occurred at moderate to rapid rates, ranging from 0.0050 percent per minute at MPA-32 to 0.0221 percent per minute at MPB-39. At MPB-39, oxygen dropped from 18.3 percent to 7.3 percent in 600 minutes.

Based on these oxygen utilization rates, an estimated 470 to 6,200 milligrams (mg) of fuel per kilogram (kg) of soil can be degraded each year at this site. This conservative estimate is based on an average air-filled porosity of approximately 0.10 liter per kg of soil, and a ratio of 3.5 mg of oxygen consumed for every 1 mg of fuel biodegraded. If oxygen can be uniformly distributed in these soils, excellent long-term remediation is predicted.

3.3.5 Potential Air Emissions

The long-term potential for air emissions from full-scale bioventing operations at this site is low because of the air injection depth and the relatively impermeable asphalt and concrete covering the surface of the site. Accumulated vapors will move slowly outward from the air injection VW, and vapor-phase hydrocarbons will be biodegraded as they move horizontally through the soil.

4.0 RECOMMENDATIONS

4.1 Site 27

Initial bioventing tests at this site indicate that oxygen has been depleted in the contaminated soils, and that air injection is an effective method of increasing aerobic fuel biodegradation. Although initial biodegradation rates at the site are relatively slow, AFCEE has recommended that air injection continue at this site to determine the long-term radius of oxygen influence and the effect of time, available nutrients, and changing temperatures on fuel biodegradation rates.

A small, 1-horsepower regenerative blower has been installed at the site to continue air injection at a rate of approximately 40 scfm. The electrical work was completed, and the blower system was started on February 8, 1994. In August 1994, ES will return to the site to sample and analyze the soil gas and conduct a repeat respiration test. In February 1995, a final respiration test will be conducted, and soil and soil gas samples will be collected from the site to determine the degree of remediation achieved during the first year of *in situ* treatment.

Figure 3.9
Respiration Test
Oxygen and Helium Concentrations
Site 44, VW
Nellis AFB, Nevada




Figure 3.10
 Respiration Test
 Oxygen and Helium Concentrations
 Site 44, MPA-32
 Nellis AFB, Nevada




TABLE 3.12
OXYGEN UTILIZATION RATES
SITE 44
NELLIS AFB, NEVADA

Location	O ₂ Loss ^{a/} (%)	Test ^{b/} Duration (min)	O ₂ Utilization ^{c/} Rate (%/min)
MPA-32	6.1	1,380	0.0050
MPB-39	11.0	600	0.0221
MPC-24	10.0	610	0.0204
VW	5.9	830	0.0082

^{a/} Actual measured oxygen loss.

^{b/} Elapsed time from beginning of test to time when minimum oxygen concentration was measured.

^{c/} Values based on best-fit lines (Figures 3.9 through 3.12).

Based on the results of the first year of pilot-scale bioventing, AFCEE will recommend one of three options:

- Upgrade, if necessary, and continue operation of the bioventing system for full-scale remediation of the site. AFCEE can assist the Base in obtaining regulatory approval for upgrading and continued operation; or
- If final soil sampling indicates significant contaminant removal has occurred, AFCEE may recommend additional sampling to confirm that cleanup criteria have been achieved; or
- If significant difficulties or poor results are encountered during bioventing at this site, AFCEE may recommend removal of the blower system and proper abandonment of the VW and MPs.

4.2 Site 28

Initial bioventing tests at this site indicate that oxygen has been depleted in the contaminated soils, and that air injection is an effective method of increasing aerobic fuel biodegradation. AFCEE has recommended that air injection continue at this site to determine the long-term radius of oxygen influence and the effect of time, available nutrients, and changing temperatures on fuel biodegradation rates.

A small, 1-horsepower regenerative blower has been installed at the site to continue air injection at a rate of approximately 52 scfm. The electrical work was completed, and the blower system was started on February 8, 1994. In August 1994, ES will return to the site to sample and analyze the soil gas and conduct a repeat respiration test. In February 1995, a final respiration test will be conducted, and soil and soil gas samples will be collected from the site to determine the degree of remediation achieved during the first year of *in situ* treatment.

Based on the results of the first year of pilot-scale bioventing, AFCEE will recommend one of three options:

- Upgrade, if necessary, and continue operation of the bioventing system for full-scale remediation of the site. AFCEE can assist the Base in obtaining regulatory approval for upgrading and continued operation; or
- If final soil sampling indicates significant contaminant removal has occurred, AFCEE may recommend additional sampling to confirm that cleanup criteria have been achieved; or
- If significant difficulties or poor results are encountered during bioventing at this site, AFCEE may recommend removal of the blower system and proper abandonment of the VW and MPs.

4.3 Site 44

Initial bioventing tests at this site indicate that oxygen has been depleted in the contaminated soils, and that air injection is an effective method of increasing aerobic fuel biodegradation. AFCEE has recommended that air injection continue at this site to determine the long-term radius of oxygen influence and the effect of time, available nutrients, and changing temperatures on fuel biodegradation rates.

APPENDIX A
GEOLOGIC BORING LOGS,
CHAIN-OF-CUSTODY FORMS,
TEST DATA, AND CALCULATIONS

LOCATION MAP		Nellis AFB - Bioventing Pilot Study		PAGE <u>1</u> OF <u>4</u>						
		WELL NUMBER ► NE1-VW		LOCATION ► 35' SW of Tank Farm Fence						
		DATE ► 1-13-94		WEATHER ► Clear, Calm 38°F						
		LOGGED BY ► S. Pearson		DRILLED BY ► EnviroDrill						
		DRILLING METHOD ► 6-5/8" ID Hollow-stem Auger		SAMPLING METHOD ► 0' -40' 1.5" S/S 40' -80' 2.0" S/S						
		GRAVEL PACK ► Colorado Silica Sand #6-9 80'-52'		SEAL ► Holeplug 47'-3' 1/4" Bentonite 52'-47'						
CASING ► TYPE Schedule 40 PVC		DIAMETER 4"		LENGTH 54'						
SCREEN ► TYPE Sch 40 PVC SLOT 0.040"		DIAMETER 4"		LENGTH 25'						
				HOLE DIA. 11"						
				TOTAL DEPTH 80'						
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS	WELL COMPLETION
						0			Pilot hole with 4-1/4" ID HSA Overdrill with 8-5/8" ID HSA	FLUSH MOUNT
						1				
						2				
						3				
						4				
dry	poor	stiff	plas			5			Cuttings - SILT AND CLAY, light brown, little fine-grained sand. (CL)	
						6				
						7				
						8				
						9				
dry	poor	v stiff	v plas			10			0.00'-1.00' CLAY, light brown, some silt, trace of very fine-grained sand, partially cemented. (CH)	
						11	1.00	17 40 50=2'		
						12				
						13				
						14				
						15			Cuttings - Same as above.	
						16				
						17				
						18				
						19				
						20				
EXPLANATION		GROUT BENTONITE		SAND CASING		SCREEN WATER LEVEL		HOLEPLUG		

LOCATION MAP						Nellis AFB - Bioventing Pilot Study							PAGE 2 OF 4					
						WELL NUMBER ► NE1-VW			LOCATION ► 35' SW of Tank Farm Fence									
						DATE ► 1-13-94			WEATHER ► Clear, Calm 38°F									
						LOGGED BY ► S. Pearson			DRILLED BY ► EnviroDrill									
						DRILLING METHOD ► 6-5/8" ID Hollow-stem Auger			SAMPLING METHOD ► 0'-40' 1.5" S/S 40'-80' 2.0" S/S									
						GRAVEL PACK ► Colorado Silica Sand #6-9 80'-52'			SEAL ► Holeplug 47'-3' 1/4" Bentonite 52'-47'									
CASING ► TYPE Schedule 40 PVC						DIAMETER 4"			LENGTH 54'			HOLE DIA. 11"						
SCREEN ► TYPE Sch 40 PVC SLOT 0.040"						DIAMETER 4"			LENGTH 25'			TOTAL DEPTH 80'						
						LITHOLOGY/REMARKS										WELL COMPLETION		
dry	poor	hard	x hard			20		50=1'	0.00'-0.94'				CLAY, as above. Little amount of caliche gravel. (CH)					
						21	0.94	-										
						22		-										
						23			21'-23'				CALICHE, Hard Drilling.					
						24												
						25												
						26												
						27												
						28												
						29												
damp		m stiff	plas			30		7	0.00'-1.18'				CLAY, light yellowish brown, some silt, trace of very fine-grained sand. (CL)					
						31	1.18	12										
						32		13										
						33												
						34												
						35			Cuttings -				Same as above.					
						36												
						37												
						38												
						39												
						40												

EXPLANATION

GROUT	SAND	SCREEN	HOLEPLUG
BENTONITE	CASING	WATER LEVEL	

LOCATION MAP		Nellis AFB - Bioventing Pilot Study		PAGE <u>3</u> OF <u>4</u>						
		WELL NUMBER ► NE1-VW		LOCATION ► 35' SW of Tank Farm Fence						
		DATE ► 1-13-94		WEATHER ► Clear, Calm 38°F						
		LOGGED BY ► S. Pearson		DRILLED BY ► EnviroDrill						
		DRILLING METHOD ► 6-5/8" ID Hollow-stem Auger		SAMPLING METHOD ► 0' -40' 1.5" S/S 40' -80' 2.0" S/S						
		GRAVEL PACK ► Colorado Silica Sand #6-9 80'-52'		SEAL ► Holeplug 47'-3' 1/4" Bentonite 52'-47'						
CASING ► TYPE Schedule 40 PVC		DIAMETER 4"		LENGTH 54'						
SCREEN ► TYPE Sch 40 PVC SLOT 0.040"		DIAMETER 4"		LENGTH 25'						
				HOLE DIA. 11"						
				TOTAL DEPTH 80'						
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS	WELL COMPLETION
damp		m stiff	plas			40		9	0.00'-1.34' CLAY, as above. Little dark mottling. (CL)	
						41	1.34	9 15		
						42				
						43				
						44				
damp	poor	m dens	plas -non		25	45		12	0.00'-1.31' SAND, light yellowish brown, fine-grained, little clay and silt, hydrocarbon odor. (ML)	
						46	1.31	15 20		
						47				
						48				
						49				
damp		v stiff	plas		48	50		30	0.00'-1.50' CLAY, light yellowish brown, little silt, trace of very fine-grained sand. (CH)	
				NE1-VW-50		51	1.50	30 50=2'		
						52				
						53				
						54				
damp		m stiff	plas			55		36	0.00'-1.50' CLAY, same as above.	
				NE1-VW-55		56		15 19		
						57				
						58				
						59				
						60				
EXPLANATION		GROUT BENTONITE		SAND CASING		SCREEN WATER LEVEL		HOLEPLUG		

LOCATION MAP				Nellis AFB - Bioventing Pilot Study				PAGE <u>4</u> OF <u>4</u>		
				WELL NUMBER ► NE1-VW		LOCATION ► 35' SW of Tank Farm Fence				
				DATE ► 1-13-94		WEATHER ► Clear, Calm 38°F				
				LOGGED BY ► S. Pearson		DRILLED BY ► EnviroDrill				
				DRILLING METHOD ► 6-5/8" ID Hollow-stem Auger		SAMPLING METHOD ► 0' -40' 1.5" S/S 40' -80' 2.0" S/S				
				GRAVEL PACK ► Colorado Silica Sand #6-9 80'-52'		SEAL ► Holeplug 47'-3' 1/4" Bentonite 52'-47'				
CASING ► TYPE Schedule 40 PVC				DIAMETER 4"		LENGTH 54'		HOLE DIA. 11"		
SCREEN ► TYPE Sch 40 PVC SLOT 0.040"				DIAMETER 4"		LENGTH 25'		TOTAL DEPTH 80'		
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS	WELL COMPLETION
damp		m stiff	plas	NE1-VW-60	14	60		13	0.00'-1.50' CLAY, as above. Some caliche pebbles and gravel. (CL)	
						61	1.50	23		
						62		50 = .5'		
						63				
						64				
damp		stiff	plas	NE1-VW-65	1200	65		10	0.00'-1.50' CLAY, as above.	
						66	1.50	10		
						67		23		
						68				
						69				
damp		stiff	plas	NE1-VW-70	NA	70		23	0.00'-1.50' CLAY, as above.	
						71	1.50	30		
						72		49		
						73				
						74				
damp		stiff	plas	NE1-VW-75	5000	75		20	0.00'-1.50' CLAY, as above.	
						76	1.50	20		
						77		17		
						78				
						79				
moist wet-sat		stiff soft	plas sl plas	NE1-VW-80	4000	79	1.50	15	0.00'-1.00' CLAY, as above. 1.00'-1.50' CLAY, light yellowish brown, some silt and fine caliche gravel, hydrocarbon odor. (CL)	
						80		18		
								25		
<div style="display: flex; justify-content: space-between; align-items: center;"> <div> EXPLANATION GROUT BENTONITE </div> <div> SAND CASING </div> <div> SCREEN WATER LEVEL </div> <div> HOLEPLUG </div> </div>										

LOCATION MAP				Nellis AFB - Bioventing Pilot Study				PAGE <u>1</u> OF <u>4</u>		
				WELL NUMBER ▶ NE1-MPA		LOCATION ▶ 35' SW of Tank Farm Fence				
				DATE ▶ 1-14-94		WEATHER ▶ Clear, Calm 40°F				
				LOGGED BY ▶ S. Pearson		DRILLED BY ▶ EnviroDrill				
				DRILLING METHOD ▶ 4-1/4" ID Hollow-stem Auger		SAMPLING METHOD ▶ 0' -65' 1.5" S/S 65'-75' 2.0" S/S				
				GRAVEL PACK ▶ Colorado Silica #6-9		SEAL ▶ Holeplug 1/4" Bentonite				
CASING ▶ TYPE 0.25" ID PVC				DIAMETER 0.5"		LENGTH 55', 65' & 70'		HOLE DIA. 8"		
SCREEN ▶ TYPE Sch 40 PVC SLOT 0.040"				DIAMETER 1"		LENGTH 6"		TOTAL DEPTH 70'		
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPN)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS	WELL COMPLETION
										FLUSH MOUNT
						0				
						1				
						2				
						3				
						4				
dry	poor	dense	non			5			Cuttings - SAND, light brown, some clay, very fine and fine-grained, little gravel, loose and dry. (ML)	
						6				
						7				
						8				
						9				
dry	poor	dense	non			10		19	0.00'-0.89' CLAY, SILT, SAND AND CALICHE GRAVEL, light brown, some limestone cobbles. (GC)	
						11	0.89	50=5'		
						12				
						13				
						14				
dry		stiff	plas			15			Cuttings - SILT AND CLAY, light brown.	
						16				
						17			17'-22' CALICHE, Hard Drilling.	
						18				
						19				
						20				
EXPLANATION		GROUT BENTONITE		SAND CASING		SCREEN WATER LEVEL		HOLEPLUG		

LOCATION MAP		Nellis AFB - Bioventing Pilot Study		PAGE <u>2</u> OF <u>4</u>							
		WELL NUMBER ► NE1-MPA		LOCATION ► 35' SW of Tank Farm Fence							
		DATE ► 1-14-94		WEATHER ► Clear, Calm 40°F							
		LOGGED BY ► S. Pearson		DRILLED BY ► EnviroDrill							
		DRILLING METHOD ► 4-1/4" ID Hollow-stem Auger		SAMPLING METHOD ► 0' -65' 1.5" S/S 65'-75' 2.0" S/S							
		GRAVEL PACK ► Colorado Silica #6-9		SEAL ► Holeplug 1/4" Bentonite							
CASING ► TYPE 0.25" ID PVC		DIAMETER 0.5"		LENGTH 55', 65' & 70'	HOLE DIA. 8"						
SCREEN ► TYPE Sch 40 PVC SLOT 0.040"		DIAMETER 1"		LENGTH 6"	TOTAL DEPTH 70'						
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPH)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS	WELL COMPLETION	
dry		hard	x hard			20			0.00'-0.71' CALICHE, white to buff, massive.		
						21	0.71				
						22					
						23					
						24					
dry		dense	hard			25			Cuttings - CLAY AND SILT, light brown, little caliche. (ML)		
						26					
						27					
						28					
						29					
dry		m dense	plas			30			0.00'-1.02' CLAY AND SILT, light brown, some caliche nodules. (ML)		
dry		v stiff	v plas			31	0.89		1.02'-1.50' CLAY, light yellowish brown, some silt, trace of very fine-grained sand. (CH)		
						32					
						33					
						34					
dry		v stiff	v plas			35			Cuttings - Same as above.		
						36					
						37					
						38					
						39					
						40					
EXPLANATION				SAND				SCREEN			
		BENTONITE		CASING				WATER LEVEL			

LOCATION MAP		Nellis AFB - Bioventing Pilot Study		PAGE <u>3</u> OF <u>4</u>						
		WELL NUMBER ► NE1-MPA		LOCATION ► 35' SW of Tank Farm Fence						
		DATE ► 1-14-94		WEATHER ► Clear, Calm 40°F						
		LOGGED BY ► S. Pearson		DRILLED BY ► EnviroDrill						
		DRILLING METHOD ► 4-1/4" ID Hollow-stem Auger		SAMPLING METHOD ► 0' -65' 1.5" S/S 65'-75' 2.0" S/S						
		GRAVEL PACK ► Colorado Silica #6-9		SEAL ► Holeplug 1/4" Bentonite						
CASING ► TYPE 0.25" ID PVC		DIAMETER 0.5"		LENGTH 55', 65' & 70'						
SCREEN ► TYPE Sch 40 PVC SLOT 0.040"		DIAMETER 1"		LENGTH 6"						
				HOLE DIA. 8"						
				TOTAL DEPTH 70'						
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS	WELL COMPLETION
dry		hard	x hard			40		31	0.00'-0.36'	
damp		v stiff	v plas		36	41	1.53	39	0.36'-1.37'	
dry		v stiff	v plas			42		49	1.37'-1.53'	
						43				
						44				
damp	poor	m dense	non			45		18	0.00'-1.08'	
					22	46	1.08	28		
						47		37		
						48				
						49				
						50		28	0.00'-0.25'	
dry		hard	x hard		36	51	1.24	12	0.25'-0.68'	
damp		soft	sl plas			52		18	0.68'-1.24'	
moist						53			Note:	
						54			Clays appear to be wetter than in NE1-VW. Possibly water used to hydrate the holeplug in NE1-VW has saturated the nearby clays.	
						55		7	0.00'-1.22'	
damp		soft	sl plas			56	1.51	14		
moist		v stiff	v plas		63	57		27	1.22'-1.51'	
damp						58			CLAY, light brown, some silt, partial calcium carbonate cementation, little amount of caliche nodules. (CH)	
						59				
						60				
<div style="display: flex; justify-content: space-between;"> <div> EXPLANATION GROUT BENTONITE </div> <div> SAND CASING </div> <div> SCREEN WATER LEVEL </div> <div> HOLEPLUG </div> </div>										

LOCATION MAP				Nellis AFB - Bioventing Pilot Study				PAGE 4 OF 4		
				WELL NUMBER ► NE1-MPA		LOCATION ► 35' SW of Tank Farm Fence				
				DATE ► 1-14-94		WEATHER ► Clear, Calm 40°F				
				LOGGED BY ► S. Pearson		DRILLED BY ► EnviroDrill				
				DRILLING METHOD ► 4-1/4" ID Hollow-stem Auger		SAMPLING METHOD ► 0' -65' 1.5" S/S 65'-75' 2.0" S/S				
				GRAVEL PACK ► Colorado Silica #6-9		SEAL ► Holeplug 1/4" Bentonite				
CASING ► TYPE 0.25" ID PVC				DIAMETER 0.5"		LENGTH 55', 65' & 70'		HOLE DIA. 8"		
SCREEN ► TYPE Sch 40 PVC SLOT 0.040"				DIAMETER 1"		LENGTH 6"		TOTAL DEPTH 70'		
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS	WELL COMPLETION
moist		soft	sl plas			60		9	0.00'-1.55' CLAY, light yellowish brown, trace of silt. (CL)	
					200	61	1.51	15		
						62		50=2"		
						63			Driller reports caliche. Hard Drilling.	
						64				
						65				
moist		soft	sl plas			65		32	0.00'-1.50' CLAY, same as above.	
					220	66	1.50	20		
						67		25		
						68				
						69				
						70				
damp		stiff	plas			70		19	0.00'-1.50' CLAY, light yellowish brown, little silt and small caliche pebbles. (CL)	
					540	71	1.50	25		
						72		43		
						73				
						74				
						75				
						76				
						77				
						78				
						79				
						80				
<div style="display: flex; justify-content: space-between; font-size: small;"> <div>EXPLANATION</div> <div> GROUT SAND SCREEN HOLEPLUG </div> <div> BENTONITE CASING WATER LEVEL </div> </div>										

LOCATION MAP		Nellis AFB - Bioventing Pilot Study		PAGE <u>1</u> OF <u>4</u>						
		WELL NUMBER ► NE1-MPB		LOCATION ► 35' SW of Tank Farm Fence						
		DATE ► 1-14-94		WEATHER ► Clear, Calm 65°F						
		LOGGED BY ► S. Pearson		DRILLED BY ► EnviroDrill						
		DRILLING METHOD ► 4-1/4" ID Hollow-stem Auger		SAMPLING METHOD ► 0' - 65' 1.5" S/S 55' - 75' 2.0" S/S						
		GRAVEL PACK ► Colorado Silica #6-9		SEAL ► Holeplug 1/4" Bentonite						
CASING ► TYPE 0.25" ID PVC		DIAMETER 0.5"		LENGTH 55', 65' & 70'						
SCREEN ► TYPE Sch 40 PVC SLOT 0.040"		DIAMETER 1"		LENGTH 6"						
				HOLE DIA. 8"						
				TOTAL DEPTH 70'						
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS	WELL COMPLETION
										FLUSH MOUNT
						0				
						1				
						2				
						3				
						4				
						5				
						6				
						7				
						8				
						9				
dry	poor	dense	non			10		6	0.00'-1.05' CLAY, SILT AND SAND, light brown, some caliche gravel. (SC)	
						11	1.05	17 50=2.5'		
						12				
						13				
						14				
						15			Cuttings - SILT AND CLAY, light brown.	
						16				
						17				
						18				
						19				
						20				
<div style="display: flex; justify-content: space-between; font-size: small;"> <div> EXPLANATION GROUT BENTONITE </div> <div> SAND CASING </div> <div> SCREEN WATER LEVEL </div> <div> HOLEPLUG </div> </div>										

LOCATION MAP		Nellis AFB - Bioventing Pilot Study		PAGE <u>2</u> OF <u>4</u>						
		WELL NUMBER ► NE1-MPB		LOCATION ► 35' SW of Tank Farm Fence						
		DATE ► 1-14-94		WEATHER ► Clear, Calm 65°F						
		LOGGED BY ► S. Pearson		DRILLED BY ► EnviroDrill						
		DRILLING METHOD ► 4-1/4" ID Hollow-stem Auger		SAMPLING METHOD ► 0' -65' 1.5" S/S 65'-75' 2.0" S/S						
		GRAVEL PACK ► Colorado Silica #6-9		SEAL ► Holeplug 1/4" Bentonite						
CASING ► TYPE 0.25" ID PVC		DIAMETER 0.5"		LENGTH 55', 65' & 70'						
SCREEN ► TYPE Sch 40 PVC SLOT 0.040"		DIAMETER 1"		LENGTH 6"						
TOTAL DEPTH 70'										
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS	WELL COMPLETION
dry		hard x hard				20		50=3'	0.00'-0.33' Cavings.	
						21	1.06	—	0.33'-1.06' CALICHE, white to light brown, massive.	
						22				
dry	m stiff non					23			Cuttings - CLAY AND SILT, light brown, little caliche gravel.	
						24				
						25				
						26				
						27				
						28				
						29				
						30		4		
						31	0.80	7		
						32		8		
dry	m stiff plas					33			Cuttings - CLAY, light yellowish brown, trace of caliche pebbles and very fine-grained sand.	
						34				
						35				
						36				
						37				
						38				
						39				
						40				

EXPLANATION	GROUT BENTONITE	SAND CASING	SCREEN WATER LEVEL	HOLEPLUG
-------------	--------------------	----------------	-----------------------	----------

LOCATION MAP		Nellis AFB - Bioventing Pilot Study		PAGE <u>3</u> OF <u>4</u>						
		WELL NUMBER ▶ NE1-MPB	LOCATION ▶ 35' SW of Tank Farm Fence							
		DATE ▶ 1-14-94	WEATHER ▶ Clear, Calm 65°F							
		LOGGED BY ▶ S. Pearson	DRILLED BY ▶ EnviroDrill							
		DRILLING METHOD ▶ 4-1/4" ID Hollow-stem Auger	SAMPLING METHOD ▶ 0' -65' 1.5" S/S 65' -75' 2.0" S/S							
		GRAVEL PACK ▶ Colorado Silica #6-9	SEAL ▶ Holeplug 1/4" Bentonite							
CASING ▶ TYPE 0.25" ID PVC		DIAMETER 0.5"		LENGTH 55', 65' & 70'	HOLE DIA. 8"					
SCREEN ▶ TYPE Sch 40 PVC SLOT 0.040"		DIAMETER 1"		LENGTH 6"	TOTAL DEPTH 70'					
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS	WELL COMPLETION
dry		m stiff	plas		82	40	0.76	11	0.00'-0.76' CLAY, light yellowish brown, trace of silt and very fine-grained sand. (CL)	
					41			17		
						42				
						43				
						44				
dry		m stiff	plas			45		10	0.00'-0.65' CLAY AND SILT, light yellowish brown, some very fine-grained sand. (ML)	
dry	poor	dense	non	100		46	1.55	35	0.65'-1.55' SAND, light yellowish brown, very fine- and fine-grained sand, little clay and silt, apparent hydrocarbon staining. (SC)	
						47		35		
						48				
						49				
damp	poor	m dense	plas			50		10	0.00'-0.53' SAND, same as above.	
damp		stiff	plas	460		51	1.52	26	0.53'-0.91' CLAY, light yellowish brown, some silt and very fine-grained sand. (CL)	
moist		soft	plas			52		21	0.91'-1.16' CLAY, light yellowish brown, trace of silt and very fine-grained sand. (CL)	
dry		m stiff	plas			53			1.16'-1.52' CLAY, light yellowish brown, some silt and very fine-grained sand, little amount of caliche pebbles. (CL)	
						54				
damp		m stiff	plas			55		9	0.00'-0.87' CLAY, light yellowish brown, some silt, little amount of caliche pebbles. (CL)	
damp		m stiff	plas	115		56	1.42	9	0.87'-1.42' CLAY, light yellowish brown, little silt and no caliche. (CL)	
						57		10		
						58				
						59				
						60				
EXPLANATION GROUT SAND SCREEN HOLEPLUG BENTONITE CASING WATER LEVEL										

LOCATION MAP				Nellis AFB - Bioventing Pilot Study				PAGE 4 OF 4		
				WELL NUMBER ► NE1-MPB		LOCATION ► 35' SW of Tank Farm Fence				
				DATE ► 1-14-94		WEATHER ► Clear, Calm 65°F				
				LOGGED BY ► S. Pearson		DRILLED BY ► EnviroDrill				
				DRILLING METHOD ► 4-1/4" ID Hollow-stem Auger		SAMPLING METHOD ► 0' -65' 1.5" S/S 65'-75' 2.0" S/S				
				GRAVEL PACK ► Colorado Silica #6-9		SEAL ► Holeplug 1/4" Bentonite				
CASING ► TYPE 0.25" ID PVC				DIAMETER 0.5"		LENGTH 55', 65' & 70'		HOLE DIA. 8"		
SCREEN ► TYPE Sch 40 PVC SLOT 0.040"				DIAMETER 1"		LENGTH 6"		TOTAL DEPTH 70'		
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS	WELL COMPLETION
damp		v stiff	v plas			60		6	0.00'-1.05' CLAY, as above. Caliche zones at 0.1' and 0.5' (CH)	
damp		v stiff	v plas		28	61	1.53	28 50=3"	1.05'-1.53' CLAY, light yellowish brown, some silt and very fine-grained sand, little amount of caliche pebbles. (CH)	
damp	poor	dense	non	NE1-MPB-65	2600	65	1.50	50=3"	0.00'-1.00' Cavings. 1.00'-1.50' CLAY, SILT AND SAND, pale brown to light yellowish brown, very fine-grained, hydrocarbon odor. (ML)	
dry	poor	dense	non	NA		69		17	0.00'-1.00' Cavings.	
dry		hard x hard		NE1-MPB-71	6600	70	1.00	50=5"	0.00'-1.50' CLAY, light yellowish brown, little silt and very fine-grained sand, very hard, large caliche cobbles are present. (CH)	
						71	1.50	117 125 112		
						72				
						73				
						74				
						75				
						76				
						77				
						78				
						79				
						80				
<div style="display: flex; justify-content: space-between;"> <div> EXPLANATION GROUT BENTONITE </div> <div> SAND CASING </div> <div> SCREEN WATER LEVEL </div> <div> HOLEPLUG </div> </div>										

LOCATION MAP		Nellis AFB - Bioventing Pilot Study		PAGE <u>1</u> OF <u>4</u>						
		WELL NUMBER ► NE1-MPC		LOCATION ► 20' NW of NE1-MPB						
		DATE ► 1-15-94		WEATHER ► Clear, Calm 65°F						
		LOGGED BY ► S. Pearson		DRILLED BY ► EnviroDrill						
		DRILLING METHOD ► 4-1/4" ID Hollow-stem Auger		SAMPLING METHOD ► 0' -65' 1.5" S/S 65' 2.0" S/S						
		GRAVEL PACK ► Colorado Silica #6-9		SEAL ► Holeplug 1/4" Bentonite						
CASING ► TYPE 0.25" ID PVC				DIAMETER 0.5" LENGTH 55', 65' & 70'						
SCREEN ► TYPE Sch 40 PVC SLOT 0.040"				DIAMETER 1" LENGTH 6"						
				HOLE DIA. 8"						
				TOTAL DEPTH 70'						
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS	WELL COMPLETION
						0				FLUSH MOUNT
						1				
						2				
						3				
						4				
						5				
						6				
						7				
						8				
						9				
dry	poor	dense	non			10		50=3.5"	0.00'-0.64' CLAY, SILT AND SAND, pale brown, some caliche gravel. (ML)	
						11	0.64			
						12				
						13				
						14				
						15				
						16				
						17				
						18				
						19				
						20				
EXPLANATION		GROUT SAND		SCREEN WATER LEVEL						
		BENTONITE CASING		HOLEPLUG						

LOCATION MAP										Nellis AFB - Bioventing Pilot Study		PAGE <u>2</u> OF <u>4</u>			
										WELL NUMBER ► NE1-MPC		LOCATION ► 20' NW of NE1-MPB			
										DATE ► 1-15-94		WEATHER ► Clear, Calm 65°F			
										LOGGED BY ► S. Pearson		DRILLED BY ► EnviroDrill			
										DRILLING METHOD ► 4-1/4" ID Hollow-stem Auger		SAMPLING METHOD ► 0' -65' 1.5" S/S 65' 2.0" S/S			
										GRAVEL PACK ► Colorado Silica #6-9		SEAL ► Holeplug 1/4" Bentonite			
CASING ► TYPE 0.25" ID PVC										DIAMETER 0.5"		LENGTH 55', 65' & 70'		HOLE DIA. 8"	
SCREEN ► TYPE Sch 40 PVC SLOT 0.040"										DIAMETER 1"		LENGTH 6"		TOTAL DEPTH 70'	
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS				WELL COMPLETION		
dry		hard	x hard			20		50-1.5'	No Recovery- CALICHE, white to pale brown, massive.						
						21	NR								
						22									
						23									
dry		stiff	v plas			24			Cuttings - CLAY, pale brown, some silt and very fine-grained sand.						
						25									
						26									
						27									
dry		m stiff	plas			28			0.00'-0.40' CLAY, SILT AND CALICHE, pale brown. 0.40'-1.50' CLAY, light yellowish brown, some silt, trace of very fine-grained sand, some caliche pebbles.						
dry		m stiff	plas			29									
						30	12								
						31	18								
						32	24								
						33									
						34									
						35									
						36									
						37									
						38									
						39									
						40									
EXPLANATION		GROUT		SAND		SCREEN		HOLEPLUG							
		BENTONITE		CASING		WATER LEVEL									

LOCATION MAP				Nellis AFB - Bioventing Pilot Study				PAGE <u>3</u> OF <u>4</u>												
				WELL NUMBER ► NE1-MPC		LOCATION ► 20' NW of NE1-MPB														
				DATE ► 1-15-94		WEATHER ► Clear, Calm 65°F														
				LOGGED BY ► S. Pearson		DRILLED BY ► EnviroDrill														
				DRILLING METHOD ► 4-1/4" ID Hollow-stem Auger		SAMPLING METHOD ► 0' -65' 1.5" S/S 65' 2.0" S/S														
				GRAVEL PACK ► Colorado Silica #6-9		SEAL ► Holeplug 1/4" Bentonite														
CASING ► TYPE 0.25" ID PVC				DIAMETER 0.5"		LENGTH 55', 65' & 70'		HOLE DIA. 8"												
SCREEN ► TYPE Sch 40 PVC SLOT 0.040"				DIAMETER 1"		LENGTH 6"		TOTAL DEPTH 70'												
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS	WELL COMPLETION										
dry		hard	hard		140	40		41	0.00'-0.88'											
						41	0.88	50=3'	CLICHE, CLAY AND SILT, pale brown to white, caliche is pebble to cobble-sized.											
						42														
						43														
						44														
damp		m stiff	plas			45		8	0.00'-1.13'											
damp	poor	m densel	plas	290		46	1.48	16	1.13'-1.48'											
						47		25	SAND, light yellowish brown, fine- and very fine-grained, subrounded, some clay and silt.											
						48														
						49														
damp	poor	m densel	plas			50		8	0.00'-0.86'											
damp		m stiff	plas			51	1.53	30	0.86'-1.53'											
moist				>10,000		52		16	SAND, as above.											
						53			CLAY, light yellowish brown, trace of silt and very fine-grained sand.											
						54														
damp		v stiff	plas			55		50	0.00'-0.39'											
dry		v stiff	plas	7800		56	1.51	50=3'	0.39'-1.51'											
		-non				57			CLAY, as above, hydrocarbon odor.											
						58			CLAY, SILT AND SAND, pale brown, fine-grained.											
						59														
						60														
<table border="0" style="width: 100%;"> <tr> <td>EXPLANATION</td> <td> GROUT</td> <td> SAND</td> <td> SCREEN</td> <td> HOLEPLUG</td> </tr> <tr> <td></td> <td> BENTONITE</td> <td> CASING</td> <td> WATER LEVEL</td> <td></td> </tr> </table>											EXPLANATION	GROUT	SAND	SCREEN	HOLEPLUG		BENTONITE	CASING	WATER LEVEL	
EXPLANATION	GROUT	SAND	SCREEN	HOLEPLUG																
	BENTONITE	CASING	WATER LEVEL																	

LOCATION MAP		Nellis AFB - Bioventing Pilot Study		PAGE 4 OF 4						
		WELL NUMBER ► NE1-MPC		LOCATION ► 20' NW of NE1-MPB						
		DATE ► 1-15-94		WEATHER ► Clear, Calm 65°F						
		LOGGED BY ► S. Pearson		DRILLED BY ► EnviroDrill						
		DRILLING METHOD ► 4-1/4" ID Hollow-stem Auger		SAMPLING METHOD ► 0' -65' 1.5" S/S 65' 2.0" S/S						
		GRAVEL PACK ► Colorado Silica #6-9		SEAL ► Holeplug 1/4" Bentonite						
CASING ► TYPE 0.25" ID PVC		DIAMETER 0.5"		LENGTH 55', 65' & 70'						
SCREEN ► TYPE Sch 40 PVC SLOT 0.040"		DIAMETER 1"		LENGTH 6"						
TOTAL DEPTH 70'										
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPH)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS	WELL COMPLETION
damp		v stiff	plas		5500	60		14	0.00'-0.53' Cavings.	
						61	1.51	50=5'	0.53'-1.51' CLAY, light yellowish brown, trace of silt and very fine-grained sand, little amount of caliche pebbles.	
						62				
						63				
						64				
						65			0.00'-1.50' CLAY AND CALICHE, light yellowish brown, trace of silt.	
dry		hard x hard		NE1-MPC-65	760	66	1.50	35		
						67				
						68				
						69				
						70			0.00'-0.69' CLAY, pale brown, some silt and fine-grained sand.	
dry		hard x hard			740	71	0.69	100=2'		
						72				
						73				
						74			Overdrill to 74'. Encounter groundwater at 74'.	
						75				
						76				
						77				
						78				
						79				
						80				
EXPLANATION GROUT SAND SCREEN HOLEPLUG BENTONITE CASING WATER LEVEL										

LOCATION MAP										Nellis AFB - Bioventing Pilot Study		PAGE 1 OF 3			
										WELL NUMBER ▶ NE2-VW		LOCATION ▶ 5' SW of Brick Wall			
										DATE ▶ 1-16/17-94		WEATHER ▶ Clear, Calm 60°F			
										LOGGED BY ▶ S. Pearson		DRILLED BY ▶ EnviroDrill			
										DRILLING METHOD ▶ 6-5/8" ID Hollow-stem Auger		SAMPLING METHOD ▶ 0' -15' 1.5" S/S 15'-45' 2.0" S/S			
										GRAVEL PACK ▶ Colorado Silica #6-9 43-15.5'		SEAL ▶ 1/4" Bentonite 15.5'-2'			
CASING ▶ TYPE Schedule 40 PVC										DIAMETER 4"		LENGTH 18'		HOLE DIA. 11"	
SCREEN ▶ TYPE Sch 40 PVC SLOT 0.040"										DIAMETER 4"		LENGTH 25'		TOTAL DEPTH 43'	
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS				WELL COMPLETION		
						0									
						1									
						2									
						3									
						4									
						5									
damp	poor	loose	non			5		6	0.00'-0.54'	SILT AND SAND, pale brown, fine-grained, little clay. (ML)					
damp	poor	m stiff	sl plas			6	1.47	5	0.54'-1.47'						
						6		6		CLAY AND SILT, pale brown, little fine-grained sand. (CL)					
						7									
						8									
						9									
damp						10		34	0.00'-0.95'	CLAY AND SILT, as above.					
dry		v stiff	plas			11	1.45	50=5"	0.95'-1.45'						
		hard	x hard			11		-		CALICHE, white to pale brown, massive.					
						12									
						13									
						14									
damp						15		20	0.00'-0.64'	CLAY, light yellowish brown, some silt and caliche nodules, hydrocarbon-filled fractures. (CL)					
		stiff	plas			16	0.93	50=1"	0.64'-0.93						
damp						16		-		Clay, black-gray, stained with hydrocarbon, some silt and caliche nodules. (CL)					
		stiff	plas			17									
						17			Massive caliche in sampler shoe.						
						18									
						19									
						20									
EXPLANATION															

LOCATION MAP				Nellis AFB - Bioventing Pilot Study		PAGE 2 OF 3				
				WELL NUMBER ▶ NE2-VW	LOCATION ▶ 5' SW of Brick Wall					
				DATE ▶ 1-16/17-94	WEATHER ▶ Clear, Calm 60°F					
				LOGGED BY ▶ S. Pearson	DRILLED BY ▶ EnviroDrill					
				DRILLING METHOD ▶ 6-5/8" ID Hollow-stem Auger	SAMPLING METHOD ▶ 0' -15' 1.5" S/S 15'-45' 2.0" S/S					
				GRAVEL PACK ▶ Colorado Silica #6-9 43-15.5'	SEAL ▶ 1/4" Bentonite 15.5'-2'					
CASING ▶ TYPE Schedule 40 PVC				DIAMETER 4"	LENGTH 18'	HOLE DIA. 11"				
SCREEN ▶ TYPE Sch 40 PVC SLOT 0.040"				DIAMETER 4"	LENGTH 25'	TOTAL DEPTH 43'				
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS	WELL COMPLETION
dry		hard	x hard	NE2-VW-20	35	20		40	0.00'-1.50' CLAY AND CALICHE, light yellowish brown, some silt, hard drilling. (CH)	
						21	1.50	50=4"		
						22				
						23				
						24				
dry				NA	600	25		50=2"	No Recovery-Hard Drilling. Collected headspace sample from cuttings.	
						26				
						27				
						28				
						29				
damp-dry		v stiff	v plas	NE2-VW-30	1200	30		28	0.00'-1.50' CLAY, pale brown, little silt and very fine-grained sand, trace of caliche. (CH)	
						31	1.50	29		
						32		50=5"		
						33				
						34				
dry			v stiff	v plas	NE2-VW-35	35		26	0.00'-1.50' CLAY, pale brown, some silt, trace of very fine-grained sand, moist zone at 1'. (CH)	
						36		50=5.5"		
						37				
						38				
						39				
						40			40' Center plug is covered with hydrocarbon-stained soil.	
<div style="display: flex; justify-content: space-between; font-size: small;"> <div>EXPLANATION</div> <div> GROUT BENTONITE </div> <div> SAND CASING </div> <div> SCREEN WATER LEVEL </div> <div> HOLEPLUG </div> </div>										

LOCATION MAP										Nellis AFB - Bioventing Pilot Study		PAGE 3 OF 3			
										WELL NUMBER ▶ NE2-VW		LOCATION ▶ 5' SW of Brick Wall			
										DATE ▶ 1-16/17-94		WEATHER ▶ Clear, Calm 60°F			
										LOGGED BY ▶ S. Pearson		DRILLED BY ▶ EnviroDrill			
										DRILLING METHOD ▶ 6-5/8" ID Hollow-stem Auger		SAMPLING METHOD ▶ 0' -15' 1.5" S/S 15'-45' 2.0" S/S			
										GRAVEL PACK ▶ Colorado Silica #6-9 43-15.5'		SEAL ▶ 1/4" Bentonite 15.5'-2'			
CASING ▶ TYPE Schedule 40 PVC										DIAMETER 4"		LENGTH 18'		HOLE DIA. 1 1/2"	
SCREEN ▶ TYPE Sch 40 PVC SLOT 0.040"										DIAMETER 4"		LENGTH 25'		TOTAL DEPTH 43'	
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS				WELL COMPLETION		
damp		m	stiff	pl		40		7	0.00'-1.30' CLAY, dark gray, trace of silt and very fine-grained sand, hydrocarbon staining. (CL) 1.30'-1.50' CALICHE, dark gray, massive, hydrocarbon stained.						
moist					41	1.50	7								
dry		hard	x	hard		42	28								
						43			Drill to 45'. Encounter groundwater at 44' below grade. Plug boring with 1/4" bentonite pellets to 43'.						
						44									
						45									
						46									
						47									
						48									
						49									
						50									
						51									
						52									
						53									
						54									
						55									
						56									
						57									
						58									
						59									
						60									
EXPLANATION										GROUT SAND SCREEN HOLEPLUG BENTONITE CASING WATER LEVEL					

LOCATION MAP										Nellis AFB - Bioventing Pilot Study		PAGE 1 OF 2			
										WELL NUMBER ▶ NE2-MPA		LOCATION ▶ 10' NW of NE2-VW			
										DATE ▶ 1-17-94		WEATHER ▶ Clear, Calm 70°F			
										LOGGED BY ▶ S. Pearson		DRILLED BY ▶ EnviroDrill			
										DRILLING METHOD ▶ 4-1/4" ID Hollow-stem Auger		SAMPLING METHOD ▶ 0' -40' 1.5" S/S 24' 32' 2.0" S/S			
										GRAVEL PACK ▶ Colorado Silica #6-9		SEAL ▶ 1/4" Bentonite			
CASING ▶ TYPE 0.25" ID PVC										DIAMETER 0.5"		LENGTH 24', 32' & 39'		HOLE DIA. 8"	
SCREEN ▶ TYPE Sch 40 PVC SLOT 0.040"										DIAMETER 1"		LENGTH 6"		TOTAL DEPTH 40'	
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS				WELL COMPLETION		
													FLUSH MOUNT		
						0									
						1									
						2									
						3									
						4									
damp			m stiff plas			5			Cuttings - CLAY, pale brown, some silt. (CL)						
						6									
						7									
						8									
						9									
						10									
						11									
						12									
						13									
						14									
damp			soft sl plas			15			0.00'-1.01' CLAY, light yellowish brown, some silt and fine-grained sand, slight hydrocarbon odor. (CL)						
					780	16	1.01	3							
						17		4							
						18		5							
						19									
						20									

EXPLANATION
 GROUT
 BENTONITE

SAND
 CASING

SCREEN
 WATER LEVEL

HOLEPLUG

LOCATION MAP		Nellis AFB - Bioventing Pilot Study		PAGE 2 OF 2						
		WELL NUMBER ► NE2-MPA		LOCATION ► 10' NW of NE2-VW						
		DATE ► 1-17-94		WEATHER ► Clear, Calm 70°F						
		LOGGED BY ► S. Pearson		DRILLED BY ► EnviroDrill						
		DRILLING METHOD ► 4-1/4" ID Hollow-stem Auger		SAMPLING METHOD ► 0' -40' 1.5" S/S 24' 32' 2.0" S/S						
		GRAVEL PACK ► Colorado Silica #6-9		SEAL ► 1/4" Bentonite						
CASING ► TYPE 0.25" ID PVC				DIAMETER 0.5" LENGTH						
SCREEN ► TYPE Sch 40 PVC SLOT 0.040"				DIAMETER 1" LENGTH 6"						
				HOLE DIA. 8"						
				TOTAL DEPTH 40'						
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS	WELL COMPLETION
dry	poor	dense	non			20		50=4"	0.00'-0.78'	
				880		21	0.78	—		
						22		—		
						23				
						24				
dry		stif	x hard	NE2-MPA-24	1600	25		11	0.00'-1.50'	
						26	1.50	50=5.5"	CLAY, light yellowish brown, some silt, partially cemented with CaCO ₃ , brittle, (CH)	
						27		—		
						28				
						29				
dry	poor	v stiff	non			30		36	0.00'-0.45'	
						31	1.11	50=4"	0.45'-1.11'	
dry	poor	v stiff	non	NE2-MPA-32	2500	32	1.00	175	0.00'-1.00'	
						33		100=1"	Refusal at 32.5' - Caliche expected.	
						34		—		
						35		24	0.00'-0.13'	
dry		v stiff	v plas		1200	36	1.50	50=6"	0.13'-1.50'	
						37		—		
						38				
moist		stiff	plas			39			0.00'-1.24'	
						40			CLAY, light yellowish brown, little silt and very fine-grained sand, small caliche lenses at 0.46', stained gray with hydrocarbons, slight odor. (CL)	
<div style="display: flex; justify-content: space-between;"> <div> EXPLANATION GROUT BENTONITE </div> <div> SAND CASING </div> <div> SCREEN WATER LEVEL </div> <div> HOLEPLUG </div> </div>										

LOCATION MAP		Nellis AFB - Bioventing Pilot Study		PAGE <u>1</u> OF <u>2</u>						
		WELL NUMBER ▶	NE2-MPB	LOCATION ▶	15' NW of NE2-MPA					
		DATE ▶	1-17-94	WEATHER ▶	Clear, Calm 70°F					
		LOGGED BY ▶	S. Pearson	DRILLED BY ▶	EnviroDrill					
		DRILLING METHOD ▶	4-1/4" ID Hollow-stem Auger	SAMPLING METHOD ▶	0' -40' 1.5" S/S 24' 32" 2.0" S/S					
		GRAVEL PACK ▶	Colorado Silica #6-9	SEAL ▶	1/4" Bentonite					
CASING ▶ TYPE 0.25" ID PVC		DIAMETER 0.5"		LENGTH 24' 32' & 39'	HOLE DIA. 8"					
SCREEN ▶ TYPE Sch 40 PVC SLOT 0.040"		DIAMETER 1"		LENGTH 6"	TOTAL DEPTH 40'					
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS	WELL COMPLETION
										FLUSH MOUNT
						0				
						1				
						2				
						3				
						4				
damp			m stiff plas			5			Cuttings - CLAY, pale brown, some silt. (CL)	
						6				
						7				
						8				
						9				
						10				
						11				
						12				
						13				
						14				
dry			stiff plas			15		4	0.00'-0.61' CLAY, light yellowish brown, some silt and very fine-grained sand. (CL)	
damp			m stiff plas		58	16	1.50	5	0.61'-1.50' CLAY AND SILT, dark gray, hydrocarbon staining and odor, some very fine-grained sand, some iron staining. (ML)	
						17		6		
						18				
						19			Stained cuttings to 19'	
						20				
EXPLANATION		GROUT SAND SCREEN HOLEPLUG		BENTONITE CASING WATER LEVEL						

LOCATION MAP										Nellis AFB - Bioventing Pilot Study		PAGE 2 OF 2			
										WELL NUMBER ► NE2-MPB		LOCATION ► 15' NW of NE2-MPA			
										DATE ► 1-17-94		WEATHER ► Clear, Calm 70°F			
										LOGGED BY ► S. Pearson		DRILLED BY ► EnviroDrill			
										DRILLING METHOD ► 4-1/4" ID Hollow-stem Auger		SAMPLING METHOD ► 0' -40' 1.5" S/S 24' 32' 2.0" S/S			
										GRAVEL PACK ► Colorado Silica #6-9		SEAL ► 1/4" Bentonite			
CASING ► TYPE 0.25" ID PVC										DIAMETER 0.5"		LENGTH		HOLE DIA. 8"	
SCREEN ► TYPE Sch 40 PVC SLOT 0.040"										DIAMETER 1"		LENGTH 6"		TOTAL DEPTH 40'	
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS				WELL COMPLETION		
dry	poor	v stiff	non	510	510	20	0.87	50=5	0.00'-0.33'	Cavings.					
						21		—	0.33'-0.87'	CLAY, SILT AND SAND, pale brown, very fine-grained, dry and brittle, caliche is expected below. (ML)					
dry				200	200	22	1.50	9	0.00'-1.50'	Hydrocarbon-stained cuttings at 24' CLAY, pale brown, some silt, partially cemented, hydrocarbon staining. (CL)					
						23		10	26						
						24		26							
						25		—							
dry				240	240	26	1.50	300	0.00'-0.50'	Cavings.					
						27		200	0.50'-1.50'	CLAY, SILT AND SAND, pale brown, very fine-grained, well cemented. (ML)					
						28		—							
						29		—							
damp				1200	1200	30	1.50	27	0.00'-1.50'	CLAY, light yellowish brown, some silt, definite vertical fracturing with hydrocarbon staining (see photo). (CL)					
						31		50=4.5							
						32		—							
						33		—							
moist				4600	4600	34	1.50	10	0.00'-0.88'	CLAY, light yellowish brown, little silt and very fine-grained sand. (CL)					
						35		9	13						
						36		—							
						37		—							
moist						38	1.50	—	0.98'-1.50'	CALICHE AND INTERBEDDED CLAY, caliche is white and clay is stained black. (CL)					
						39		—							
40	—														
EXPLANATION															
GROUT SAND SCREEN HOLEPLUG															
BENTONITE CASING WATER LEVEL															

LOCATION MAP		Nellis AFB - Bioventing Pilot Study		PAGE <u>1</u> OF <u>2</u>						
		WELL NUMBER ▶ NE2-MPC	LOCATION ▶ 15' NW of NE2-MPA							
		DATE ▶ 1-18-94	WEATHER ▶ Clear, Calm 70°F							
		LOGGED BY ▶ S. Pearson	DRILLED BY ▶ EnviroDrill							
		DRILLING METHOD ▶ 4-1/4" ID Hollow-stem Auger	SAMPLING METHOD ▶ 2' x 1.5" S/S							
		GRAVEL PACK ▶ Colorado Silica #6-9	SEAL ▶ 1/4" Bentonite							
CASING ▶ TYPE 0.25" ID PVC		DIAMETER 0.5"		LENGTH 24', 32' & 39'	HOLE DIA. 8"					
SCREEN ▶ TYPE Sch 40 PVC SLOT 0.040"		DIAMETER 1"		LENGTH 6"	TOTAL DEPTH 40'					
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS	WELL COMPLETION
										FLUSH MOUNT
						0				
						1				
						2				
						3				
						4				
damp			m stiff plas			5			Cuttings - CLAY, pale brown, some silt.	
						6				
						7				
						8				
						9				
						10				
						11				
						12				
						13				
						14				
damp			m stiff plas			15			0.00'-1.51' CLAY AND SILT, black, hydrocarbon staining, little very fine-grained sand. (CL)	
				830		16	1.51	3		
						17		5		
						18		6		
						19			Hydrocarbon staining to 19'	
						20				
EXPLANATION		GROUT BENTONITE		SAND CASING		SCREEN WATER LEVEL		HOLEPLUG		

LOCATION MAP										Nellis AFB - Bioventing Pilot Study		PAGE 2 OF 2					
										WELL NUMBER ► NE2-MPC		LOCATION ► 15' NW of NE2-MPA					
										DATE ► 1-18-94		WEATHER ► Clear, Calm 70°F					
										LOGGED BY ► S. Pearson		DRILLED BY ► EnviroDrill					
										DRILLING METHOD ► 4-1/4" ID Hollow-stem Auger		SAMPLING METHOD ► 2' x 1.5" S/S					
										GRAVEL PACK ► Colorado Silica #6-9		SEAL ► 1/4" Bentonite					
CASING ► TYPE 0.25" ID PVC										DIAMETER 0.5"		LENGTH		HOLE DIA. 8"			
SCREEN ► TYPE Sch 40 PVC SLOT 0.040"										DIAMETER 1"		LENGTH 6"		TOTAL DEPTH 40'			
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS				WELL COMPLETION				
dry	poor	v stiff	non		1300	20	0.78	50=5"	0.00'-0.25' Cavings. 0.25'-0.78' CLAY, SILT AND SAND, pale brown, very fine-grained, dry and brittle. (ML)								
						21		-									
						22											
						23											
						24											
damp		m stiff	plas		2700	25		4	0.00'-1.52' CLAY AND SILT, pale brown with gray hydrocarbon staining, some very fine-grained sand, caliche lense at 0.38'. (ML)								
						26	1.52	4									
						27		6									
						28											
						29											
damp		m stiff	plas		4100	30		6	0.00'-1.16' CLAY AND SILT, pale brown, slight hydrocarbon staining, some very fine-grained sand and caliche pebbles. (CL)								
						31	1.50	9									
dry		hard	v plas			32		45	1.16'-1.50' CLAY, as above, partially cemented, brittle and dry. (CH)								
						33											
						34											
damp		v stiff	v plas		80	35		8	0.00'-1.50' CLAY, light yellowish brown, some silt, trace of very fine-grained sand. (CH)								
		-hard				36	1.50	18									
						37		39									
						38											
damp-moist		stiff	plas		360	39			0.00'-1.39' CLAY, light yellowish brown, little silt and very fine-grained sand, caliche gravel lense at 0.83', hydrocarbon-stained fractures and sand lenses. (CL)								
						40	1.52										
damp		hard	x hard						1.39'-1.52' CALICHE, gray, hydrocarbon-stained.								
EXPLANATION										GROUT		SAND		SCREEN		HOLEPLUG	
										BENTONITE		CASING		WATER LEVEL			

LOCATION MAP										Nellis AFB - Bioventing Pilot Study		PAGE 1 OF 4			
										WELL NUMBER ▶ NE3-VW		LOCATION ▶ 15' NW of Building 947			
										DATE ▶ 1-19-94		WEATHER ▶ Clear, Calm 60°F			
										LOGGED BY ▶ S. Pearson		DRILLED BY ▶ EnviroDrill			
										DRILLING METHOD ▶ 6-5/8" ID Hollow-stem Auger		SAMPLING METHOD ▶ 0'-30' 1.5" S/S 30'-65' 2.0" S/S			
										GRAVEL PACK ▶ Colorado Silica #6-9 65'-27'		SEAL ▶ Holeplug 22'-3' 1/4" Bentonite 27'-22'			
CASING ▶ TYPE Schedule 40 PVC										DIAMETER 4"		LENGTH 30'		HOLE DIA. 11"	
SCREEN ▶ TYPE Sch 40 PVC SLOT 0.040"										DIAMETER 4"		LENGTH 35'		TOTAL DEPTH 65'	
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS				WELL COMPLETION		
						0			Pilot hole with 4-1/4" ID HSA Overdrill with 6-5/8" ID HSA						
						1									
						2									
						3									
						4									
dry	poor		m stiffsl	plas		5			Cuttings- CLAY, SILT AND SAND, light brown, very fine-grained sand. (SC)						
						6									
						7									
						8									
						9									
damp			m stiffsl	plas		10		4	0.00'-0.27' Cavings.						
					55	11	1.39	6	0.27'-1.39' CLAY AND SAND, light yellowish brown, fine- and very fine-grained. (SC)						
						12		8							
						13									
						14									
						15									
						16									
						17									
						18									
						19									
						20									
EXPLANATION		GROUT SAND		SCREEN		HOLEPLUG		BENTONITE		CASING		WATER LEVEL			

LOCATION MAP										Nellis AFB - Bioventing Pilot Study		PAGE 2 OF 4			
										WELL NUMBER ► NE3-VW		LOCATION ► 15' NW of Building 947			
										DATE ► 1-19-94		WEATHER ► Clear, Calm 60°F			
										LOGGED BY ► S. Pearson		DRILLED BY ► EnviroDrill			
										DRILLING METHOD ► 6-5/8" ID Hollow-stem Auger		SAMPLING METHOD ► 0' -30' 1.5" S/S 30'-65' 2.0" S/S			
										GRAVEL PACK ► Colorado Silica #6-9 65'-27'		SEAL ► Holeplug 22'-3' 1/4" Bentonite 27'-22'			
CASING ► TYPE Schedule 40 PVC										DIAMETER 4"		LENGTH 30'		HOLE DIA. 11"	
SCREEN ► TYPE Sch 40 PVC SLOT 0.040"										DIAMETER 4"		LENGTH 35'		TOTAL DEPTH 65'	
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS		WELL COMPLETION				
damp		m stiff	pl		56	20	1.49	5	0.00'-0.33'	Cavings.					
						21		9	0.33'-1.25'	Clay, light yellowish brown, some fine- and very fine-grained sand, little silt, mottled. (CL)					
dry		m stiff	pl			22		10	1.25'-1.49'	CLAY AND SAND, light brown, fine-grained, some silt, (SC)					
						23									
						24									
damp		soft	sl		56	25	0.80	6	0.00'-0.80'	CLAY, light yellowish brown, some fine-grained sand, little silt and very fine-grained sand, slight mottling. (CL)					
						26		5							
						27									
						28									
						29									
damp		m stiff	pl		58	30		17	0.00'-1.50'	CLAY, pale brown, little silt and very fine-grained sand, trace of caliche pebbles. (CL)					
						31	1.50	7							
						32		7							
						33									
						34									
						35		4	0.00'-1.30'	CLAY, as above.					
damp		m stiff	pl		54	36	1.50	13	1.30'-1.50'	CALICHE, white to light brown, hard and massive.					
dry		hard	x hard			37		50=3.5"							
						38									
						39									
						40									
EXPLANATION															

LOCATION MAP										Nellis AFB - Bioventing Pilot Study		PAGE 3 OF 4	
										WELL NUMBER ▶ NE3-VW		LOCATION ▶ 15' NW of Building 947	
										DATE ▶ 1-19-94		WEATHER ▶ Clear, Calm 60°F	
										LOGGED BY ▶ S. Pearson		DRILLED BY ▶ EnviroDrill	
										DRILLING METHOD ▶ 6-5/8" ID Hollow-stem Auger		SAMPLING METHOD ▶ 0' -30' 1.5" S/S 30'-65' 2.0" S/S	
										GRAVEL PACK ▶ Colorado Silica #6-9 65'-27'		SEAL ▶ Holeplug 22'-3' 1/4" Bentonite 27'-22'	
CASING ▶ TYPE Schedule 40 PVC DIAMETER 4" LENGTH 30' HOLE DIA. 11"													
SCREEN ▶ TYPE Sch 40 PVC SLOT 0.040" DIAMETER 4" LENGTH 35' TOTAL DEPTH 65'													
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS		WELL COMPLETION		
damp		stiff	plas	NE3-VW-40	92	40		20	0.00'-1.30' CLAY, pale brown, some silt, fine- and very fine-grained sand, trace of caliche gravel. (CL)				
						41	1.30	19					
								18					
						42							
						43							
						44							
damp dry		v stiff hard	plas x hard	NE3-VW-45	57	45		19	0.00'-0.80' CLAY, as above. 0.80'-1.20' CALICHE, light brown, massive.				
						46	1.20	32					
								30					
						47							
						48							
						49							
dry moist		hard mod m	v hard dense non	NE3-VW-50	7500	50		15	0.00'-0.40' CALICHE, massive, pale brown. 0.40'-1.50' SAND, pale brown, fine- and very fine-grained, trace of silt, trace of hydrocarbon staining. (SM)				
						51	1.50	12					
								50					
						52							
						53							
						54							
damp moist	poor	m stiff	plas	NE3-VW-55	1400	55		8	0.00'-1.50' SAND AND CLAY, pale brown, fine- and very fine-grained sand, some silt, little hydrocarbon staining, little amount of caliche pebbles. (SC)				
						56	1.50	15					
								17					
						57							
						58							
						59							
						60							
EXPLANATION										GROUT SAND SCREEN HOLEPLUG BENTONITE CASING WATER LEVEL			

LOCATION MAP										Well Number		Location					
										NE3-VW		15' NW of Building 947					
										DATE		1-19-94		WEATHER		Clear, Calm 60°F	
										LOGGED BY		S. Pearson		DRILLED BY		EnviroDrill	
										DRILLING METHOD		6-5/8" ID Hollow-stem Auger		SAMPLING METHOD		0' -30' 1.5" S/S 30'-65' 2.0" S/S	
										GRAVEL PACK		Colorado Silica #6-9 65'-27'		SEAL		Holeplug 22'-3' 1/4" Bentonite 27'-22'	
CASING										TYPE Schedule 40 PVC		DIAMETER 4"		LENGTH 30'		HOLE DIA. 11"	
SCREEN										TYPE Sch 40 PVC SLOT 0.040"		DIAMETER 4"		LENGTH 35'		TOTAL DEPTH 65'	
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS				WELL COMPLETION				
moist -wet		m stiff	plas	NE3-VW-60	750	60		10	0.00'-1.50' CLAY, pale brown, some silt and very fine-grained sand, little amount of caliche pebbles, hydrocarbon odor. (CL)								
						61	1.50	14									
						62		15									
						63			0.00'-1.00' CALICHE, light yellowish brown, gravelly, some clay and silt, saturated, strong hydrocarbon odor. (GC)								
						64											
						65		35									
sat		hard x hard		NE3-VW-65	>10,000	65		18	1.00'-1.50' CLAY, light yellowish brown, some fine- and very fine-grained sand, some silt. (CH)								
						66	1.50	15									
						67											
moist -wet		v stiff v	plas			68											
						69											
						70											
						71											
						72											
						73											
						74											
						75											
						76											
						77											
						78											
						79											
						80											
EXPLANATION																	
GROUT SAND SCREEN HOLEPLUG																	
BENTONITE CASING WATER LEVEL																	

LOCATION MAP

Nellis AFB - Bioventing Pilot Study

PAGE 1 OF 4

WELL NUMBER ▶ NE3-MPA

LOCATION ▶ 15' N of NE3-VW

DATE ▶ 1-20-94

WEATHER ▶ Clear, Calm - 35°F
Midnight Drilling

LOGGED BY ▶ S. Pearson

DRILLED BY ▶ EnviroDrill

DRILLING METHOD ▶ 4-1/4" ID Hollow-stem Auger

SAMPLING METHOD ▶ 0' -60' 1.5" S/S
42' 2.0" S/S

GRAVEL PACK ▶ Colorado Silica #6-9

SEAL ▶ Holeplug
1/4" Bentonite

CASING ▶ TYPE 0.25" ID PVC

DIAMETER 0.5"

LENGTH 30', 40', 50' & 60'

HOLE DIA. 8"

SCREEN ▶ TYPE Sch 40 PVC SLOT 0.040"

DIAMETER 1"

LENGTH 6"

TOTAL DEPTH 60'

MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS	WELL COMPLETION
						0				
						1				
						2				
						3				
						4				
						5				
						6				
						7				
						8				
						9				
damp		soft sl plas				10		3	0.00'-0.33' Cavings.	
				320		11	1.13	3	0.33'-1.13' CLAY, pale brown, some silt and very fine-grained sand. (CL)	
						12		4		
						13				
						14				
						15				
						16				
						17				
						18				
						19				
						20				

EXPLANATION

GROUT

SAND

SCREEN

HOLEPLUG

BENTONITE

CASING

WATER LEVEL

LOCATION MAP										Nellis AFB - Bioventing Pilot Study		PAGE 2 OF 4			
										WELL NUMBER ► NE3-MPA		LOCATION ► 15' N of NE3-VW			
										DATE ► 1-20-94		WEATHER ► Clear, Calm - 35°F Midnight Drilling			
										LOGGED BY ► S. Pearson		DRILLED BY ► EnviroDrill			
										DRILLING METHOD ► 4-1/4" ID Hollow-stem Auger		SAMPLING METHOD ► 0' -60' 1.5" S/S 42' 2.0" S/S			
										GRAVEL PACK ► Colorado Silica #6-9		SEAL ► Holeplug 1/4" Bentonite			
CASING ► TYPE 0.25" ID PVC										DIAMETER 0.5"		LENGTH 30', 40', 50' & 60'		HOLE DIA. 8"	
SCREEN ► TYPE Sch 40 PVC SLOT 0.040"										DIAMETER 1"		LENGTH 6"		TOTAL DEPTH 60'	
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS				WELL COMPLETION		
dry	poor	m dense	non			20		6	0.00'-1.50' SAND, pale brown, some silt and clay. (SM)						
				78	1.50	10									
						20									
damp	m stiff	sl pas			21			0.00'-1.51' CLAY, light yellowish brown, some silt, fine and very fine-grained sand. (CL)							
			94	1.51	4										
					5										
damp-moist	stiff	v plas			22			0.00'-0.50' Cavings. 0.50'-1.11' CLAY, pale brown, little silt and very fine-grained sand. (CH)							
			100	1.11	2										
					4										
damp	stiff	plas-hard			23			0.00'-0.31' Cavings 0.31'-1.41' CLAY AND CALICHE, pale brown, some silt and very fine-grained sand, partially and preferentially cemented, caliche is interbedded. (CH)							
			120	1.41	32										
					42										
					24										
						25									
						26									
						27									
						28									
						29									
						30									
						31									
						32									
						33									
						34									
						35									
						36									
						37									
						38									
						39									
						40									

EXPLANATION	GROUT	SAND	SCREEN	HOLEPLUG
	BENTONITE	CASING	WATER LEVEL	

LOCATION MAP										Nellis AFB - Bioventing Pilot Study		PAGE 3 OF 4			
										WELL NUMBER ► NE3-MPA		LOCATION ► 15' N of NE3-VW			
										DATE ► 1-20-94		WEATHER ► Clear, Calm - 35°F Midnight Drilling			
										LOGGED BY ► S. Pearson		DRILLED BY ► EnviroDrill			
										DRILLING METHOD ► 4-1/4" ID Hollow-stem Auger		SAMPLING METHOD ► 0' -60' 1.5" S/S 42' 2.0" S/S			
										GRAVEL PACK ► Colorado Silica #6-9		SEAL ► Holeplug 1/4" Bentonite			
CASING ► TYPE 0.25" ID PVC										DIAMETER 0.5"		LENGTH 30', 40', 50' & 60'		HOLE DIA. 8"	
SCREEN ► TYPE Sch 40 PVC SLOT 0.040"										DIAMETER 1"		LENGTH 6"		TOTAL DEPTH 60'	
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS				WELL COMPLETION		
damp	mod	loose	non-sl plas			40		7	0.00' - 1.50' SAND, light yellowish brown, fine and very fine-grained sand, little clay and silt. (SC)						
				120		41	1.5	7							
								9							
damp		m stiff	plas			42		4	0.00' - 1.50' CLAY, light yellowish brown, little silt and very fine-grained sand. (CL)						
				150		43	1.50	5							
								7							
moist		m stiff	sl plas			44			0.00' - 1.50' CLAY, light yellowish brown, little silt, trace of very fine-grained sand. (CL)						
						45		5							
				250		46	1.50	3							
						47		7							
						48									
						49									
damp -wet	poor	m stiff	sl plas			50		10	0.00' - 0.97' CLAY, SILT AND SAND, light yellowish brown, fine- and very fine-grained sand, hydrocarbon odor. (SC)						
				7200		51	0.97	12							
								14							
						52			0.00' - 0.87' CLAY, light yellowish brown, little silt, little caliche pebbles, trace of very fine-grained sand. (CL)						
						53									
						54									
damp		m stiff	plas			55		5							
				2000		56	0.87	10							
								6							
						57									
						58									
						59									
						60									
EXPLANATION		GROUT		SAND		SCREEN		HOLEPLUG							
		BENTONITE		CASING		WATER LEVEL									

LOCATION MAP 		Nellis AFB - Bioventing Pilot Study		PAGE 4 OF 4
WELL NUMBER ▶ NE3-MPA		LOCATION ▶ 15' N of NE3-VW		
DATE ▶ 1-20-94		WEATHER ▶ Clear, Calm - 35°F Midnight Drilling		
LOGGED BY ▶ S. Pearson		DRILLED BY ▶ EnviroDrill		
DRILLING METHOD ▶ 4-1/4" ID Hollow-stem Auger		SAMPLING METHOD ▶ 0' -60' 1.5" S/S 42' 2.0" S/S		
GRAVEL PACK ▶ Colorado Silica #6-9		SEAL ▶ Holeplug 1/4" Bentonite		

CASING ▶ TYPE 0.25" ID PVC **DIAMETER** 0.5" **LENGTH** 30', 40', 50' & 60' **HOLE DIA.** 8"

SCREEN ▶ TYPE Sch 40 PVC SLOT 0.040" **DIAMETER** 1" **LENGTH** 6" **TOTAL DEPTH** 60'

MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPH)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS	WELL COMPLETION
damp		stiff	plas			60		7	0.00'-1.50' CLAY, light yellowish brown, some silt, little fine-grained sand. (CL)	
					1300	61	1.50	10		
								11		
						62				
						63				
						64				
						65				
						66				
						67				
						68				
						69				
						70				
						71				
						72				
						73				
						74				
						75				
						76				
						77				
						78				
						79				
						80				

EXPLANATION GROUT BENTONITE	SAND CASING	SCREEN WATER LEVEL	HOLEPLUG
--	----------------	-----------------------	----------

LOCATION MAP										Nellis AFB - Bioventing Pilot Study		PAGE 1 OF 4			
										WELL NUMBER ► NE3-MPB		LOCATION ► 15' N of NE3-MPA			
										DATE ► 1-19-94		WEATHER ► Clear, Calm - 50°F Midnight Drilling			
										LOGGED BY ► S. Pearson		DRILLED BY ► EnviroDrill			
										DRILLING METHOD ► 4-1/4" ID Hollow-stem Auger		SAMPLING METHOD ► 0'-60' 1.5" S/S 30'.40'.50' 2.0" S/S			
										GRAVEL PACK ► Colorado Silica #6-9		SEAL ► Holeplug 1/4" Bentonite			
CASING ► TYPE 0.25" ID PVC										DIAMETER 0.5"		LENGTH 30'.40'.50' & 60'		HOLE DIA. 8"	
SCREEN ► TYPE Sch 40 PVC SLOT 0.040"										DIAMETER 1"		LENGTH 6"		TOTAL DEPTH 60'	
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS				WELL COMPLETION		
													FLUSH MOUNT		
						0									
						1									
						2									
						3									
						4									
						5									
						6									
						7									
						8									
						9									
damp						10			0.00'-1.50' CLAY AND SILT, light yellowish brown, little fine- and very fine-grained sand. (ML)						
	soft	sl	plas		64	1.50	4								
		-non					5								
						11		7							
						12									
						13									
						14									
						15									
						16									
						17									
						18									
						19									
						20									

EXPLANATION
 GROUT
 BENTONITE

SAND
 CASING

SCREEN
 WATER LEVEL

HOLEPLUG

LOCATION MAP		Nellis AFB - Bioventing Pilot Study		PAGE 2 OF 4						
		WELL NUMBER ▶ NE3-MPB	LOCATION ▶ 15' N of NE3-MPA							
		DATE ▶ 1-19-94	WEATHER ▶ Clear, Calm - 50°F Midnight Drilling							
		LOGGED BY ▶ S. Pearson	DRILLED BY ▶ EnviroDrill							
		DRILLING METHOD ▶ 4-1/4" ID Hollow-stem Auger	SAMPLING METHOD ▶ 0'-60' 1.5" S/S 30' 40' 50' 2.0" S/S							
		GRAVEL PACK ▶ Colorado Silica #6-9	SEAL ▶ Holeplug 1/4" Bentonite							
CASING ▶ TYPE 0.25" ID PVC		DIAMETER 0.5"		LENGTH 30', 40', 50' & 60'	HOLE DIA. 8"					
SCREEN ▶ TYPE Sch 40 PVC SLOT 0.040"		DIAMETER 1"		LENGTH 6"	TOTAL DEPTH 60'					
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS	WELL COMPLETION
damp		soft	sl plas -non		110	20		3	0.00'-1.25'	CLAY, pale brown, some silt, trace of fine- and very fine-grained sand. (CL)
						21	1.25	6		
						22		3		
damp		soft	sl plas		65	25		3	0.00'-0.40'	CLAY, pale brown, little silt and very fine grained sand, caliche nodules at 0.4'. (CL)
damp	poor	loose	non			26	1.50	4	0.40'-1.50'	
						27		7		SAND AND CLAY, light yellowish brown, some silt, fine- and very fine-grained sand. (SC)
						28				
damp-moist		soft	sl plas		62	30		2	0.00'-0.50'	Cavings. CLAY, light yellowish brown, little silt, trace of fine- and very fine-grained sand. (CL)
						31	1.50	2	0.50'-1.50'	
						32		4		
moist dry		soft	sl plas		130	35		50-3.5"	0.00'-0.35'	CLAY, as above.
		loose	non			36	0.55		0.35'-0.55'	
						37				SILT, light brown, partially cemented, consistency of flour. (ML)
						38				
						39				
						40				
<div style="display: flex; justify-content: space-between; align-items: center;"> <div> EXPLANATION GROUT BENTONITE </div> <div> SAND CASING </div> <div> SCREEN WATER LEVEL </div> <div> HOLEPLUG </div> </div>										

LOCATION MAP		Nellis AFB - Bioventing Pilot Study		PAGE 3 OF 4						
		WELL NUMBER ▶ NE3-MPB	LOCATION ▶ 15' N of NE3-MPA							
		DATE ▶ 1-19-94	WEATHER ▶ Clear, Calm - 50°F Midnight Drilling							
		LOGGED BY ▶ S. Pearson	DRILLED BY ▶ EnviroDrill							
		DRILLING METHOD ▶ 4-1/4" ID Hollow-stem Auger	SAMPLING METHOD ▶ 0'-60' 1.5" S/S 30' 40' 50' 2.0" S/S							
		GRAVEL PACK ▶ Colorado Silica #6-9	SEAL ▶ Holeplug 1/4" Bentonite							
CASING ▶ TYPE 0.25" ID PVC		DIAMETER 0.5"		LENGTH 30', 40', 50' & 60'						
SCREEN ▶ TYPE Sch 40 PVC SLOT 0.040"		DIAMETER 1"		LENGTH 6"						
TOTAL DEPTH 60'										
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS	WELL COMPLETION
damp-moist		stiff	plas	NE3-MPB-40	115	40		11	0.00'-1.50' CLAY, light yellowish brown, some silt and very fine-grained sand. (CL)	
						41	1.50	25		
						42		25		
						43				
						44				
						45		10	0.00'-0.72' CALICHE, pale brown to white.	
dry damp		hard m stiff	hard x plas		180	46	1.50	7	0.72'-1.50' CLAY, light yellowish brown, some silt and very fine-grained sand. (CL)	
						47		7		
						48				
						49				
						50		12	0.00'-0.50' Cavings.	
moist-wet	mod	dnes	sl plas	NE3-MPB-50	6200	51	1.50	29	0.50'-1.50' SAND AND CLAY, light yellowish brown, fine-grained, little very fine-grained sand. (SC)	
						52		40		
						53				
						54				
damp		stiff	v plas		9500	55		7	0.00'-1.50' CLAY, pale brown, little silt and very fine-grained sand, caliche in sampler shoe. (CH)	
						56	1.50	50=3"		
						57				
						58				
						59				
						60				
<div style="display: flex; justify-content: space-between; align-items: center;"> <div> EXPLANATION GROUT BENTONITE </div> <div> SAND CASING </div> <div> SCREEN WATER LEVEL </div> <div> HOLEPLUG </div> </div>										

LOCATION MAP										Nellis AFB - Bioventing Pilot Study		PAGE 4 OF 4			
										WELL NUMBER ► NE3-MPB		LOCATION ► 15' N of NE3-MPA			
										DATE ► 1-19-94		WEATHER ► Clear, Calm - 50°F Midnight Drilling			
										LOGGED BY ► S. Pearson		DRILLED BY ► EnviroDrill			
										DRILLING METHOD ► 4-1/4" ID Hollow-stem Auger		SAMPLING METHOD ► 0'-60' 1.5" S/S 30' 40' 50' 2.0" S/S			
										GRAVEL PACK ► Colorado Silica #6-9		SEAL ► Holeplug 1/4" Bentonite			
CASING ► TYPE 0.25" ID PVC										DIAMETER 0.5"		LENGTH 30', 40', 50' & 60'		HOLE DIA. 8"	
SCREEN ► TYPE Sch 40 PVC SLOT 0.040"										DIAMETER 1"		LENGTH 6"		TOTAL DEPTH 60'	
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS				WELL COMPLETION		
moist		m stiff	plas			60									
						61			0.00'-1.50' CLAY, light yellowish brown, some silt and very fine-grained sand. (CL)						
						62									
						63									
						64									
						65									
						66									
						67									
						68									
						69									
						70									
						71									
						72									
						73									
						74									
						75									
						76									
						77									
						78									
						79									
						80									
EXPLANATION		GROUT		SAND		SCREEN		HOLEPLUG							
		BENTONITE		CASING		WATER LEVEL									

LOCATION MAP										Nellis AFB - Bioventing Pilot Study		PAGE 1 OF 4			
										WELL NUMBER ▶ NE3-MPC		LOCATION ▶ 25' N of NE3-MPB			
										DATE ▶ 1-19-94		WEATHER ▶ Clear, Calm 60°F			
										LOGGED BY ▶ S. Pearson		DRILLED BY ▶ EnviroDrill			
										DRILLING METHOD ▶ 4-1/4" ID Hollow-stem Auger		SAMPLING METHOD ▶ 0'-50' 1.5" Split Spoon			
										GRAVEL PACK ▶ Colorado Silica #6-9		SEAL ▶ Holeplug 1/4" Bentonite			
CASING ▶ TYPE 0.25" ID PVC										DIAMETER 0.5"		LENGTH 30', 40', 50' & 60'		HOLE DIA. 8"	
SCREEN ▶ TYPE Sch 40 PVC SLOT 0.040"										DIAMETER 1"		LENGTH 6"		TOTAL DEPTH 50'	
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPH)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS				WELL COMPLETION		
												FLUSH MOUNT			
						0									
						1									
						2									
						3									
						4									
						5									
						6									
						7									
						8									
						9									
						10			No Recovery.						
						11									
						12									
						13			13.5'-16' Driller reports caliche. Hard Drilling.						
						14									
						15									
						16									
						17									
						18									
						19									
						20									
EXPLANATION		GROUT		SAND		SCREEN		HOLEPLUG							
		BENTONITE		CASING		WATER LEVEL									

LOCATION MAP		Nellis AFB - Bioventing Pilot Study		PAGE 2 OF 4						
		WELL NUMBER ▶ NE3-MPC	LOCATION ▶ 25' N of NE3-MPB							
		DATE ▶ 1-19-94	WEATHER ▶ Clear, Calm 60°F							
		LOGGED BY ▶ S. Pearson	DRILLED BY ▶ EnviroDrill							
		DRILLING METHOD ▶ 4-1/4" ID Hollow-stem Auger	SAMPLING METHOD ▶ 0'-50' 1.5" Split Spoon							
		GRAVEL PACK ▶ Colorado Silica #6-9	SEAL ▶ Holeplug 1/4" Bentonite							
CASING ▶ TYPE 0.25" ID PVC		DIAMETER 0.5"		LENGTH 30', 40', 50' & 60'	HOLE DIA. 8"					
SCREEN ▶ TYPE Sch 40 PVC SLOT 0.040"		DIAMETER 1"		LENGTH 6"	TOTAL DEPTH 50'					
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS	WELL COMPLETION
dry		m dense non			4300	20		5	0.00'-0.42' Cavings.	
dry		hard x hard				21	0.74	9	0.42'-0.65' CLAY, SILT AND SAND, pale brown, very fine-grained. (SC)	
						22		10	0.65'-0.74' CALICHE, white, massive.	
						23				
						24				
damp	poor	loose	non-			25		7	0.21'-1.50' CLAY AND SAND, light yellowish brown, fine- and very fine-grained, some silt. (SC)	
		m dense plas			1500	26	1.50	7		
						27		9		
						28				
						29				
						30		3	No Recovery-CALICHE. Headspace sample collected from cuttings.	
					2000	31	NA	6		
						32		10		
						33				
						34				
dry	poor	hard	non			35		50-4"	0.00'-0.21' Cavings.	
dry	poor	hard	non		110	36	0.48		0.21'-0.48' SAND, light brown, very fine-grained, some silt and fine-grained sand, trace of clay, cemented. (SM)	
						37				
						38				
						39				
						40				
<div style="display: flex; justify-content: space-between; font-size: small;"> <div> EXPLANATION GROUT BENTONITE </div> <div> SAND CASING </div> <div> SCREEN WATER LEVEL </div> <div> HOLEPLUG </div> </div>										

LOCATION MAP										Nellis AFB - Bioventing Pilot Study		PAGE 3 OF 4			
										WELL NUMBER ► NE3-MPC		LOCATION ► 25' N of NE3-MPB			
										DATE ► 1-19-94		WEATHER ► Clear, Calm 60°F			
										LOGGED BY ► S. Pearson		DRILLED BY ► EnviroDrill			
										DRILLING METHOD ► 4-1/4" ID Hollow-stem Auger		SAMPLING METHOD ► 0'-50' 1.5" Split Spoon			
										GRAVEL PACK ► Colorado Silica #6-9		SEAL ► Holeplug 1/4" Bentonite			
CASING ► TYPE 0.25" ID PVC										DIAMETER 0.5"		LENGTH 30', 40', 50' & 60'		HOLE DIA. 8"	
SCREEN ► TYPE Sch 40 PVC SLOT 0.040"										DIAMETER 1"		LENGTH 6"		TOTAL DEPTH 50'	
MOISTURE CONTENT	SORTING	DENSITY	PLASTICITY	SAMPLE NUMBER	TIP READING (PPM)	DEPTH	SAMPLE RECOVERY	PENETRATION RESISTANCE	LITHOLOGY/REMARKS				WELL COMPLETION		
dry	poor	dense	non		70	40		95	0.00'-0.46' Cavings.						
damp	mod	dense	sl plas			41	1.08	23	0.46'-1.08' SAND AND SILT, light brown, fine- and very fine-grained, cemented. (SM)						
						42		37	1.08'-1.50' SAND, light yellowish brown, fine- and very fine-grained, little silt and clay, (SM)						
						43									
						44									
dry	poor	dense	non		140	45		40	0.00'-0.49' SILT AND SAND, light brown, fine- and very fine-grained sand, trace of clay. (SM)						
						46	1.49	31							
						47		20							
						48									
						49									
wet		soft	sl plas			50		5	0.00'-0.21' CLAY, light yellowish brown, trace of silt and very fine-grained sand. (CL)						
wet		m stiff	sl plas		>10,000	51	1.50	16	0.21'-1.50' CLAY, SILT AND SAND, grayish white, very fine-grained, trace of caliche pebbles, interbedded massive caliche. (SC)						
						52		26							
						53									
						54			Encounter groundwater between 51.5' and 55'						
						55			No Recovery-Saturated sample fell from sampler.						
						56									
						57									
						58									
						59									
						60									
EXPLANATION															



AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

180 BLUE RAVINE ROAD, SUITE B
FOLSOM, CA 95630
(916) 985-1000 • FAX (916) 985-1020

CHAIN OF CUSTODY RECORD

Page 1 of 1

PROJECT # 722408.50010 PO # 722408.50010 COLLECTED BY (Signature) [Signature]

REMARKS WELLS AFB - BIOVENTING - THREE SITES

FIELD SAMPLE I.D.#	SAMPLING MEDIA (Tenax, Canister etc.)	DATE/TIME	ANALYSIS	VAC./PRESSURE	LAB I.D. #
NE3-MPA-50	CANISTER (SUMMA)	1/26/94 / 0727	TO-3 (STEX/TPH)	0.5" Hg	
NE2-VW		1/25/94 - 1151		8.0" Hg	
NE2-MPC-39		1/25/94 - 1507		1.5" Hg	
NE1-MPA-55		1/26/94 - 0932		0.5" Hg	
NE1-MPC-70		1/25/94 - 1021		1.0" Hg	
NE1-VW		1/25/94 - 0858		0.5" Hg	
NE3-MPC-30		1/26/94 - 0831		1.5" Hg	
NE2-MPA-32		1/25/94 - 1425		2.0" Hg	
NE3-VW		1/25/94 - 1609		2.0" Hg	

RELINQUISHED BY: DATE/TIME 1/26/94 1630 RECEIVED BY: DATE/TIME 1/26/94 1615
[Signature] FED EX 1/26/94/1630 [Signature]

LAB USE ONLY

SHIPPER NAME AIR BILL # OPENED BY: DATE/TIME TEMP(°C) CONDITION

REMARKS Custody seals not present

CHAIN OF CUSTODY RECORD

[illegible]

cc85011


一

WCHS01L

Respiration Test																	
Site 27																	
Nellis AFB, Nevada																	
Monitoring Point	Date	Days Elapsed (frac. days)	Hrs elapsed (fractional days)	Days Elapsed	Time	Elapsed Time (min. x 1000)	O2%	CO2%	Hydro-carbon	Helium	Comments	Trend of O2/ Time	New x-values	k			
															Begin Respiration Test		
VW	01/27/94	0.00	08:14	0.00	0.00	0.00	20.6	0.50	4.800	2.1		19.168388		0	0.003761		
VW	01/27/94	0.00	09:14	0.04	0.04	0.06	19.2	0.50	6.600	1.9		11.722534		1.98			
VW	01/27/94	0.00	12:14	0.17	0.17	0.24	17.5	0.60	9.200	1.7							
VW	01/27/94	0.00	17:14	0.38	0.38	0.54	16.2	0.90	13.600	1.7							
VW	01/27/94	0.00	22:14	0.58	0.58	0.84	15.8	1.00	15.600	1.7							
VW	01/28/94	1.00	08:14	0.00	1.00	1.44	13.0	1.50	19.200	1.7							
VW	01/28/94	1.00	17:14	0.38	1.38	1.98	12.7	1.75	19.200	1.4							
VW	01/29/94	2.00	09:14	0.04	2.04	2.94	11.6	2.00	>20,000	1.7							
VW	01/29/94	2.00	17:17	0.38	2.38	3.42	12.2	2.00	>20,000	1.6							
VW	01/30/94	3.00	11:14	0.13	3.13	4.50	11.2	2.50	>20,000	1.3							
VW	01/31/94	4.00	08:14	0.00	4.00	5.76	10.2	2.60	>20,000	1.6							
VW	02/01/94	5.00	08:30	0.01	5.01	7.22	10.7	2.50	>20,000	1.5							
VW	02/05/94	9.00	09:19	0.05	9.05	13.03	9.9	3.30	>20,000	1.4							
MPA-70	01/27/94	0.00	08:20	0.00	0.00	0.01	20.2	0.20	6.400	2.0		19.871905		0	0.000488		
MPA-70	01/27/94	0.00	09:19	0.05	0.05	0.07	20.0	0.20	14.200	2.1		16.34955		7.22			
MPA-70	01/27/94	0.00	12:19	0.17	0.17	0.25	19.5	0.20	16,000	1.8							
MPA-70	01/27/94	0.00	22:20	0.59	0.59	0.85	19.4	0.35	20,000	1.9							
MPA-70	01/28/94	1.00	08:19	0.00	1.00	1.45	19.1	0.45	>20,000	1.9							
MPA-70	01/29/94	2.00	09:19	0.05	2.05	2.95	18.2	0.60	>20,000	1.8							
MPA-70	01/30/94	3.00	11:30	0.14	3.14	4.52	17.7	0.60	>20,000	1.3							
MPA-70	01/31/94	4.00	08:19	0.00	4.00	5.77	17.0	0.75	>20,000	1.9							
MPA-70	02/01/94	5.00	08:35	0.01	5.01	7.22	16.5	0.60	>20,000	1.3							
MPA-70	02/05/94	9.00	09:25	0.05	9.05	13.03	16.5	0.60	>20,000	1.3							
MPA-55	01/27/94	0.00	08:23	0.01	0.01	0.01	16.1	10.10	12,800	1.5		16.267884		0	5.48E-05		
MPA-55	01/27/94	0.00	09:22	0.05	0.05	0.07	16.1	10.50	11,400	1.4		15.553857		13.03			
MPA-55	01/27/94	0.00	12:22	0.17	0.17	0.25	16.0	10.50	10,000	1.6							
MPA-55	01/27/94	0.00	22:23	0.59	0.59	0.85	16.5	10.50	10,000	1.7							
MPA-55	01/28/94	1.00	08:22	0.01	1.01	1.45	16.5	10.90	10,000	1.6							
MPA-55	01/29/94	2.00	09:22	0.05	2.05	2.95	16.2	10.40	10,000	1.5							
MPA-55	01/30/94	3.00	11:27	0.13	3.13	4.51	16.0	11.00	11,400	1.2							
MPA-55	01/31/94	4.00	08:23	0.01	4.01	5.77	15.9	10.90	12,000	1.6							
MPA-55	02/01/94	5.00	08:39	0.02	5.02	7.23	15.9	10.90	12,000	1.5							
MPA-55	02/05/94	9.00	09:28	0.05	9.05	13.03	15.5	10.90	12,400	1.1							
MPB-70	01/27/94	0.00	08:27	0.01	0.01	0.01	19.8	1.00	>20,000	1.8		19.208583		0	0.000265		
MPB-70	01/27/94	0.00	09:27	0.05	0.05	0.07	19.7	0.80	>20,000	1.9		15.751936		13.04			
MPB-70	01/27/94	0.00	12:26	0.18	0.18	0.25	18.9	0.70	>20,000	1.7							
MPB-70	01/27/94	0.00	22:29	0.59	0.59	0.86	19.0	0.80	>20,000	1.8							
MPB-70	01/28/94	1.00	08:26	0.01	1.01	1.45	18.9	0.80	>20,000	1.6							
MPB-70	01/29/94	2.00	09:28	0.05	2.05	2.95	17.9	0.90	>20,000	1.6							
MPB-70	01/30/94	3.00	11:36	0.14	3.14	4.52	17.7	0.90	>20,000	1.2							
MPB-70	01/31/94	4.00	08:27	0.01	4.01	5.77	17.3	0.90	>20,000	1.9							
MPB-70	02/01/94	5.00	08:44	0.02	5.02	7.23	17.0	0.90	>20,000	1.6							
MPB-70	02/05/94	9.00	09:32	0.05	9.05	13.04	16.3	0.90	>20,000	1.4							
Test																	Page 1

MPB-55	01/27/94	0.00	08:31	0.01	0.01	0.02	20.5	0.10	440	2.2	20.297627	0	0.000535
MPB-55	01/27/94	0.00	09:31	0.05	0.05	0.08	20.1	0.20	760	2.2	16.432975	7.23	
MPB-55	01/27/94	0.00	12:30	0.18	0.18	0.26	19.8	0.09	1,160	2.1			
MPB-55	01/27/94	0.00	22:32	0.60	0.60	0.86	19.9	0.20	2,400	2.1			
MPB-55	01/28/94	1.00	08:30	0.01	1.01	1.46	19.8	0.50	3,200	2.0			
MPB-55	01/29/94	2.00	09:32	0.05	2.05	2.96	18.6	0.60	5,400	1.8			
MPB-55	01/30/94	3.00	11:40	0.14	3.14	4.53	18.0	0.70	7,000	1.3			
MPB-55	01/31/94	4.00	08:30	0.01	4.01	5.78	16.9	0.80	8,800	1.8			
MPB-55	02/01/94	5.00	08:48	0.02	5.02	7.23	16.6	0.95	11,000	1.5			
MPB-55	02/05/94	9.00	09:35	0.06	9.06	13.04	15.4	1.10	10,600	1.2			
MPB-55	02/05/94	9.00	09:35	0.06	9.06	13.04	15.4	1.10	10,600	1.2			
MPC-70	01/27/94	0.00	08:36	0.02	0.02	0.02	20.0	0.80	>20,000	1.7	19.076459	0	0.000286
MPC-70	01/27/94	0.00	09:36	0.08	0.08	0.08	19.1	0.90	>20,000	1.7	15.347551	13.04	
MPC-70	01/27/94	0.00	12:35	0.18	0.18	0.26	18.9	0.70	>20,000	1.7			
MPC-70	01/27/94	0.00	22:37	0.60	0.60	0.86	18.8	0.80	>20,000	1.7			
MPC-70	01/28/94	1.00	08:35	0.01	1.01	1.46	18.8	0.80	>20,000	1.7			
MPC-70	01/29/94	2.00	09:37	0.06	2.06	2.96	17.6	0.90	>20,000	1.8			
MPC-70	01/30/94	3.00	11:45	0.15	3.15	4.53	17.4	0.80	>20,000	1.1			
MPC-70	01/31/94	4.00	08:37	0.02	4.02	5.78	17.0	0.80	>20,000	1.8			
MPC-70	02/01/94	5.00	08:52	0.03	5.03	7.24	17.0	0.80	>20,000	1.5			
MPC-70	02/05/94	9.00	09:35	0.06	9.06	13.04	15.8	0.80	>20,000	1.2			
MPC-55	01/27/94	0.00	08:39	0.02	0.02	0.03	20.5	0.20	760	2.1	19.992636	0	0.000144
MPC-55	01/27/94	0.00	09:39	0.06	0.06	0.09	20.0	0.30	1,000	2.3	18.112805	13.05	
MPC-55	01/27/94	0.00	12:39	0.18	0.18	0.27	19.0	0.20	1,600	2.1			
MPC-55	01/27/94	0.00	22:41	0.60	0.60	0.87	20.0	0.70	3,600	2.3			
MPC-55	01/28/94	1.00	08:38	0.02	1.02	1.46	20.0	0.80	3,800	2.0			
MPC-55	01/29/94	2.00	09:40	0.06	2.06	2.97	19.5	0.90	3,600	1.7			
MPC-55	01/30/94	3.00	11:51	0.15	3.15	4.54	19.5	0.80	5,200	1.4			
MPC-55	01/31/94	4.00	08:40	0.02	4.02	5.79	19.1	1.00	6,600	1.1			
MPC-55	02/01/94	5.00	08:54	0.03	5.03	7.24	19.1	1.10	4,600	1.1			
MPC-55	02/05/94	9.00	09:41	0.06	9.06	13.05	18.0	1.50	6,600	1.2			

Respiration Test
Oxygen and Helium Concentrations
Site 27, MPA-55
Nellis AFB, Nevada




Respiration Test

Oxygen and Helium Concentrations

Site 27, MPB-70

Nellis AFB, Nevada




Respiration Test

Oxygen and Helium Concentrations

Site 27, MPC-70


Nellis AFB, Nevada



Respiration Test															
Site 28															
Nellis AFB, Nevada															
Monitoring Point	Date	Days Elapsed (frac. days)	Time	Hrs elapsed (fractional days)	Days Elapsed	Elapsed Time (min. x 1000)	O2%			Hydro-carbon	Helium	Comments	Trend of O2/ Time	New x-values	k
VW	01/30/94	0.00	08:58	0.03	0.03	0.04	19.1	2.40	13.200	2.7			19.066516	0	0.004338
VW	01/30/94	0.00	10:21	0.09	0.09	0.13	18.8	2.20	10.400	2.2			10.433596	1.99	
VW	01/30/94	0.00	14:20	0.25	0.25	0.37	16.8	2.60	14.200	2.2					
VW	01/30/94	0.00	20:01	0.49	0.49	0.71	15.8	2.30	10.400	1.9					
VW	01/31/94	1.00	06:51	-0.06	0.94	1.36	13.8	2.20	10.400	1.9					
VW	01/31/94	1.00	17:20	0.38	1.38	1.99	10.2	2.80	16.400	2.7					
VW	02/01/94	2.00	06:49	-0.06	1.94	2.80	8.4	3.00	18.000	2.5					
VW	02/01/94	2.00	16:55	0.36	2.36	3.40	7.0	3.60	>20,000	2.3					
VW	02/02/94	3.00	07:52	-0.02	2.98	4.30	6.8	4.00	>20,000	2.1					
VW	02/02/94	3.00	22:55	0.61	3.61	5.20	5.3	4.30	>20,000	2.5					
MPA-50	01/30/94	0.00	09:04	0.03	0.03	0.05	20.0	0.10	4.200	2.6			19.904756	0	0.004688
MPA-50	01/30/94	0.00	10:25	0.09	0.09	0.13	19.2	0.10	6.800	2.2			3.9202076	3.41	
MPA-50	01/30/94	0.00	14:25	0.26	0.26	0.37	17.7	0.10	6.800	0.4	Bag empty for Helium test.				
MPA-50	01/30/94	0.00	20:08	0.50	0.50	0.71	17.2	0.25	7.400	0.6	Possibly bad bag.				
MPA-50	01/31/94	1.00	06:56	-0.05	0.95	1.36	14.2	0.50	9.200	1.4					
MPA-50	01/31/94	1.00	17:25	0.38	1.38	1.99	9.0	0.60	17.000	2.1					
MPA-50	02/01/94	2.00	06:54	-0.06	1.94	2.80	6.3	0.70	19.600	2.0					
MPA-50	02/01/94	2.00	16:59	0.36	2.36	3.41	4.9	0.90	>20,000	2.0					
MPA-50	02/02/94	3.00	07:56	-0.01	2.99	4.30	3.7	1.00	>20,000	1.5					
MPA-50	02/02/94	3.00	23:03	0.62	3.62	5.21	2.8	1.10	>20,000	2.3					
MPA-40	01/30/94	0.00	09:07	0.04	0.04	0.05	18.4	4.10	3.000	2.3			17.938005	0	0.004329
MPA-40	01/30/94	0.00	10:28	0.09	0.09	0.13	17.0	6.20	5.000	1.8			11.963538	1.38	
MPA-40	01/30/94	0.00	14:28	0.26	0.26	0.37	16.0	7.30	6.800	1.6					
MPA-40	01/30/94	0.00	20:12	0.50	0.50	0.72	14.6	8.10	8.000	2.0					
MPA-40	01/31/94	1.00	07:09	-0.05	0.95	1.38	12.2	9.60	10.000	1.7					
MPA-40	01/31/94	1.00	17:28	0.38	1.38	1.99	12.9	9.10	9.200	1.6					
MPA-40	02/01/94	2.00	06:57	-0.05	1.95	2.80	12.0	9.80	10.000	1.5					
MPA-40	02/01/94	2.00	07:03	-0.05	1.95	2.81	11.9	9.70	10.200	1.4					
MPA-40	02/02/94	3.00	08:00	-0.01	2.99	4.31	11.2	9.90	8.800	1.3					
MPA-40	02/02/94	3.00	23:06	0.62	3.62	5.21	10.0	10.00	11.600	1.2					
MPB-60	01/30/94	0.00	09:15	0.04	0.04	0.06	20.2	0.20	5.600	2.2			20.76861	0	0.002961
MPB-60	01/30/94	0.00	10:34	0.10	0.10	0.14	20.2	0.20	7.200	1.5			12.447692	2.81	
MPB-60	01/30/94	0.00	14:33	0.26	0.26	0.38	20.0	0.50	12.600	1.7					
MPB-60	01/31/94	1.00	07:04	-0.05	0.95	1.37	17.0	0.95	>20,000	2.3					
MPB-60	01/31/94	1.00	17:33	0.39	1.39	2.00	15.1	1.00	>20,000	2.3					
MPB-60	02/01/94	2.00	07:03	-0.05	1.95	2.81	12.1	1.30	>20,000	1.9					
MPB-60	02/01/94	2.00	17:07	0.37	2.37	3.41	12.0	1.50	>20,000	1.9					
MPB-60	02/02/94	3.00	08:05	-0.01	2.99	4.31	12.8	1.80	>20,000	1.9					
MPB-60	02/02/94	3.00	23:13	0.62	3.62	5.22	12.1	2.00	>20,000	2.1					
MPC-40	01/30/94	0.00	09:36	0.06	0.06	0.08	20.3	0.20	2.600	2.6			20.797747	0	0.000875
MPC-40	01/30/94	0.00	10:37	0.10	0.10	0.14	20.3	0.08	4.40	2.3			16.231806	5.22	
MPC-40	01/30/94	0.00	14:36	0.27	0.27	0.38	20.3	0.15	5.20	2.2					
MPC-40	01/31/94	1.00	07:13	-0.04	0.96	1.38	20.1	0.10	1.400	2.6					
MPC-40	01/31/94	1.00	17:37	0.39	1.39	2.00	19.6	0.20	1.3.600	2.4					3.41

Respiration

Respiration Test
Oxygen and Helium Concentrations
Site 28, MPA-40
Nellis AFB, Nevada




Respiration Test														
Site 44														
Nellis AFB, Nevada														
Monitoring Point	Date	Days Elapsed (frac. days)	Hrs elapsed (fractional days)	Days Elapsed	Elapsed Time (min. x 1000)	O2%	CO2%	Hydro-carbon	Total	Helium	Comments	Trend of O2/ Time	New x-values k	
VW	02/01/94	0.00	10:05	0.08	0.08	0.11	19.9	0.50	2,400	2.6	Begin Respiration Test.	20.614659	0	0.008158
VW	02/01/94	0.00	11:07	0.12	0.12	0.17	19.4	0.60	3,200	3.0		13.84376	0.83	
VW	02/01/94	0.00	14:09	0.25	0.25	0.36	17.2	0.90	4,000	3.0				
VW	02/01/94	0.00	16:06	0.33	0.33	0.47	16.7	1.00	4,000	2.6				
VW	02/01/94	0.00	18:06	0.41	0.41	0.59	15.8	1.20	4,000	2.7				
VW	02/01/94	0.00	22:07	0.58	0.58	0.83	14.0	1.70	4,200	3.1				
VW	02/02/94	1.00	08:07	0.00	1.00	1.43	12.6	2.20	4,000	2.3				
VW	02/02/94	1.00	22:17	0.59	1.59	2.28	11.0	2.60	5,800	2.9				
VW	02/03/94	2.00	16:46	0.36	2.36	3.39	9.3	3.30	6,400	2.5				
VW	02/04/94	3.00	12:51	0.19	3.19	4.60	8.3	4.00	6,400	2.8				
MPA-32	02/01/94	0.00	10:08	0.08	0.08	0.11	20.2	0.15	13,200	2.6		20.536044	0	0.004951
MPA-32	02/01/94	0.00	11:09	0.12	0.12	0.18	19.8	0.20	2,600	2.7		13.703724	1.38	
MPA-32	02/01/94	0.00	14:11	0.25	0.25	0.36	19.0	0.50	4,200	2.5				
MPA-32	02/01/94	0.00	16:10	0.33	0.33	0.48	18.0	0.70	4,800	2.8				
MPA-32	02/01/94	0.00	18:09	0.41	0.41	0.60	17.2	0.70	5,000	2.7				
MPA-32	02/01/94	0.00	22:10	0.58	0.58	0.84	16.0	0.80	4,800	2.4				
MPA-32	02/02/94	1.00	07:10	-0.04	0.96	1.38	14.1	0.85	4,600	2.8				
MPA-32	02/02/94	1.00	22:19	0.59	1.59	2.29	11.5	1.00	5,600	2.7				
MPA-32	02/03/94	2.00	16:50	0.36	2.36	3.40	8.7	1.50	6,400	2.9				
MPA-32	02/04/94	3.00	12:54	0.19	3.19	4.60	6.3	2.00	6,400	3.0				
MPA-24	02/01/94	0.00	10:09	0.08	0.08	0.12	19.0	5.90	6,400	3.0		19.498124	0	0.004788
MPA-24	02/01/94	0.00	11:12	0.12	0.12	0.18	18.5	5.90	6,000	2.8		12.891311	1.38	
MPA-24	02/01/94	0.00	14:13	0.25	0.25	0.36	18.2	6.00	6,000	2.7				
MPA-24	02/01/94	0.00	16:12	0.33	0.33	0.48	17.2	6.00	6,000	2.6				
MPA-24	02/01/94	0.00	18:12	0.42	0.42	0.60	16.5	6.00	5,200	2.6				
MPA-24	02/01/94	0.00	22:13	0.58	0.58	0.84	15.1	6.00	4,600	2.9				
MPA-24	02/02/94	1.00	07:12	-0.04	0.96	1.38	13.1	6.00	4,400	1.2	Bag almost empty.			
MPA-24	02/02/94	1.00	22:22	0.59	1.59	2.29	10.6	6.00	5,600	3.1				
MPA-24	02/03/94	2.00	16:52	0.36	2.36	3.40	8.3	6.20	6,000	2.3				
MPA-24	02/04/94	3.00	12:57	0.20	3.20	4.60	7.2	6.40	5,200	2.2				
MPB-39	02/01/94	0.00	10:12	0.08	0.08	0.12	18.3	0.15	1,900	2.3		19.764735	0	0.022065
MPB-39	02/01/94	0.00	11:14	0.13	0.13	0.18	15.5	0.20	3,600	2.8		6.5258231	0.6	
MPB-39	02/01/94	0.00	12:14	0.17	0.17	0.24	13.9	0.40	4,400	3.0				
MPB-39	02/01/94	0.00	14:15	0.25	0.25	0.36	11.0	0.50	5,400	2.2				
MPB-39	02/01/94	0.00	16:15	0.33	0.33	0.48	8.9	0.60	6,200	3.0				
MPB-39	02/01/94	0.00	18:14	0.42	0.42	0.60	7.3	0.70	6,600	3.0				
MPB-39	02/01/94	0.00	22:16	0.58	0.58	0.84	5.3	0.80	6,800	3.1				
MPB-39	02/02/94	1.00	07:16	-0.04	0.96	1.38	3.5	0.80	7,400	1.2	Bag almost empty.			
MPB-32	02/01/94	0.00	10:15	0.08	0.08	0.12	18.1	0.40	3,000	2.9		22.899696	0	0.03888
MPB-32	02/01/94	0.00	11:16	0.13	0.13	0.18	15.6	0.60	4,000	2.9		8.9749025	0.36	
MPB-32	02/01/94	0.00	12:18	0.17	0.17	0.24	14.1	0.90	4,800	2.6				
MPB-32	02/01/94	0.00	14:17	0.25	0.25	0.36	8.6	1.10	5,600	3.1				
MPB-32	02/01/94	0.00	18:17	0.42	0.42	0.60	6.9	1.40	5,600	3.0				
MPB-32	02/01/94	0.00	22:20	0.59	0.59	0.85	4.8	1.70	5,200	3.0				


[illegible]

MPC-39	02/01/94	0.00	10:20	0.09	0.09	0.13	13.1	1.50	11,200	2.7	16,564,341	0	0.033539
MPC-39	02/01/94	0.00	11:20	0.13	0.13	0.19	9.8	2.60	11,400	3.2	4,154,811	0.37	
MPC-39	02/01/94	0.00	12:22	0.17	0.17	0.25	7.5	3.20	12,000	3.0			
MPC-39	02/01/94	0.00	14:20	0.25	0.25	0.37	4.8	3.60	12,400	2.8			
MPC-39	02/01/94	0.00	16:20	0.34	0.34	0.49	3.1	4.10	12,400	2.9			
MPC-39	02/01/94	0.00	18:20	0.42	0.42	0.61	2.6	4.50	11,600	2.9			
MPC-32	02/01/94	0.00	10:23	0.09	0.09	0.13	14.1	3.70	8,400	2.2	17,580,384	0	0.034318
MPC-32	02/01/94	0.00	11:22	0.13	0.13	0.19	10.4	4.10	10,800	2.9	4,882,783	0.37	
MPC-32	02/01/94	0.00	12:24	0.17	0.17	0.25	8.2	4.50	12,000	2.9			
MPC-32	02/01/94	0.00	14:23	0.26	0.26	0.37	5.5	5.00	12,000	2.7			
MPC-32	02/01/94	0.00	16:23	0.34	0.34	0.49	4.0	5.10	11,800	2.9			
MPC-32	02/01/94	0.00	18:23	0.42	0.42	0.61	3.1	5.10	11,200	1.9	Bag empty for Helium test.		
MPC-24	02/01/94	0.00	10:26	0.09	0.09	0.13	18.3	0.09	440	2.5	20,399,212	0	0.020398
MPC-24	02/01/94	0.00	11:25	0.13	0.13	0.19	16.3	0.10	1,720	2.4	7,956,5002	0.61	
MPC-24	02/01/94	0.00	12:27	0.18	0.18	0.25	14.9	0.15	1,400	2.6			
MPC-24	02/01/94	0.00	14:25	0.26	0.26	0.37	12.6	0.15	1,840	2.7			
MPC-24	02/01/94	0.00	16:25	0.34	0.34	0.49	10.2	0.20	2,000	3.0			
MPC-24	02/01/94	0.00	18:25	0.42	0.42	0.61	8.3	0.15	2,400	2.9			
MPC-24	02/01/94	0.00	22:24	0.59	0.59	0.85	6.4	0.20	2,600	1.8	Out of sample on Helium test.		
MPC-24	02/02/94	1.00	07:22	-0.04	0.95	1.39	2.6	0.30	2,800	3.0			

Respiration Test Oxygen and Helium Concentrations Site 44, MPA-24 Nellis AFB, Nevada



Respiration Test
Oxygen and Helium Concentrations
Site 44, MPB-32
Nellis AFB, Nevada



NELLIS AFB - SITE 27

Biodegradation Rate Calculations

enter data

calculated data

Formula: $K_b = K_o \times 1/100\% \times A \times D_o \times C$ Where:

K_b = fuel biodegradation rate

K_o = O_2 utilization rate (%/min.)

A = volume of air/kg soil

D_o = O_2 density 1340 mg/L

C = Carbon/ O_2 ratio for hexane mineralization = 1/3.5

Test Results:

MPC-55

K_o = max. observed rate

0.000144

%/min.

w = moisture content

15.0

%

Assume:

Soil properties for silty clay

Specify from

Table 1.4 (Ref. Foundation Engineering, Peck, Hanson, and Thornburn, John Wiley Press, 1974)

Porosity:

$n = 0.45$

Unit weight (dry):

$\gamma_d = 1.43$

Void ratio:

$e = n/1-n = 0.82$

Specific gravity:

$G = 2.65$

Calculate A = Air filled volume (V_a)/unit wt.

Solving for 1 liter of soil

a) $V_v = n \times 1 \text{ L}$

$V_v = 0.45$ liters

V_v = void volume

b) $S_r = Gw/e$

$S_r = 0.48$

S_r = degree of saturation

c) $V_w = S_r \times V_v$

$V_w = 0.22$ liters

V_w = volume of water

d) $V_a = V_v - V_w$

$V_a = 0.23$ liters

V_w = volume of water

e) Bulk density = $\gamma_d + (V_w \times \gamma_w) = 1.7$ kg/l soil

f) $A = V_a/\text{Bulk density} = 0.135$ l air/kg soil

$K_b = K_o \times 1/100\% \times A \times D_o \times C \times 525,600 \text{ min/yr} = 40$ mg TPH/year

SITE: _____

[illegible]

NELLIS AFB - SITE 27

Biodegradation Rate Calculations

enter data

calculated data

Formula: $K_b = K_o \times 1/100\% \times A \times D_o \times C$ Where:

K_b = fuel biodegradation rate

K_o = O_2 utilization rate (%/min.)

A = volume of air/kg soil

D_o = O_2 density 1340 mg/L

C = Carbon/ O_2 ratio for hexane mineralization = 1/3.5

Test Results:

MPB-55

K_o = max. observed rate

0.000535

%/min.

w = moisture content

15.0

%

Assume:

Soil properties for silty clay

Specify from

Table 1.4 (Ref. Foundation Engineering, Peck, Hanson, and Thornburn, John Wiley Press, 1974)

Porosity:

n = 0.45

Unit weight (dry):

g_d = 1.43

Void ratio:

$e = n/1-n$ = 0.82

Specific gravity:

G = 2.65

Calculate A = Air filled volume (V_a)/unit wt.

Solving for 1 liter of soil

a) $V_v = n \times 1 \text{ L}$

V_v = 0.45 liters

V_v = void volume

b) $S_r = Gw/e$

S_r = 0.48

S_r = degree of saturation

c) $V_w = S_r \times V_v$

V_w = 0.22 liters

V_w = volume of water

d) $V_a = V_v - V_{vw}$

V_a = 0.23 liters

V_w = volume of water

e) Bulk density = $g_d + (V_w \times g_w)$ = 1.7 kg/l soil

f) $A = V_a/\text{Bulk density}$ = 0.135 l air/kg soil

$K_b = K_o \times 1/100\% \times A \times D_o \times C \times 525,600 \text{ min/yr}$ = 150 mg TPH/year

NELLIS AFB - SITE 28

Biodegradation Rate Calculations

enter data

calculated data

Formula: $K_b = K_o \times 1/100\% \times A \times D_o \times C$ Where:

K_b = fuel biodegradation rate

K_o = O_2 utilization rate (%/min.)

A = volume of air/kg soil

D_o = O_2 density 1340 mg/L

C = Carbon/ O_2 ratio for hexane mineralization = 1/3.5

Test Results:

MPA-50

K_o = max. observed rate

0.004688

%/min.

w = moisture content

16.0

%

Assume:

Soil properties for silty clay

Specify from

Table 1.4 (Ref. Foundation Engineering, Peck, Hanson, and Thornburn, John Wiley Press, 1974)

Porosity:

n = 0.45

Unit weight (dry):

γ_d = 1.43

Void ratio:

$e = n/1-n$ = 0.82

Specific gravity:

G = 2.65

Calculate A = Air filled volume (V_a)/unit wt.

Solving for 1 liter of soil

a) $V_v = n \times 1 \text{ L}$

V_v = 0.45 liters

V_v = void volume

b) $S_r = Gw/e$

S_r = 0.52

S_r = degree of saturation

c) $V_w = S_r \times V_v$

V_w = 0.23 liters

V_w = volume of water

d) $V_a = V_v - V_{vw}$

V_a = 0.22 liters

V_w = volume of water

e) Bulk density = $\gamma_d + (V_w \times \gamma_w) =$ 1.7 kg/l soil

f) $A = V_a/\text{Bulk density} =$ / 0.129 l air/kg soil

$K_b = K_o \times 1/100\% \times A \times D_o \times C \times 525,600 \text{ min/yr} =$ 1220 mg TPH/year

NELLIS AFB - SITE 28

Biodegradation Rate Calculations

enter data

calculated data

Formula: $K_b = K_o \times 1/100\% \times A \times D_o \times C$ Where:

K_b = fuel biodegradation rate

K_o = O_2 utilization rate (%/min.)

A = volume of air/kg soil

D_o = O_2 density 1340 mg/L

C = Carbon/ O_2 ratio for hexane mineralization = 1/3.5

Test Results:

MPC-40

K_o = max. observed rate

0.000875

%/min.

w = moisture content

26.0

%

Assume:

Soil properties for silt and sand

Specify from

Table 1.4 (Ref. Foundation Engineering, Peck, Hanson, and Thornburn, John Wiley Press, 1974)

Porosity:

n = 0.45

Unit weight (dry):

γ_d = 1.43

Void ratio:

$e = n/1-n$ = 0.82

Specific gravity:

G = 2.65

Calculate A = Air filled volume (V_a)/unit wt.

Solving for 1 liter of soil

a) $V_v = n \times 1 \text{ L}$

V_v = 0.45 liters

V_v = void volume

b) $S_r = Gw/e$

S_r = 0.84

S_r = degree of saturation

c) $V_w = S_r \times V_v$

V_w = 0.38 liters

V_w = volume of water

d) $V_a = V_v - V_{vw}$

V_a = 0.07 liters

V_w = volume of water

e) Bulk density = $\gamma_d + (V_w \times \gamma_w) =$

1.8

kg/l soil

f) $A = V_a/\text{Bulk density} =$

0.039

l air/kg soil

$K_b = K_o \times 1/100\% \times A \times D_o \times C \times 525,600 \text{ min/yr} =$

70

mg TPH/year

NELLIS AFB - SITE 44

Biodegradation Rate Calculations

enter data

calculated data

Formula: $K_b = K_o \times 1/100\% \times A \times D_o \times C$ Where:

K_b = fuel biodegradation rate

K_o = O_2 utilization rate (%/min.)

A = volume of air/kg soil

D_o = O_2 density 1340 mg/L

C = Carbon/ O_2 ratio for hexane mineralization = 1/3.5

Test Results:

VW

K_o = max. observed rate

0.002465

%/min.

w = moisture content

20.0

%

Assume:

Soil properties for silty clay

Specify from

Table 1.4 (Ref. Foundation Engineering, Peck, Hanson, and Thornburn, John Wiley Press, 1974)

Porosity:

n = 0.45

Unit weight (dry):

g_d = 1.43

Void ratio:

$e = n/1-n$ = 0.82

Specific gravity:

G = 2.65

Calculate A = Air filled volume (V_a)/unit wt.

Solving for 1 liter of soil

a) $V_v = n \times 1 \text{ L}$

V_v = 0.45 liters

V_v = void volume

b) $S_r = Gw/e$

S_r = 0.65

S_r = degree of saturation

c) $V_w = S_r \times V_v$

V_w = 0.29 liters

V_w = volume of water

d) $V_a = V_v - V_{vw}$

V_a = 0.16 liters

V_w = volume of water

e) Bulk density = $g_d + (V_w \times g_w)$ = 1.7 kg/l soil

f) $A = V_a/\text{Bulk density}$ = 0.094 l air/kg soil

$K_b = K_o \times 1/100\% \times A \times D_o \times C \times 525,600 \text{ min/yr}$ = 470 mg TPH/year

NELLIS AFB - SITE 44

Biodegradation Rate Calculations

enter data

calculated data

Formula: $K_b = K_o \times 1/100\% \times A \times D_o \times C$ Where:

K_b = fuel biodegradation rate

K_o = O_2 utilization rate (%/min.)

A = volume of air/kg soil

D_o = O_2 density 1340 mg/L

C = Carbon/ O_2 ratio for hexane mineralization = 1/3.5

Test Results: MPC-32 K_o = max. observed rate 0.021384 %/min.
 w = moisture content 10.5 %

Assume: Soil properties for silty clay Specify from
 Table 1.4 (Ref. Foundation Engineering, Peck, Hanson, and Thornburn,
 John Wiley Press, 1974)

Porosity: $n = 0.40$
 Unit weight (dry): $g_d = 1.43$
 Void ratio: $e = n/1-n = 0.67$
 Specific gravity: $G = 2.65$

Calculate A = Air filled volume (V_a)/unit wt.

Solving for 1 liter of soil

a) $V_v = n \times 1 \text{ L}$
 $V_v = 0.4$ liters V_v = void volume

b) $S_r = Gw/e$
 $S_r = 0.42$ S_r = degree of saturation

c) $V_w = S_r \times V_v$
 $V_w = 0.17$ liters V_w = volume of water

d) $V_a = V_v - V_{vw}$
 $V_a = 0.23$ liters V_w = volume of water

e) Bulk density = $g_d + (V_w \times g_w) = 1.6$ kg/l soil

f) $A = V_a/\text{Bulk density} = 0.144$ l air/kg soil

$K_b = K_o \times 1/100\% \times A \times D_o \times C \times 525,600 \text{ min/yr} = 6200$ mg TPH/year

NELLIS AFB – Site 27 Steady–state Equation – Air Injection

Enter data

Calculated data

$$k = \frac{Q \mu \ln (R_w / R_i)}{H \pi P_{atm} [1 - (P_w / P_{atm})^2]}$$

Where:

Q = Volumetric flow rate of vent well

$$36.0 \text{ scfm} \times (30.48 \text{ cm/ft})^3 \times (1 \text{ min}/60 \text{ s}) = 1.70\text{E}+04 \text{ cm}^3/\text{s}$$

$$\mu = \text{Viscosity of Air @ } 18^\circ \text{ C} = 1.80\text{E}-04 \text{ g/cm s}$$

P_{atm} = Ambient pressure @ 3200 feet of elevation

$$364 \text{ inches H}_2\text{O} \times (3.61\text{E}-2 \text{ psia/in. H}_2\text{O}) = 13.140 \text{ psia}$$

$$13.140 \text{ psia} \times (6.89476\text{E}4 \text{ g/cm s}^2)/\text{psia} = 9.06\text{E}+05 \text{ g/cm s}^2$$

R_w = Radius of Vent Well

$$2 \text{ inches} \times 2.54 \text{ cm/in} = 5.08 \text{ cm}$$

H = Depth of Screen (length of screened interval)

$$25 \text{ feet} \times 30.48 \text{ cm/ft} = 762 \text{ cm}$$

R_i = Maximum Radius of Venting Influence

$$45 \text{ feet} \times 30.48 \text{ cm/ft} = 1372 \text{ cm}$$

P_w = Absolute Pressure at Vent Well

$$46 \text{ inches H}_2\text{O} \times (3.61\text{E}-2 \text{ psia/in. H}_2\text{O}) = 1.661 \text{ psia}$$

$$1.661 \text{ psia} + 13.140 \text{ psia} = 14.801 \text{ psia}$$

$$14.801 \text{ psia} \times (6.89476\text{E}4 \text{ g/cm s}^2)/\text{psia} = 1.02\text{E}+06 \text{ g/cm s}^2$$

$$k = 2.938\text{E}-08 \text{ cm}^2$$

$$2.940\text{E}-08 \text{ cm}^2 \times (1 \text{ m}/100 \text{ cm})^2 = 2.900\text{E}-12 \text{ m}^2$$

$$2.900\text{E}-12 \text{ m}^2 \times 1 \text{ darcy}/(9.870\text{E}-13 \text{ m}^2) = 2.94 \text{ darcys}$$

NELLIS AFB – Site 28
Steady-state Equation – Air Injection

Enter data

Calculated data

$$k = \frac{Q \mu \ln(R_w / R_i)}{H \pi P_{atm} [1 - (P_w / P_{atm})^2]}$$

Where:

Q = Volumetric flow rate of vent well

$$\boxed{32.5} \text{ scfm} \times (30.48 \text{ cm/ft})^3 \times (1 \text{ min}/60 \text{ s}) = \boxed{1.53\text{E}+04} \text{ cm}^3/\text{s}$$

$$\mu = \text{Viscosity of Air @ } 18^\circ \text{ C} = \boxed{1.80\text{E}-04} \text{ g/cm s}$$

P_{atm} = Ambient pressure @ 3200 feet of elevation

$$\boxed{364} \text{ inches H}_2\text{O} \times (3.61\text{E}-2 \text{ psia/in. H}_2\text{O}) = \boxed{13.140} \text{ psia}$$

$$\boxed{13.140} \text{ psia} \times (6.89476\text{E}4 \text{ g/cm s}^2)/\text{psia} = \boxed{9.06\text{E}+05} \text{ g/cm s}^2$$

R_w = Radius of Vent Well

$$\boxed{2} \text{ inches} \times 2.54 \text{ cm/in} = \boxed{5.08} \text{ cm}$$

H = Depth of Screen (length of screened interval)

$$\boxed{35} \text{ feet} \times 30.48 \text{ cm/ft} = \boxed{1067} \text{ cm}$$

R_i = Maximum Radius of Venting Influence

$$\boxed{56} \text{ feet} \times 30.48 \text{ cm/ft} = \boxed{1707} \text{ cm}$$

P_w = Absolute Pressure at Vent Well

$$\boxed{83.1} \text{ inches H}_2\text{O} \times (3.61\text{E}-2 \text{ psia/in. H}_2\text{O}) = \boxed{3.000} \text{ psia}$$

$$\boxed{3.000} \text{ psia} + \boxed{13.140} \text{ psia} = \boxed{16.140} \text{ psia}$$

$$\boxed{16.140} \text{ psia} \times (6.89476\text{E}4 \text{ g/cm s}^2)/\text{psia} = \boxed{1.11\text{E}+06} \text{ g/cm s}^2$$

$$k = \boxed{1.040\text{E}-08} \text{ cm}^2$$

$$\boxed{1.040\text{E}-08} \text{ cm}^2 \times (1 \text{ m}/100 \text{ cm})^2 = \boxed{1.000\text{E}-12} \text{ m}^2$$

$$\boxed{1.000\text{E}-12} \text{ m}^2 \times 1 \text{ darcy}/(9.870\text{E}-13 \text{ m}^2) = \boxed{1.01} \text{ darcys}$$

NELLIS AFB – Site 44
Steady-state Equation – Air Injection

Enter data

Calculated data

$$k = \frac{Q \mu \ln (R_w / R_i)}{H \pi P_{atm} [1 - (P_w / P_{atm})^2]}$$

Where:

Q = Volumetric flow rate of vent well

$$36.0 \text{ scfm} \times (30.48 \text{ cm/ft})^3 \times (1 \text{ min}/60 \text{ s}) = 1.70\text{E}+04 \text{ cm}^3/\text{s}$$

$$\mu = \text{Viscosity of Air @ } 18^\circ \text{ C} = 1.80\text{E}-04 \text{ g/cm s}$$

P_{atm} = Ambient pressure @ 3200 feet of elevation

$$364 \text{ inches H}_2\text{O} \times (3.61\text{E}-2 \text{ psia/in. H}_2\text{O}) = 13.140 \text{ psia}$$

$$13.140 \text{ psia} \times (6.89476\text{E}4 \text{ g/cm s}^2)/\text{psia} = 9.06\text{E}+05 \text{ g/cm s}^2$$

R_w = Radius of Vent Well

$$2 \text{ inches} \times 2.54 \text{ cm/in} = 5.08 \text{ cm}$$

H = Depth of Screen (length of screened interval)

$$25 \text{ feet} \times 30.48 \text{ cm/ft} = 762 \text{ cm}$$

R_i = Maximum Radius of Venting Influence

$$35 \text{ feet} \times 30.48 \text{ cm/ft} = 1067 \text{ cm}$$

P_w = Absolute Pressure at Vent Well

$$45 \text{ inches H}_2\text{O} \times (3.61\text{E}-2 \text{ psia/in. H}_2\text{O}) = 1.625 \text{ psia}$$

$$1.625 \text{ psia} + 13.140 \text{ psia} = 14.765 \text{ psia}$$

$$14.765 \text{ psia} \times (6.89476\text{E}4 \text{ g/cm s}^2)/\text{psia} = 1.02\text{E}+06 \text{ g/cm s}^2$$

$$k = 2.872\text{E}-08 \text{ cm}^2$$

$$2.870\text{E}-08 \text{ cm}^2 \times (1 \text{ m}/100 \text{ cm})^2 = 2.900\text{E}-12 \text{ m}^2$$

$$2.900\text{E}-12 \text{ m}^2 \times 1 \text{ darcy}/(9.870\text{E}-13 \text{ m}^2) = 2.94 \text{ darcys}$$

APPENDIX B
O&M CHECKLIST

FILE: _____

[illegible]